AVIATION WEEK

A McGRAW-HILL PUBLICATION

APR. 24, 1950



Grumman

The Grumman MALLARD

When the forces of nature conspire to defeat ordinary means of travel, the need for transportation is always most desperate. At such times the Grumman MALLARD demonstrates its unique abilities. As the only executive aircraft to combine the speed of a land plane with the versatility of an amphibian, the MALLARD is depended upon by individuals, agencies and corporations for swift transportation to places where things are happening.

GRUMMAN AIRCRAFT ENGINEERING CORPORATION, BETHPAGE.

LET

EX-CELL-O

MAKE IT



Precision parts and sub-assemblies, made to customers' specifications, are an Ex-Cell-O specialty. Typical of Ex-Cell-O's products for the aircraft industry are the precision parts (at left) and hydraulic assemblies (above) shown on this page. Ex-Cell-O has complete engineering, machining, heat-treating, grinding, sub-assembling, and inspection facilities— all under one competent, experienced management. Ex-Cell-O makes precision parts to your specifications, in small or large volume, and delivers them in accordance with your schedule. To see how this service can benefit you, write Ex-Cell-O in Detroit today.

EX-CELL-O CORPORATION DETROIT 32

Special Multiple Way Type Precision Boring Machines • Special Multiple Precision Drilling Machines • Precision Boring, Turning, and Facing Machines and Fixtures • Precision Cylinder Boring Machines • Precision Thread Grinding Machines • Precision Lapping Machines • Precision Broach Sharpening Machines • Other Special Purpose Machines • Tool Grinders • Continental Cutting Tools • Broaches and Broach Fixtures • Counterbore Sets • Grinding Spindles • Hydraulic Power Units • Drill Jig Bushings • R. R. Pins and Bushings • Fuel Injection Equipment • Dairy Equipment • Aircraft and Miscellaneous Production Parts

49-S



The pipe that flies like a plane

THE strange looking device on the rail of this plane is the Flying Boom. It's a new telescoping pipe for inflight refueling, developed by Boeing

The vee shaped vanes on this pipe—called 'ruddevators — are airplane-like controls used to actually *fly* the pipe into position for refueling And like the control surfaces of a plane, these ruddevators have to be accurate at any altitude in any weather Which means, of course, they have to be protected against ice

Looking for the best answer to the icing problem, Boeing turned to B F Goodrich BFG engineers recommended electric rubber—a B F Goodrich development that is the most efficient method of supplying spot anti-icing heat

Pads of B F Goodrich electrically heated rubber are bonded to the leading edges of the ruddevators. They provide plenty of heat to prevent ice formation, permit accurate control of the Flying Boom.

The simplicity and efficiency of B F Goodrich electric rubber makes it ideal for this job It's made of thin, tough rubber with a core of resistance wires that distribute the heat as needed It's light weight and very flexible A pair of lead wires to carry the current is the only other equipment used

B F Goodrich electric rubber is also doing a successful anti-icing job on airplane wings, propellers, air intakes, jet cowls, hydraulic lines, water tanks and many other aircraft parts. Get a recommendation for your application from BFG engineers. Write to *The B F Goodrich Company, Aeronautical Division, Akron, Ohio*

B.F.Goodrich

FIRST IN RUBBER


Auburn

Short-type threaded

JET IGNITOR

Spark Plugs

With high altitude shield



Designed and made in any size to meet your needs.

Plug shown is actual size.

Also makers of flange-type jet ignitor spark plugs.

Let us figure on your particular needs.

Five years of specializing in turbo-jet, jet prop and rocket spark plugs and ignition parts. Makers of

- Quick-action Thermocouples
- Thermocouple Spark Plugs
- Glow Plugs
- Tail-burning Ignitors
- Aircraft Spark Plug Connectors
- Neoprene Terminal Collars

AUBURN
SPARK PLUG CO., INC.
AUBURN, N. Y.

Aircraft Division
1180 Raymond Blvd., Newark 2, N. J.

Export Office
120 W. 42nd St., New York 18, N. Y.

In Canada

Railway & Power Engineering Corp., Ltd.
Montreal • Noranda • North Bay • Toronto
Hamilton • Windsor • Winnipeg
Sydney, Nova Scotia • Vancouver

Aviation Week

Volume 52 **April 24, 1950** **Number 17**

Headline News

Missile Program Under Fire ... 12
Missile Motors Work Gets Results ... 13
Aircraft Fabrication Revolution? ... 15
Political Gifts ... 16
To Aircraft Industry Salaries ... 17

Aviation Sales & Service

New Super Cubs Display Utility ... 18

Financial

How Past Taxes Affect Earnings ... 21

Aeronautical Engineering

Long Range Transport Power Study ... 23
Temperature Data on Plastics ... 36

Avionics

Computer 'Flies' Aircraft Designs ... 43

Air Force Contracts

February Awards Top $70 Million ... 46

Air Transport

Damon Patterson Top Salary List ... 54
Jets No Traffic Control Problem ... 56
Tide Turns From East To West ... 57

Editorial

20 Years—No Crash! ... 66

Departments

News Sidelights ... 7
Aviation Calendar ... 8
News Digest ... 9
Who's Where ... 11
Letters ... 64
Industry Observer ... 11
New Aviation Products ... 44
Shortlines ... 60
CAB Schedule ... 61

Robert H. Wood
EDITOR

Merlin H. Mickel — MANAGING EDITOR

William Kroger — Assistant Managing Editor
Irving Stone — Technical Editor
Alexander McSurely — Manufacturing Editor
Charles L. Adams — Transport Editor
Ben Lee — Military
G. L. Christian, III — Maintenance & Equipment
Henry Lefer — Editorial Makeup
Katherine Johnsen — Congress
Thomas M. Self — West Coast
Marie Adams — Editorial Assistant
Scott H. Reinager — Editorial Assistant
Victoria Giaculli — Editorial Assistant
Erwin J. Bulban — Editorial Assistant

Executive and Editorial Offices: 330 West 42nd St., New York 18, N. Y. Phone Longacre 4-3035; National Press Bldg., Washington 4, D. C., Phone National 3414.

Domestic News Bureaus: Atlanta 3, Rhodes-Haverty Bldg.; Chicago 11, 520 N. Michigan Ave.; Cleveland 15, Hanna Bldg.; Detroit 26, Penobscot Bldg.; Los Angeles 14, 621 S. Hope St.; San Francisco 4, 68 Post St.; Houston, 514 South St. *Correspondents* in more than 60 major cities.

Foreign News Bureaus: London, Paris, Frankfurt, Tokyo, Bombay, Melbourne, Rio de Janeiro, Mexico City. *Correspondents* in more than 50 major cities.

Robert F. Boger
PUBLISHER

J. G. Johnson, *Business Manager*; R. W. Martin, Jr., *Sales Manager*, Sales Representatives: J. C. Anthony, New York; M. J. Storz, Philadelphia; V. K. Dissette, Cleveland; L. J. Biehl, Chicago; W. E. Donnell, St. Louis; J. H. Allen, Dallas; R. C. Maultsby, Atlanta; J. W. Otterson, San Francisco; C. F. McReynolds, Los Angeles. Other sales offices in Pittsburgh, Detroit, Boston, London.

Anita Scaffo, *Research and Marketing*

Member of Associated Business Publications, Inc., and the Audit Bureau of Circulations

Aviation Week — April 24, 1950 — Vol. 52, No. 17

McGRAW-HILL PUBLISHING CO., Inc.; James H. McGraw (1860-1948), Founder. Publication office—99-129 N. Broadway, Albany, N. Y. CURTIS W. McGRAW, President; WILLARD CHEVALIER, Executive Vice-President; JOSEPH A. GERARDI, Secretary and Treasurer; PAUL MONTGOMERY, Senior Vice-President. Publications Division: NELSON BOND, Vice President and Director of Advertising; J. F. BLACKBURN, Jr., Vice-President and Director of Circulation. Published Weekly in U. S. A. price 35¢ a copy; 50¢ in Canada. subscription rates—United States and possessions, $6 a year; $9 for 1½ yr., $12 for 2 yr. Canada, $8 for 1 yr., $12 for 2 yr., $16 for 3 yr., payable in Canadian currency at par. Pan American countries, $16 for 1 yr., $18 for 1½ yr., $20 for 2 yr. All other countries, $20 for 1 yr., $30 for 2 yr., $40 for 3 yr. Address all communications about subscriptions to 99-129 N. Broadway, Albany 1, N. Y., or Director of Circulation, 330 W. 42nd St., New York 18, N. Y. Please indicate position and company connection on all subscription orders. Allow at least ten days for change of address. Entered as second class matter, June 16, 1947, at Post Office, Albany 1, N. Y., under Act of March 3, 1879. Copyright 1950, McGraw-Hill Publishing Co. Cable address: McGraw-Hill, New York. Publications combined with: AVIATION WEEK are AVIATION, AVIATION NEWS, AIR TRANSPORT, AERONAUTICAL ENGINEERING AND AIRCRAFT JOURNAL. All rights to these names are reserved by McGraw-Hill Publishing Co.

Hamilton-Standard

18 YEARS

FAFNIR

To Hamilton-Standard Division (United Aircraft Corp.) must go a large measure of credit for the aircraft progress contributed by propeller improvements. It's been Fafnir's privilege to work closely with Hamilton-Standard almost from the beginning . . . about eighteen years. There's a good reason for this mutually satisfying partnership. That reason is an attitude and an aptitude . . . a way of looking at anti-friction bearings from the designer's side, an aptitude gained from more than twenty years' specialization in aircraft ball bearings. Write for new catalog. The Fafnir Bearing Company, New Britain, Connecticut.

Fafnir thrust bearing for propeller blades, developed for Hamilton-Standard to handle the thousands of pounds of centrifugal load imposed upon the blades of controllable pitch propellers





AIRCRAFT LANDING GEAR COMPONENT

An outstanding example of forging technique—the piercing operation in the case of this 276-lb. alloy steel forging results in a weight saving of approximately 30 per cent in addition to an improved metallurgical structure.

For the greatest combination of physical properties (tensile and compressive strength, ductility, impact and fatigue strength) with minimum weight and uniform quality no other method of forming metal compares with the forging process.

In lerge and madium-size forgings of staal and light alloy—thare is no substitute for Wymen-Gordon experienca.

Standard of the Industry for More Than Sixty Years

WYMAN-GORDON

Forgings of Aluminum, Magnesium, Steel

WORCESTER, MASSACHUSETTS, U. S. A.

HARVEY, ILLINOIS - - - DETROIT, MICHIGAN

NEWS SIDELIGHTS

Runway Glow

First service test of phosphorescent white paint at a major terminal is being studied at Washington National Airport. Two dual stripes have been painted on runway 33, and pilots are being asked to comment on how well the lines show up. Reports have been favorable but indicate that a wider strip is desirable.

The narrow ones may be obliterated too soon by tire marks and oil smudges. One of the delays in the use of phosphorescent paint for runways has been the development of a "non skid" paint. If the present tests are satisfactory, look for an early repainting of all runway markings at other airports.

No. 3 Contributor

The aviation industry takes third place as the Democratic Party's financial godmother. A survey of 1949 political contributions showed that the party's heaviest contributor was the movie industry with donations totaling $68,000. The Democrats' second biggest windfall came from the liquor industry with contributions totaling $54,000. The aviation industry was in third place, with thirty, plus aviation executives and attorneys contributing $37,000. A careful check by AVIATION WEEK showed no contributions by aviation executives to the Republican Party last year. The GOP's biggest contributors were from banking, oil, mining, and metal manufacturing.

Arcata Demise

The Landing Aids Experiment station at Arcata, Calif., is now officially dead. Withdrawal of financial support by all interested agencies leaves the CAA experiment station at Indianapolis as the only one functioning at present. Airline Pilots Assn. and Air Transport Assn. want Cleveland Municipal and Newark Airports used as experiment stations. Both organizations have invested time and money at these places and feel they provide good practical test conditions. To date, CAA is definitely opposed to any shift from Indianapolis.

The government's Air Navigation Development Board recently explained why it could not sponsor continued operation of the Arcata station. It said that at least one high intensity approach lighting system adequate for the Radio Technical Commission for Aeronautics transition program installation is already in being, and no research and development is involved in the selection of the particular configuration to be used.

ANDB stated that at least one of Arcata's high intensity approach light systems can, in conjunction with transition program electronic aids, permit regular operations with ceiling and visibility minimums of 100 ft. and ½ mi. The board feels the value of any contribution that presently known types of visual aids can be expected to make in reducing minimums below 100 ft. and ½ mi. is highly questionable and does not warrant the large expenditures necessary to maintain the Arcata station.

Early Will Resign

Stephen T. Early is expected to resign his post as Deputy Secretary of Defense August 1, 1950, to return to vice presidency of Pullman Company. According to close associates he will retire from Pullman Company activities December 1.

Impending reorganization of Defense Department Office of Public Information including a revision of mission and strengthening of its command functions through the mission revision will be the parting gesture of Mr. Early at steadying the still wobbling unified Department of Defense.

Office of Public Information reorganization is scheduled for announcement July 1.

MATS Cut Back

Defense Department's plans to reduce transport operations of the Military Air Transport Service by one-third are being received warmly in airline quarters.

Commercial carriers have long contended that MATS should only be a "nucleus" transport organization with emphasis on training—and shouldn't be allowed to compete with the airlines even for government business. Air Transport Assn. protested vigorously several months ago when MATS announced plans to reestablish regular service to South America. Sen. Edwin Johnson (D., Colo.) chairman of the Senate Commerce Committee, quoting an AVIATION WEEK story, later asked Maj. Gen. Laurence S. Kuter, MATS commander, for an explanation of the South American expansion.

Pressure from within the military also has been brought on MATS. Gen. Joseph T. McNarney, special assistant to the secretary of defense, told MATS to economize through consolidations. Further, Army Ground Forces have eyed MATS' airline operations sourly while pointing to their own lack of adequate tactical airlift support.

Even before disclosure of the proposed change in mission, MATS discontinued its "Statesman" transcontinental passenger flights, thereby throwing added business to the airlines.

Brewster Rankled

That Sen. Owen Brewster (R., Me.), former chairman of the Congressional Aviation Policy Board, still rankles at the vacillating attitude taken by the aircraft industry on the question of government support for air transport prototypes was made quite evident at a recent Washington meeting of the Institute of Aeronautical Sciences.


The meeting was programmed as a discussion about why the aviation industry wants government support for new transport prototypes and headlined Adm. DeWitt C. Ramsey, president of AIA. But when time came for discussion Sen. Brewster took the floor and in his best senatorial manner proceeded to tell the aircraft manufacturers off for their inability to make up their minds as to whether they did or did not want government support. The senator pointed out that after the congressional board went down the line for the aircraft companies at their insistent urging in testimony before it and plugged strongly for prototype financing that the industry had changed its tune. Opposition by the industry to prototype legislation he indicated was a large factor in killing chance for its passage in the last session of Congress. The senator seemed a little amazed at the temerity of the industry for once more asking for government prototype aid.

Adm. Ramsey, picking up the pieces after the Brewster remarks were completed, did not discuss the former various positions of the industry but pointed out again that the industry wants prototype federal support now and if it can't get anything better would like to have passage of the Air Coordinating Committee bill to finance a testing program for jet prototypes for $12 million.



The AVITRUC YC 122B

efficient



maximum visibility for crew • standardized controls and instrument panel • fast acting ramp and cargo door • ramp loading at truck bed height • cargo floor only 29 inches above ground level • ***result*** = reduced ground handling costs + fast, safe, economical air cargo transportation •

AVITRUC—designed for the job •

Chase AIRCRAFT CO., Inc.
WEST TRENTON, NEW JERSEY

AVIATION CALENDAR

Apr 27-28—Air traffic conference, sponsored by Air Traffic Conference of Air Transport Assn., Saxony Hotel, Miami Beach, Fla.

Apr 29-30—Fifth annual southeastern air show and exposition, Jacksonville, Fla.

May 3-4—15th National Aircraft Standards Committee national meeting, Aircraft Industries Assn. offices, Hollywood Roosevelt Hotel, Los Angeles, Calif.

May 3-5—Organization meeting for National Aviation Conference, Oklahoma City, Okla.

May 9-20—Fourth annual technical conference of the International Air Transport Assn., Berkeley-Carteret Hotel, Asbury Park, N. J.

May 12-13—Midwestern conference on fluid dynamics and meeting of American Physical Society (fluid dynamics div.) in conjunction with dedication of new mechanical engineering building, University of Illinois, Urbana.

May 18-19—Annual meeting and third national forum of Corporation Aircraft Owners Assn., Hotel Statler, Washington, D. C.

May 19-20—Seventh annual personal aircraft meeting, sponsored by Institute of Aeronautical Sciences, Lassen Hotel, Wichita, Kans.

May 23—National meeting of AIA airplane Technical Committee, Carlton Hotel, Washington, D. C.

May 24-26—Technical conference on telemetering, sponsored by American Institute of Electrical Engineers and National Telemetering Forum, Benjamin Franklin Hotel, Philadelphia, Penn.

May 25-26—Aircraft Industries Assn. board of governors meeting, Williamsburg, Va.

May 25-27—Spring meeting, Society for Experimental Stress Analysis, Hotel Statler, Cleveland.

May 27—Annual spring air regatta, Philadelphia Aviation Club, Wings Field, Ambler, Penn. (May 28 is alternate date in event of bad weather.)

May 27-30—Wright Memorial Glider Meet, South Dayton Airport, Dayton.

June 1-4—Aviation Writers Assn. annual convention, Hotel Mount Royal, Montreal, Canada.

June 8—Pratt & Whitney distributor operation and maintenance meeting, Airwork Corp., Millville, N. J.

June 10-13—National Aeronautics Assn., annual convention, Hotel Statler, St. Louis, Mo.

June 10-25—International aero exhibition, Centenary Palace, Brussels, Belgium.

July 7-8—Royal Air Force 1950 display, Farnborough airfield, England.

Sept 5-10—Eleventh flying display and exhibition, Society of British Aircraft Constructors, Farnborough airfield, England.

Oct 16-20—1950 annual general meeting of the International Air Transport Assn., Fairmont Hotel, San Francisco.

PICTURE CREDITS

12—G. E.; 13—G. E.; 16—Wide World; 18—Erwin J. Bulban

NEWS DIGEST

DOMESTIC

Colonial Airlines completed on Apr. 18 its 20th year of scheduled operation without a fatality or serious injury to passenger or crew member. In the period, the line flew 310,276,067 passenger miles, carried more than 1,204,800 passengers, and made more than 455,000 landings on its 3182 mi. system.

Domestic trunkline passenger traffic during February was up more than 12 percent over the same month last year. January traffic had shown a 13 percent gain over January, 1949.

Port of N. Y. Authority commissioners authorized lease agreements with five foreign-flag airlines operating at N. Y. International Airport. Carriers are Air France, KLM, LAV, Sabena, and Scandinavian Airlines System. Leases are sequel to so-called Dewey airline settlement of Aug. 5, 1949, between Authority and several domestic airlines and BOAC.

American Airlines President C. R. Smith advocated airline use of Air Force jet bombers such as the B-45 in long haul civil cargo operations as a means of developing basic information on day-to-day use of jet transports. Writing in the AIA publication "Planes," Smith said airline operation of military jets on a "dummy route" basis would go far in helping the U. S. retain world air transport leadership in the face of gains by England and Canada.

Marshall Mars, giant Navy Martin flying boat which crash-landed at sea during a recent test flight, was a JRM-1 instead of a JRM-2 as it was inadvertently listed in News Digest last week.

United Air Lines last month flew more revenue passenger miles than in any previous March in its history. Passenger traffic was up 4 percent over the same month last year, freight rose 5 percent, express 71 percent and mail 11 percent.

Second Martin XB-51 variable-incidence-wing bomber made its first flight last Monday. Company also revealed that the first XB-51 has completed Phase I flight tests and has been turned over to USAF for Phase II tests at the company's field.

Two Airlines—Eastern and National—have asked CAB permission to remove the 10 percent extra fares now charged on deluxe Constellation and DC-6 flights. Reduction would be effective on or before June 1. EAL and NAL also hope to extend their air coach services to new points during May.

Exports of personal and executive planes of 5000 lb. and under (empty airframe weight) for March by nine companies totaled 37 valued at $200,674, compared with 21 at $256,246 listed by the same companies for February. Reporting were Aeronca, Beech, Bellanca, Cessna, Engineering & Research, Piper, Ryan, Taylorcraft and TEMCO.

Leverett Edwards, Oklahoma City attorney, has been appointed to the National Mediation Board, which handles airline disputes.

Jet transport forecasts featured the Society of Automotive Engineers aeronautic meeting in New York last week, with proponents in general agreement that the turboprop will power medium-range craft and the turbojet long-range transports. Registration for the four day session was more than 600, and 30 manufacturers set up displays.

FINANCIAL

Glenn L. Martin Co. reported net income of $642,682 or 57 cents per share for the first quarter of 1950 on sales deliveries and billings of $10,577,404. Comparable figures for the same period last year: net income of $402,643 on sales of $12,283,265, or 35 cents per share. Current assets Mar. 31, including unrestricted cash of $10,171,540, totaled $25,684,801 as compared with current liabilities of $13,522,468. Backlog at the end of the first quarter totaled $92,118,000 (65 percent military), compared with $71,655,000 at the beginning of 1950. Current employment is up to 8400.


Consolidated Vultee Aircraft reported a profit of $2,934,496 for the first quarter ended Feb. 28. Sales totaled approximately $92 million, with approximately $77 million for the USAF and about $13 million for the Navy.

INTERNATIONAL

Handley Page Hermes 4, first of 25, has been delivered to BOAC and is being used for crew training and operational development flights. At least 23 of the type have reached final assembly stage at builder's Radlett plant. A half-dozen have been tested and inspected by BOAC and are to leave for the airline's Hurn base almost immediately. Others will follow at the rate of one per week.

Air Services of India has taken delivery on its second SNCA Sud-Ouest Corse transport. The Corse is a French twin-engine 10-13 passenger craft with 185 mph. cruising speed.

The New Trim Trol®
ELECTRIC ROTARY ACTUATOR



SIDE MOUNTING MODEL



"LEADING EDGE" MODEL


★ Two Mounting Styles: Side mounting model for general purpose and "Leading Edge" mounting model for Trim-Tab applications. See above.
★ Compact Size. See dimensions above.
★ Weight 2.25 pounds.
★ Operating Load Capacity 350 in. lbs. (Std. Ratio)
★ Static Capacity 1500 in. lbs. minimum.
★ Zero Backlash Output Shaft.
★ Positive Overtravel Safety Stops.
★ Radio Noise Filter Built In.
★ Compliance with all applicable specifications.
★ POSITIONING CONTROL—are electrical synchronizing available using our "Servosyn" unit.



★ Position Transmitter Potentiometer Built In and Externally Adjustable.

WRITE FOR BULLETIN 111

AIRBORNE
ACCESSORIES CORPORATION
25 MONTGOMERY ST. • HILLSIDE 5 NEW JERSEY




at high speeds . . .

Torrington Needle Bearings insure stamina

6,000 . . . 8,000 . . . 10,000 and as high as 15,000 rpm are among practical operating speeds on many outstandingly successful Torrington Needle Bearing applications.

The low coefficient of starting and running friction of compact Needle Bearings assures more efficient operation and contributes to longer service life in many high-speed installations.

In planning a new product or re-designing an old one, investigate all the features you can gain through the use of Needle Bearings. Our engineering department will provide full cooperation on any anti-friction bearing problem.



THE TORRINGTON COMPANY
Torrington, Conn. • South Bend 21, Ind.
District Offices and Distributors in Principal Cities of United States and Canada

TORRINGTON *NEEDLE* **BEARINGS**

NEEDLE
SPHERICAL ROLLER
TAPERED ROLLER
STRAIGHT ROLLER
BALL
NEEDLE ROLLERS



WHO'S WHERE

Saying Good-By

Dr. Albert C. Roper is retiring next year as secretary general of the International Civil Aviation Organization. Dr. Roper has been active in international aviation more than 30 years. He was secretary of the Aeronautical Commission of the 1919 peace conference, and secretary general of the International Commission for Air Navigation 25 years.

Dr. Paul T. David has resigned as alternate U. S. representative on the council of ICAO to accept an appointment with the Brookings Institution, Washington, D. C. Since 1946 Dr. David represented this country on the Air Transport Committee, and was appointed U. S. alternate representative the following year. In 1948 he was elected chairman of the economic commission at the second annual session of the ICAO assembly in Geneva. Shortly thereafter he served as chairman for the initial year of the reorganized 12-member Air Transport Committee.

Changes

▶ **Around the Manufacturers**—James W. Roche has been appointed supervisor of customer field service for Northrop Aircraft and will supervise field service on the F-89 Scorpion all-weather interceptor and the C-125 Raider transport. . . William G. Key has joined public relations staff of Fairchild E&A Corp. and will continue as editor of the company's house organ, "The Pegasus," in addition to other assignments in Washington, D. C., and Hagerstown, Md. . . . Aviation division of Goodyear Tire & Rubber Co. has made following changes: J. E. Leonard has been named district manager with hq. at Dallas, Tex., R. H. Hill has been assigned to the Akron office in charge of Goodyear's contacts with the lightplane industry and also will coordinate activities of the division's field men with the plant. C. H. Bruns has been transferred to manufacturers sales department working out of Kansas City. . . Albert E. Smyser, Jr., formerly of Fairchild's NEPA division, has been made public relations staff asst. at Glenn L. Martin Co. . . . Edwin P. Foltz has been named asst. industrial relations director of Pesco division of Borg-Warner Corp.

▶ **Around the Airlines**—**Eugene T. Thummel** has been named supt. of passenger service for Pioneer Air Lines with hq. in Dallas. He replaces Jay G. Rupe, who resigned. . . **Jack Flynn** has been appointed district sales manager for Northwest Airlines in Newark, N. J.

Travel Log

Beverly Howard, top-ranking acrobatic pilot has left for France to fly in a series of stunt exhibitions against Europe's top pilots. He is scheduled to fly his Warner-powered Bucker Jungmeister biplane at Paris, Apr. 30; Sarrebruck, May 7; Toulouse, May 14; Rouen, June 4; plus other dates not yet announced. He also plans a brief visit to Pakistan by airliner in June.

INDUSTRY OBSERVER

▶ **New Allison J-35-A23 turbojet engine is actually rated at 9700-lb. thrust instead of the 9200-lb. thrust previously quoted.**

▶ **Designation of YB-56 has just been given to the four-jet version of the Boeing Stratojet sweptwing bomber, replacing the original designation of B-47C. The new tag indicates the plane is scheduled for production sooner than was heretofore expected. It is powered with four of the Allison J-35-A23 engines instead of six GE J-47 engines (rated at 5200 lb. thrust each).**

▶ **Airframe companies will get only about half of the $1.2 billion announced by the USAF for 1950 plane procurement, while the rest goes to engine, propeller, accessory and equipment manufacturers.**

▶ **British Bristol 173 feederline helicopter will be first modern European helicopter to adopt tandem rotor configuration, and is being slated for use on British European Airways system after experimental development. The Model 173 is designed to carry 10-12 passengers, and will be powered by two of the Alvis Leonides 550-hp. radial engines which have become standard helicopter powerplants in Britain. Prototype is not expected to be ready for first flight until the summer of 1951. Meanwhile Bristol continues with its successful smaller 171 single-engine helicopter and BEA will begin June 1 to use Westland-Sikorsky S-51s on a scheduled service between Liverpool and Cardiff.**

▶ **Score of 90 Thunderjet F-84s "shot down" in the "attack" on Vieques Island during Operation Portrex was credited by official umpires to Marine Squadron VMF-115 using Grumman Panther F9F-2 jet fighters, with only 9 Panthers lost in the defense.**

▶ **Douglas Aircraft hopes to fly one of the first C-124A transports down to Operation Swarmer at Camp Mackall, N. C., late in April. The big four-engine transport would not be used in the exercise, but will probably be on display as a sample of bigger aircraft soon to be available.**

▶ **Bell Aircraft studies show that higher tip speeds for helicopter blades up to over 700 fps. are practical, but researchers feel additional studies are necessary on use of high tip speeds since standard airfoil data is not completely applicable to rotor blade problems. Drawback is that the advancing blade of the rotor is at high Mach number only instantaneously, and then at a low angle of attack, other airfoils are subject to more constant speeds.**

▶ **A dive at 185 mph. (in excess of Ercoupe design requirements) was cited as the cause for structural failure of a 1950 Ercoupe near Riverdale, Md. Pilot Robert Sanders bailed out at 4000 ft. and suffered a broken leg and head cuts. He had previously completed a dive test of 165 mph. (also above design requirements) in the same plane. Sanders, head of Sanders Aviation, National Ercoupe distributor, has flown most of the tests on the Ercoupe since early prewar prototype days.**

▶ **Cook Cleland, twice winner of the Thompson Trophy at the Cleveland National Air Races, is working on a plastic float for light planes, expected to be manufactured at Cleveland by an associate, Joe DeOlloqui, owner of a plastics plant.**

▶ **The two J-35 engines in the Hughes XH-17 jet helicopter were specially modified by General Electric to siphon off most of the compressed air to the rotor blades. GE removed the last few stages of the compressor and substituted an annulus to collect the air. This air is piped through the rotors to orifices at the blade tips where it is mixed with fuel and burned to provide thrust for the blades. The rotors are free wheeling with no gears. The GE modification permits just enough air to flow to the combustion chambers to give the turbine power to turn the compressor, without furnishing any thrust.**

▶ **Industry sources are wondering about the apparent omission of Beech and TEMCO trainers from the 1950 USAF procurement list. It was generally understood that the USAF was ordering three each of the Beech T-34 Mentor and the TEMCO T-35 Buckaroo. Yet neither was listed nor was their principal rival for the small trainer business, the Fairchild T-31.**

Vol 52, No. 17

AVIATION WEEK

April 24, 1950



TEST FACILITIES such as GE's rocket motor firing pit at Malta aid in developing guided missiles, but volume missile output is far off.

$100 Million Missile Program Under Fire

With no production in sight, Congress tells Defense Department to investigate.

By Ben Lee

Sweeping investigation of Defense Department's entire guided missile program is building up based on a stream of unofficial reports to Congress over inequities in service leadership of the $100-million plus program.

Congress has ordered the Defense Department to examine its missile research program. Order is based on reports from research scientists through the nation, appalled at gross duplication of effort and allocation of funds to facility projects for which there is no adequate use seen within the next five years.

►**Background**—For the first time the military has had sole responsibility for a development in which there has not been and does not seem to be commercial civilian industry interest (at least in the near future). As a result, Defense Department's Research and Development Board, charged with overall rule of missile development, has cloaked all data pertaining to rockets under tight security.

Congress has had no quarrel with development cognizance as constituted under R&DB's organization. Secrecy of specific weapons has been guarded, for status of the missile as a weapon could well decide the impetus to war—or force an aggressor to hold off its attack.

Congress has, until of late, left the military pretty much to its own devices in missile development because of military science's convincing argument that no stone in basic missile research should be left unturned. According to Capitol Hill sources so many "stones" have been turned however, that R&DB's Committee on Guided Missiles has been unable to concentrate development in definitive channels and progress has been slowed.

Recently completed USAF Stuart Report (AVIATION WEEK, March 6) representing a survey of the entire Missile Program is now before the Joint Chiefs of Staff. While many of the problems considered by the Stuart Committee resulted in split decisions the report recommended elimination of five guided missile development contracts and consolidation of six other separate missile projects to three.

Defense Department, though not concerned directly with Stuart Report, was displeased with inability of Stuart Committee to concur in the report's entirety and coupled with a congressional request, organized its own survey board to examine R&D activities in the guided missiles field. While report of the individual teams have not as yet been completely correlated, preliminary indications are that almost without exception each examined agency agreed that there is exhorbitant waste and little real progress in missile research and development.

It was reported that of the nine supersonic missile projects under development for air defense operations, two will not be ready for testing until 1951, two others will not be ready for test until 1952, three are scheduled for test in 1953 and two others will not reach the experimental test stage until late in 1954. Most familiar of the air defense type rockets under test is Boeing's GAPA missile which is being developed for Air Force. Model test vehicle research has been concluded. Overshadowing prototype test performance has been its utilization by the military to recapture waning congressional and public interest in expensive missile research. Publicity was spectacular and succeeded in bolstering Defense Department's policy for the public, that adequate progress was being made. Actually, the proposed GAPA is a 5000 lb ground-to-air missile with 200 lb warhead scheduled for a Mach 2.5 speed developed by ramjet propulsion. It will not be available for service test for nearly two years.

Navy is developing an air-to-air missile which it identifies only as Meteor. It is an airborne missile for fighter craft and will weigh 500 lb. It will have a Mach 3 speed and a 25 lb warhead. Powered by liquid rocket propulsion, it is currently undergoing guidance tests but will not be available for service test until 1953.

►**Combat Air Support**—There are six guided missiles scheduled for combat air support. Five are Navy developments and the sixth is Air Force. Two are air-to-air, one is air-to-surface and three are air-to-underwater. Two missiles in this category are little more than refined models of conventional air-to-surface bombs.

Others in this category, with exception of Hughes Aircraft's MX-904 rocket which is scheduled for test late this year for Air Force, will not be available for testing for at least five years. Navy Oriole, for example, which will weigh approximately 1500 lb., will have an estimated speed of Mach 3. and a range of about 20 mi. Also powered by ramjet engine, it is not scheduled for test until late 1955.

►**Land Operations**—Of the seven missiles under development for land combat operations, five are in development by Army, one by Air Force and one by Navy. Navy's development is scheduled for amphibious use and is known as LaCrosse. To be used against shore installations it will weigh about 1200 lb. and will be powered by a reciprocating engine which will give LaCrosse a 250 mph speed. It is scheduled for test in 1954.

Best known of missiles intended for land combat operations is the Douglas WAC Corporal under Army cognizance. Currently undergoing evaluation tests it is one of the few rockets which could be engineered for immediate emergency use. It weighs approximately 11,000 lb., has a range of about 50 mi. and a speed approaching Mach 4.

Another development closely paralleling the WAC Corporal is Hermes A-1. Chief difference is that it weighs approximately 7000 lb., is slightly slower and is said to be capable of conversion from present test vehicle stage to operational service use by 1952. Hermes II and Hermes A-3 are "heavier" versions of the same basic weapon. Hermes II weighs approximately 25,000 lb. and Hermes A-3 about half that. Neither will be ready for service test before 1952.

In the field of development for sea combat operations there are 8 missiles in various stages of research, all of which are under Navy cognizance. Three of the eight missiles under development are actually weapons which were developed during later stage of World War II and are in current development only for component testing of devices for other missiles. The remainder of Navy developments is not scheduled for testing for at least two years.

Eleven guided missiles are under development for strategic air operations. Nine are under Air Force cognizance, one Army and one Navy. Three of USAF's "missiles" are air-to-surface bombs refined from war-time prototypes. The remainder are not scheduled for test for from three to five years.

Factually, to date there is but one "guided missile" capable of immediate emergency use. This is Banshee, a Boeing B-29 drone which can carry a 10,000-lb. bomb load at 250 mph. Range is approximately 3000 mi. (Operating mechanism of the Banshee is adaptable to other large planes.)

This is cause of congressional unrest and what has provoked impending investigation. With more than $300 million spent in missile research and construction of elaborate test facilities since 1946 neither Air Force, Army nor Navy have come up with one adequate prototype guided missile.

Reasons attributed by research scientists are:

- **Duplicatory research** has drained 40 percent of the dollar effort placed in missile research.
- **Test facilities** for which there is no adequate project return foreseen in next three to five years, have cost Air Force and Navy millions.

Inyokern, a multi-million-dollar test facility built for Navy in a remote area on the West Coast is running at less than half capacity.

This is principally due to Navy's inability to interest sufficient scientists and technicians to migrate to so remote an area. USAF's development of Banana River, Florida, joint long range missile test center has been cited as another case in point. There is not, according to reports received on Capitol Hill, a missile in research which has reached a sufficient stage of development to require the tremendous expenditure of funds asked by USAF for emergency development of the Banana River installation.

Two other installations, Point Mugu, California, in operation for several years, and Air Engineering Development Center which Air Force now has under construction in Tennessee are also scheduled reevaluation. Point Mugu, operated by Navy, is doing its job well according to reports but many of its activities are duplicated elsewhere and with the proposed development of USAF's Banana River installation its activities would be duplicated completely.

Research scientists are not all convinced that there is a need for AEDC as it is presently planned. Objections to the installation arise from proposed use of wind tunnel equipment which is felt to be inadequate in the high subsonic and supersonic ranges because of size of instrument and model test sections. It was also noted by those interviewed that the remoteness of the AEDC project area would present USAF with the same difficulty in staffing the plant as Navy has faced with its Inyokern installation.



TEST CELL at GE's Malta station, with flame pit at right fires motors.

Missile Motors Work Gets Results

Showing off its test station, GE joins Army Ordnance in claiming U. S. has increased rocket engine efficiency.

The question of how far American rocket motor development has progressed since the end of the war has been answered in exact terms by the Army Ordnance Department and engineers at the General Electric Co., Schenectady, N. Y.

The efficiency of rocket motors developed by GE is at least 10 percent greater than that of German models built at the end of World War II, GE claims.

►**10 Percent Gain**—American rocket motors have reached a least 90 percent efficiency, against 80 percent reached by the Germans, five years ago. GE

rocket experts point out that this 10 percent gain is a significant increase in view of the fact that engineers must fight for every fraction of a percent increase in efficiency when nearing the 100 percent mark. One-hundred percent efficiency would be realized if the input (propellant) to the motor were converted 100 percent into output (thrust).

Translated into payload and range, the 10 percent gain means that American guided missiles comparable in size to German World War II models now can carry warheads at least 40 percent heavier, or fly 20 percent farther.

In round terms, GE says its rocket motor research program has reached a point where "large-scale power plants of higher efficiency, less weight and greater reliability than World War II motors can be built."

►**"Hermes" Project**--This information was revealed earlier this month when GE and the Army opened the door for a few hours to GE's jealously guarded Malta Test Station, Malta, N Y. GE is one of several contractors under the Army's rocket research and development program.

Newsmen invited to the Malta station, where all rocket motors developed by GE under the so-called "Hermes" project are tested, witnessed the firing of a 16,000 lb.-thrust rocket motor held stationary in a special test rig during the firing run. Firing time was not over 30 sec., but it was long enough for recording devices to pick up the desired performance data. The motor burned liquid oxygen and alcohol.

►**Little Giant**--While this particular unit has a much higher thrust rating than any turbojet engine, it is only 3 ft. long and 8½ in. in diameter at the headplate (nozzle). (The largest production turbojet in the U. S. is the 8,000 lb. Pratt & Whitney J-48.)

The motor demonstrated at Malta points up the trend in this country towards smaller, high thrust units operating at high temperatures and pressures. The Germans seemed to be going toward larger sizes at the end of the war. The V-2 motor, for instance, had a cluster of 18 nozzles feeding into a common motor body, while development at GE seems to favor compact, single-nozzle motors.

Three factors contributing to better motor efficiency and smaller size are improved high-strength, high-temperature metals, improved propellants having high flame speed and combustion temperatures, and better cooling methods, GE says. But cooling and need for improved metals remains an extremely critical problem in trying to achieve higher performance.

►**What Happens at Malta**--GE's facility at Malta is purely a test base. A rocket motor may be put through 20-30 sec. firing tests several times at Malta to check various phases of performance and to collect data for refinements in a particular unit. After GE has built a motor and tested it at Malta the motor is sent to White Sands, N. Mex.

Dr. R. W. Porter, head of the project, says GE has several new rockets in various stages of development for the Army. An experimental motor destined for White Sands is a finished article by the time it is shipped. Design and construction of these units depend on joint effort of several GE departments. Some refinements in construction--shown to be needed by test firing--can be made in the Malta station's own machine shop.

Malta also is conducting experiments with various propellants, including hydrazine, hydrogen peroxide, boron hydrides and gasoline, in addition to liquid oxygen and alcohol.

Diborane, a boron hydride, gives considerably better performance than alcohol and has an extraordinary flame speed," says Dr. Porter. It has a combustion temperature of about 6800 degrees F.

GE also is conducting research in the field of ramjet propelled guided missiles and holds a contract with the Army to assemble components of V-2s captured in Germany, make parts which may be missing or defective and supervise technical aspects of the launchings at White Sands. Engineers say study of the V-2 aided considerably in starting GE's rocket development program.

►**Malta Equipment**--Malta station, the first of its type in the U. S., has been in full scale operation more than three years, but the first test at the site was made in 1945. It can handle rocket motors up to 50,000 lb. thrust.

The installation consists primarily of four test pits and subsidiary structures. They are in a heavily wooded, isolated 3000-acre tract near Schenectady and are operated by 150 persons, mostly GE employes.

Two of the test pits from the outside look like concrete bunkers used to store explosives: constructed of reinforced concrete and set in the forward slope of a hill with earth heaped over the top and around the sides. But there's no resemblance internally.

►**Inside the Pit**--Each test pit is divided into four sections--control room, motor room and two "reactant" or fuel rooms. The control room contains fuel regulators, data recording devices and other equipment required to conduct the firing runs. Specially calibrated tanks permit constant electronic measurement of fuel consumption in the "reactant" rooms. Tanks are protected from fire or explosion by ventilating fans and high-pressure water nozzles which operate automatically or manually.

The motor room has only three walls, so that exhaust gases from the rocket motors spurt through the open end. A few yards back of this opening is a flame deflector screen made of concrete and heavy wire mesh. This flare baffle breaks up exhaust flames when they go beyond the walls of the motor room.

►**Vertical Pits**--There are two newer and larger test installations where motors are mounted vertically and fired downward into concrete flame pits 60 ft. deep and containing water. Engineers control and observe firing in the vertical test pits from a control building about 100 ft. from the test stand.

Control rooms for all four pits are protected by concrete walls 3 ft. thick on the side facing the rocket motor. All other walls and roofs are 2 ft. thick. Observation windows are 3 in. bullet proof glass panes, abutted on each side with 2 in. steel plates. There never has been a serious accident at Malta.

During firing tests, a string of bright "diamond" spots could be seen in the core of the exhaust, caused by the supersonic speed of the jet. During the blast, the rocket exerts pressure on the adjacent steel framework and this pressure is transmitted electrically from the framework to a recording graph.

►**Water Test**--Before a rocket is fired water is pumped through the nozzle to make certain the system is clear. This water test also can be used to determine the pressure required for the fuel flow. In a demonstration, the water was pumped into the rocket motor at the equivalent of a fuel consumption of 70 lb. per second.

The 16,000 lb.-thrust motor fired at the demonstration had two fuel lines, one for liquid oxygen, the other for the alcohol. The alcohol line fed into a jacket around the motor body. This arrangement serves a double purpose: the alcohol cools the motor and at the same time is preheated before injection. The liquid oxygen flows directly to the headplate.


Aircraft Research Activities Polled

In a survey of the research requirements of American industry, 71 percent of the aircraft companies polled stated that they would not curtail their technical staffs even in the event of a reversal of the present growing economy.

Should the present condition of the national economy continue, only 29 percent of the aircraft industry stated it would increase future research activities, while 14 percent stated research would be decreased and 57 percent predicted an increase.



SKIN AND STIFFENERS are squeezed out in one long roll in one operation from . . .



EXTRUSION PRESS with 5500 lb. pressure behind ram. Skin emerges from press as . . .

RIBBED CYLINDER which, then is cut lengthwise, straightened and stretched.

Aircraft Fabrication Revolution?

By Alexander McSurely

Important new trend in U. S. aircraft manufacturing methods which will have a major effect on future airplane design and fabrication is forecast as a result of the development to commercial stage of a new Reynolds aluminum extrusion process announced last week.

The revolutionary new process actually squeezes out airplane skin for wings and fuselages complete with built-in stiffeners thus creating a new semi-finished material for planes which promises to take many of the tedious man-hours and high labor costs out of airplane fabrication.

Reynolds Metal Co. engineers demonstrated recently to leading airplane manufacturers' engineers and to top USAF industrial planning specialists at Phoenix, Ariz., that their new extrusion process can turn out ribbed sheet suitable for airplane wings and fuselages from 75S alloy, the tough material selected by modern designers for the higher stresses to which high speed planes are subjected. The ribs are integral reinforcements at regular intervals along the sheet, and so designed that no other structural beefing is required to take the loads put on fuselages and wings in flight.

►**Simple Fabrication**--Potential of the new process for aircraft structures is enough to start the most stolid aircraft designer to penciling doodles on an envelope.

Without requirement for internal spars and bracings, the new material is expected to make it possible to shape plane wings and fuselage structures by far simpler fabrication processes, and at far more rapid production rates than is possible with present flat sheet materials and methods.

"The extruded sections," says Lt. Col. Carl W. Andrews, chief, resources planning section, industrial planning division, AMC, "have high physical properties and because of excellent detail configuration they will carry high compression stresses even with widely spaced supports, thus both weight advantage and simplification of internal structure can be obtained."

►**Ribbed Cylinder**--Using a hydraulic extrusion press with 5500 tons pressure behind the ram, the Reynolds demonstrators squeezed out through a die a long, ribbed cylinder with an inside diameter of 8.858 in. and a circumscribing circular diameter of 11.86 in. Slit lengthwise, the cylinder was laid out by a series of straightening and stretching processes to become a flat aluminum skin nearly 28 in. wide, weighing 5.784 lb. per sq. ft. with 14 T-shaped integral stiffeners running longitudinally at equally spaced intervals. Various skin thicknesses such as 0.04 in. and 0.07 in. have been used.

The section, according to Dr. George Perkins, Reynolds director of technical services, has been extruded successfully in 61S, 24S and 75S alloys and is considered commercial.

►**5 ft. Sheet**--Perhaps a 28-in. ribbed sheet is too narrow, if so, Reynolds engineers say they can make a comparable ribbed sheet up to 5 ft. in width by use of a larger press with approximately three times as much pressure.

To make a cylinder of sufficient internal diameter (20 in.) a 15,000 lb. press would be required to ram the extrusion out. When cut lengthwise and flattened, such a cylinder would make a skin approximately 5 ft. wide.

►**Future Lengths**--With present equipment a single section of SK-562, the experimental extruded cylinder shown, can be produced to a length of about 25 ft. with possibility of increasing this to a future length of 35 to 40 ft. Length of sections is governed by the maximum weight of aluminum alloy billets, now

175 lb. Possibility of increasing this to 250 lb. is under consideration.

Thicknesses of skin up to ⅝ in. will be required for some designs under consideration, it was reported at the demonstration, but these presumably can be produced with suitable dies and sufficient pressure.

▶**Lockheed Experiments**—Analysis of experimental work at Lockheed Aircraft in forming extruded sheet with integral stiffeners, presented by George W. Papen, showed that on an average, structures built with the new material weighed about 10 percent less than conventional structures.

Even more significant was the finding that the number of attachment operations and of separate parts was reduced 60 percent as compared to conventional design.

▶**Small Bends**—Papen said that forming methods using both stretch and compression rubber forming had been successfully used and that the compression method was particularly suited for forming airfoil sections involving small-bend radii out of the integrally stiffened sheet.

Average cost reduction on a basis of quantities ranging from 50 to 500 units, amounted to about 10 percent. Most estimates for stiffened sheet structures ranged from less than 50 percent to over 150 percent of the cost of conventional structures. However, high relative cost was accompanied by weight reduction, with a maximum premium per pound of weight saved of $2.

▶**War Availability**—The Lockheed engineer pointed out that availability factor of the new material in case of war, was even more important than weight and cost reduction factors. Production techniques made possible by integrally stiffened skin will require only a small fraction of the aluminum ingot capacity and machine tool capacity which are required for wing and fuselage skin built up of many fabricated parts held together by multiple rivets or spot welds, or made of solid metal, milled to required dimensions.

Papen called for requirements of rolled and forged stiffened sheet in addition to extruded stiffened sheet. He estimated that Lockheed could use integrally stiffened sheet of these three types for about 70 percent of its production replacing riveted stiffeners.

▶**Dow and Alcoa**—It was pointed out that somewhat similar magnesium extrusion development had been made by Dow Metals in 1940 and that the Alcoa had produced a smaller extrusion of 38 alloy as early as 1933 but that the Reynolds achievement with 75S alloy made possible new attainments in aircraft structural design.

Other significant points discussed at the Phoenix demonstration:

• **Integrally stiffened skin** sections of sizes and designs available with present presses will probably not be adaptable to all manufacturers' wing designs.

• **Good potential applications** for integrally stiffened skin include fuselages, bulkheads, floors, side panels and bottoms of flying boats, and guided missiles. (Possibility is seen for extruding the complete fuselage of a missile as a cylinder, without the flattening process.)

• **Best production technique**, it was indicated, would be for the cylindrical sections to be flattened at the extrusion mill, prior to forming and heat treating at the aircraft plant (except in the case of a missile fuselage cylinder). Flatness and straightness tolerances will be needed.

• **Maximum 28 in. width** produced with present press is reduced to 24 in. after trimming and while this is acceptable for many present applications, greater widths are desirable and will result in additional structural economy.

• **Transverse properties** of the sections after flattening and stretching require additional investigation.

• **Similarly produced magnesium** sheet with integral stiffening is desired for many interior applications.

The demonstration at the Reynolds Phoenix plant was the result of a manufacturing methods contract let by AMC to Reynolds more than a year ago, after the aircraft industry had expressed interest in this type of structurally reinforced material in a 1948 survey conducted by the technical service of the Aircraft Industries Assn.

Significance of the new development to the industry was shown by the turnout of top engineers, structural experts and designers from major aviation companies including Bell, Boeing, Consolidated-Vultee, Douglas, Lockheed, Chance Vought, Fairchild, Goodyear Aircraft, Hughes Aircraft, Glenn L. Martin Co., McDonnell Aircraft, Curtiss Wright, Northrop, North American, Republic and Ryan. Alcoa and Kaiser Aluminum and Chemical Corp. also were represented. Boeing sent five engineers, while Convair and Lockheed each sent three.

Military delegation led by Brig. Gen. A. H. Johnson, industrial planning division chief, AMC, included Cols. Leigh Hunt and Omer Niergarth of the Munitions Board staff, several Navy industrial planning representatives, and additional officers and civilian specialists from AMC.



CONVAIR ENGINEERING INGENUITY

First flight tests were made last week at Ft. Worth with an experimental nacelle carrier built to carry four Pratt & Whitney R-4360 engines suspended below the bomb-bay of a Convair B-36 bomber. Two complete nacelles are enclosed in each of two cylindrical pods, each 32 ft. long and 8 ft. in diameter. Pods are attached to an airfoil shaped beam suspended just forward of wing leading edge. Nacelles are bolted on to beam with same 4 bolt attachment with which nacelles are normally mounted on a B-36 wing. Arrangement makes it possible for B-36 to carry four spare powerplants for its own use to bases as needed. Carrier fully loaded weighs 25,000 lb. Preliminary design of carrier was at Convair Ft. Worth with detail and fabrication at Convair, San Diego.

Political Gifts

Financial contributions of aviation personalities going to Democrats.

Aviation executives are turning a cold financial shoulder on the Republican Party and pouring political contributions into Democratic hands.

Survey of 1949 contributions to finance this year's Democratic campaign show these donations:

James Bruce, American Airlines director and stockholder (former Ambassador to Argentina; now director of the European Arms program) $4000. (His brother, David Bruce, new Ambassador to France, contributed $3000.)

Robert Six, president Continental Airlines, $3500.

F. Smythe Gambrell, attorney Eastern Air Lines, $2000.

Allan G. Chase, president Standardized Aircraft, $3000.

Robert Hinckley, former assistant secretary of Commerce for air, now vice president, American Broadcasting Co., $3100.

Robert Thaleh, airline attorney, $2000.

C. R. Smith, chairman of the board American Airlines, $2250.

Thomas Morgan, Chairman of the board Sperry Corp., $2000.

W. B. Pawley, former Ambassador to Brazil, now an executive of central Aircraft, $3000.

George Whiteside, attorney, TWA, $1000.

Robert L. Earle, former vice president, Curtiss-Wright Corp., $1000.

Sigmund Janas, President Colonial Airlines, $1000.

G. W. Vaughan, former president, Curtiss-Wright Corp., $1000.

Herbert Gilette, president, Marquette Metal Products Co., Curtiss-Wright subsidiary, $1000.

Joseph Kennedy, former counsel, House Armed Services Committee (for its B-36 investigation), $1000.

J. Carroll Cone, assistant vice president, Pan American Airways, $1000.

L. Welch Pogue, World Travel Inc., Aviation attorney and former chairman, Civil Aeronautics Board, $1000.

Sullivan, Bernard, and Shea, Airline attorneys, $1000.

A. K. Christie, Washington representative, Pratt and Whitney aircraft, $1000.

Myrle Scudder, Washington representative, Republic Aviation Corp., $1000.

Harry Playford, President, U. S. Airlines, $1000.

Sherman Fairchild, director, Pan American Airways and Fairchild Engine & Aircraft Corp., $500.

Floyd Odlum, chairman of the board, Consolidated Vultee Aircraft Corp., $500.

Thomas Boorse, aviation consultant, $500.

T. Peter Agoberry, attorney Colonial Airlines, $500.

A. L. Wheeler, airline attorney, $400.

James Francis Reilly, airline attorney, $250.

J. Earl Cox, CAB examiner, $250.

Max Truitt, airline attorney, son in law of vice president Barkley, $225.

Richard Boutelle, president, Fairchild Engine & Aircraft Corp., $220.

D. W. Reinkel, Administrator of Civil Aeronautics, $200.

Jack Frye, former TWA president, now president, General Aniline and Dye, $100.

W. A. Patterson, president, United Air Lines, $100.

O. M. Mosier, vice president, American Airlines, $100.

Lewis C. Borowell, president, Resort Airlines, $100.

Warren Lee Pierson, chairman of the board, TWA, $100.

A careful check showed up no contributions to the Republican Party by aviation officials. Robert Lovett, former assistant secretary of war for air, contributed $300 to the GOP.

List Top Aircraft Industry Salaries

Top salaries paid by seven aircraft manufacturing firms during 1949 are listed in a second partial survey by AVIATION WEEK. (Ten other companies' salaries were reported in the April 10 issue and additional companies will be listed later.)

Salary details:

▶**Boeing Airplane Co.**—William Allen, president, $60,050, plus incentive payments of $1429 cash and $1071 stock; Wellwood Beall, vice president, $35,025, plus incentive payments of $1284 cash and $966 stock; Fred Landan, vice president, $28,085, plus incentive payments of $1284 cash and $966 stock; J. E. Schaefer, vice president, $28,005, plus incentive payments of $957 cash and $693 stock. Total payment to officers and directors $274,135, plus incentive payments totaling $8204 cash and $6111 in stock.

▶**Republic Aviation Corp.**—Mundy Peale, president, $61,000, Alexander Kartveli, vice president, $47,150, Thomas Davis, secretary, $30,000. Total payments to officers and directors $199,250.

▶**United Aircraft Corp.**—H. Mansfield Horner, president, $103,100, plus $40,000 incentive payment and $7610 retirement payment; Frederick Rentschler, chairman, $103,450; Leonard Hobbs, vice president, $73,400, plus $30,000 incentive payment and $7565 retirement payment; Raycroft Walsh, vice chairman, $63,350, plus $20,000 incentive payment and $8736 retirement payment. Total payment to officers and directors $683,350, plus $202,500 in incentive payments and $52,658 in retirement payments.

▶**Lockheed Aircraft Corp.**—Robert Gross, president, $75,200, plus $11,819 pension payment; C. A. Barker, vice president, $60,350, plus $12,292 pension payment; Courtlandt Gross, vice president, $60,350, plus $5773 pension payment; Cyril Chappellet, vice president, $45,300, plus $4050 pension payment; Hall Hibbard, vice president, $45,000, plus $4508 pension payment; Herbert Ryker, vice president, $45,353, plus $9173 pension payment; Carl Squier, vice president, $45,000, plus $9683 pension payment. Total for officers and directors $476,944, plus $62,702 in pension payments.

▶**Grumman Aircraft Engineering Corp.**—L. R. Grumman, chairman, $50,200, plus $9718 retirement payment; L. A. Swarbul, president, $60,200, plus $10,141 retirement payment; William Schwendler, executive vice president, $40,200, plus $5716 retirement payment; E. Clinton Towl, vice-president, $27,150, plus $3597 retirement payment. Total for officers and directors $211,300, plus $33,919 in retirement payments.

▶**Fairchild Engine and Airplane Corp.**—Richard Boutelle, president, $39,012, plus $20,000 bonus; Arthur Flood, vice president, $19,371, plus $10,000 bonus; Myron Gordon vice president, $36,600; Lawrence Richardson, consultant, $36,600; J. Carlton Ward, chairman of the board to July $90,600, plus $52,092 bonus payment. (The company anticipated that this amount would be claimed by Ward, but may be contested by the company. It represents $600 director's fee, $65,000 salary, $25,000 severance pay, $52,092 bonus from the firm's profits.) Total payment to officers and directors $297,954, plus $91,592 in bonus payments.

NACA Program Moves Forward

Chopping $11 million from the Budget Bureau recommendation, the House Appropriations Committee approved a $66 million 1951 fiscal year appropriation for National Advisory Committee for Aeronautics.

The committee called on NACA, which has expanded from a $25,000,000-a-year operation in 1945, to start "leveling off" its activities.

The $66,390,630 ($56,390,630 cash and $10,000,000 contract authorization) approved by the House group compared with the $77,600,000 ($62,600,000 cash and $15,000,000 contract authorization) recommended by the Budget Bureau.



SIEBEL COPTER NEARS CERTIFICATION

S-4 Copter developed by Siebel Helicopter Co., Wichita, Kans., shows its features in this flight view. Note cargo location directly beneath main rotor. Certification was due yesterday. Development and certification costs are estimated at $80,000, work being done in less than two years by four men. The company hopes to market the S-4 for about $10,000 and is tooling up with that figure in mind. Supercharging allows the helicopter adequate hovering performance at altitude.



SUPER CUB TAKES OFF, with dust bin open, over 20-ft. barrier 150 ft. from start.



TANDEM WHEELS of plane help in takeoffs and landings from very rough strips

New Super Cubs Display Utility

Piper shows Model 105s, said to take off and land in less space than any approved type now available.

By Erwin J. Bulban

Piper this year is going all out to sell the new 105 Super Cubs on their high utility merits. Steep takeoffs and landings out and into small areas and slow flight speeds of the agricultural and tandem-wheel models were stressed recently by the company during demonstrations at Flushing Airport, N.Y. The company claims that these planes will take off and land in less space than any other certificated aircraft now available.

►**Innovations Help**—These Super Cubs have increased power (108-115 hp Lycomings) and flaps. The potent effect of these innovations was displayed in takeoffs over a 20-ft. barrier from a marked-out strip only 150 ft. long. Landings were made in approximately half that distance. During slow flight, speed was down to just over 30 mph. The planes were fitted with fixed-pitch metal Sensenich props. Wind was relatively light, about 5-10 mph.

The tandem wheel model repeatedly made short takeoffs and landings using an unprepared and very rough portion of the field.

The craft were lightly loaded, each carrying only the pilot, while the dust/spray edition had only a portion of its up-to-1000-lb. dust capacity. However, Piper says that fully loaded to a CAA-approved gross of 1500 lb. the Super Cubs 105 will take off in 575 ft. in still air and land in 385 ft. Basic price of the craft is $2995.

Several liaison officers watched the demonstrations unofficially and stated that they would prepare an informal report on the display.


►**Prices**—The agricultural plane with the dual-purpose dust/spray installation is tagged at about $4100. The aluminum tank has a capacity of 80 gal. of chemical or 600 lb. of dust. The dust/spray combination was designed and is being supplied by Art Whitaker, a Piper distributor in Oregon. Three agricultural models have already been shipped abroad, with one each going to France, Morocco, and South Africa, and three are scheduled to go to Bogota, Colombia. About 20 more are on order.

Gear on the tandem model was also designed and is being supplied by Art Whitaker. Each landing gear strut carries two balloon tires mounted one ahead of the other. The front wheel has no brakes and is inflated to only four pounds, while the rear wheel carries eight pounds pressure.

The gear, which costs $265 extra, adds 40 lb., but effect on performance is said to be negligible. Owners of planes with standard wheels can buy the tandem wheel setup through their local dealer and have it installed by him. Installation is simple and can be readily handled by any qualified mechanic. About 60 of the tandem-wheel 105 Super Cubs have already been distributed. Approval of the craft on Edo Model 1400 floats is expected soon.

►**Piper Prospects**—The company views 1950 with optimism and sees the possibility of production reaching 110 per cent of last year (1278 planes shipped in 1949, including 203 Stinsons—AVIATION WEEK Feb. 27). If output of the Super Cub could be stepped up to 8-10 daily over a six-month period, it is believed that man-hours per plane could be reduced to 190-200.


WRIGHT BROTHERS


ADMIRAL BYRD


LINDBERGH


AMELIA EARHART


SIR HUBERT WILKINS


KINGSFORD SMITH


WILEY POST


JOE DE BONA

The Flying Red Horse Flew with them All!



FROM the Wright Brothers' first flight in 1903 to Joe DeBona's Bendix Trophy victory last year, leading aviators have put their trust in the Flying Red Horse. Keep *your* plane at full power with *Mobilgas Aircraft*—dependably protected with famous *Mobiloil Aero!*

SIGNS OF SAFETY & PERFORMANCE


At Over 1,000 U.S. Airports

Mobilgas AIRCRAFT

Mobiloil AERO

SOCONY-VACUUM OIL CO., INC., and Affiliates MAGNOLIA PETROLEUM CO., GENERAL PETROLEUM CORP.

In J33 Turbo-Jets the hottest job goes to INCONEL





The J33 Turbo Jet powers Lockheed's famous P-80 "Shooting Star." Inconel combustion chamber linings help extend engine life and reduce maintenance costs

It takes a *tough* metal . . an unusually corrosive-resistant and heat-resistant one . . to survive the white-hot blast of burning jet fuels

That is why the designers of the J33 Turbo Jet chose Inconel* for burner liners. And why Inconel is used as the metal reinforcement in the insulation blankets on the J33 tail cone.

Inconel . . . unique among nonferrous alloys . . . withstands temperatures up to 2000° F, and is remarkably resistant to both hot and cold corrosives. It is harder and stronger than structural steel, yet readily workable. Welds in Inconel are as heat and corrosion resistant as the parent alloy itself.

Because of these "fight back" qualities, Inconel has proved to be the answer to some of aviation's knottiest high-temperature problems . . . engine exhaust systems, heater combustion chambers, and fastenings, for example.

Where even greater hot strength is required, *Inconel X** offers properties never before obtainable in a practical, easy-to-buy metal.

If you would like more information about Inconel or other Inco Nickel alloys . . . or if you would like help with a specific metal problem . . . write to our Technical Service Department. *Reg. U. S. Pat. Off.

EMBLEM OF SERVICE INCO

THE INTERNATIONAL NICKEL COMPANY, INC.
67 Wall Street, New York 5, N. Y.

INCONEL*...for long life at high temperatures

How Past Taxes Affect Earnings

Peculiar nature of aircraft industry makes the annual reports of manufacturers only tentative at best.

There is no doubt about the impressive nature of aircraft earnings last year. Only in a few cases, however, are the results indicative of so-called "normal" earnings. In some instances, tax adjustments belonging to prior years are important factors in adding or curtailing earnings. Taxes which properly may belong to prior periods also remain as a contingent claim against earnings of subsequent years.

There are other adjustments which must be given serious attention to appraise earnings currently reported. The aircraft industry is essentially a contracting business and as such does not lend itself to an exact accounting by precise yearly periods.

Major procurement contracts may run upwards of two years before completion. Accordingly, any interim accounting determination must be regarded as only tentative until all contract deliveries are made. Actually, however, once the annual reports of most aircraft companies are released, the published figures are accepted as final and filed away in the reference manuals.

▶ **Settlement Delayed**—Even assuming that contract deliveries are all completed, there is no irrevocable finality to the transaction. With the government the principal customer, the aircraft industry is subject to a series of contract price redeterminations and renegotiations.

These processes may run their course a year or more before management will know the exact profit or loss adjustments that may apply to completed business of prior years. For example:

• **Douglas Aircraft Corp.** for the year ended Nov. 30, 1949, reported net income of $5,516,700 or $9.19 per share. However, a note to the financial statements call attention to the fact that the U. S. Treasury Department is now contesting certain tax matters for 1946 and 1947.

If all of the government contentions prevail, an additional tax liability of $6,600,000 plus interest would be imposed upon Douglas. The company does not agree with the government contention and has made no provision for such payment in its statements. (To do so would, in effect, tacitly admit the government claim). Douglas, in another action, is prosecuting a claim for approximately $3 million of excess profits tax relief for 1941.

• **Curtiss-Wright Corp.**, since the end of the war, has shown as a current liability a substantial amount representing provision for federal income taxes. As of Dec. 31, 1949, this item came to $15,267,844, down from the $18,151,430 shown a year earlier.

Here too, a financial note calls attention to the fact that 1944 to 1947 tax returns are in the process of examination by the Treasury Department. The management, however, believes that it is probable that a substantial portion of the amount provided in the balance sheet for this purpose will be restored to surplus when settlement of taxes for these years has been concluded.

In other words, results for 1944 to 1947 may have been understated in the light of this pending tax adjustment.

• **Lockheed Aircraft Corp.'s** earnings for 1949, as reported, amounted to $5,491,000 or $5.10 per share. However, during that year the company picked up in current earnings tax adjustments belonging to previous years. These amounted to $1,155,988 or $1.07 per share.

• **Consolidated Vultee** provides one of the more noteworthy examples as to what a difference accounting treatment can make in earnings. For the year ended Nov. 30, 1949, the company showed net earnings of $3,713,156 or $1.60 per share.

With the close of the 1949 fiscal year, Convair changed its accounting policy with respect to cost-plus fixed-fee government contracts. Starting with the first quarter of fiscal 1950, the company will bill allowable costs and associated fees on a current basis, a practice followed by most aircraft units.

In the past, the company carried sales and fees to income only as the actual articles built were delivered. Under this procedure, a certain amount of profit and sales remained suspended between the time of actual accomplishment of the work and the final delivery of the articles manufactured.

Were this revised accounting system in effect during 1949, Convair's earnings last year would have been augmented by $2,200,000 (about 95 cents a share), approximately $400,000 of which would have been attributable to that year.

It is obvious that this $2,200,000 will now become part of 1950's earnings together with the current profits to be accumulated this year under the revised accounting system. In other words, it is likely that the final 1950 earnings for Convair will show a substantial improvement over 1949, but part of this result will be due to an accounting change.

• **Republic Aviation Corp.** reports a net income of $876,632 or about 87 cents a share for 1949. Included in current earnings as part of other income, however, is an item of $580,121 representing separation claims recovered as an allowable cost and which presumably could be attributed to activities in prior periods.

On this basis, it would appear that Republic's "normal" earnings, after tax adjustments, for 1949 were closer to $560,790 or about 56 cents per share.

• **Fairchild Engine & Airplane Corp.'s** annual report reveals perhaps the most astounding accounting "adjustment." For the year ended Dec. 31, 1948, the former management reported a net profit, after taxes, of $1,552,382.

An examination of the 1948 statements reveals no mention or note anywhere to give an inkling of what is now disclosed in the 1949 annual report. The Securities and Exchange Commission, it is now indicated, issued a deficiency letter concerning the 1948 annual report, in which an item of $500,000 was included in valuing inventories to reflect the probable recovery of general and administrative expenses in some future year.

The former management considered that such expenses were applicable to airplanes to be delivered in future years and would be taken into account in subsequent price redetermination proceedings. Also, the 1948 report by the former management, included as an inventory item $86,572 representing the cost of certain development work undertaken with a view to obtaining additional contracts.

The present Fairchild management asserts that it considered the treatment of these two items as departures from the accounting policies previously followed by the company and not warranted by existing circumstances. Accordingly, amended statements for 1948 were filed with the SEC in which these expenses were charged to income. This action resulted in a reduction after taxes of $340,819 in earnings for the year 1948.


—Selig Altschul

FROM 20,000 TO 800,000 BTU/HR...



South Wind has the answer to your aircraft heating problem!

For heating, pre-heating or thermal anti-icing any type of military, commercial or civilian aircraft



*New application not released from military censorship

SOUTH WIND offers a complete line of combustion-type heaters and exhaust-gas heat exchangers, especially designed for simplified installation and minimum maintenance. These lightweight South Wind units already assure maximum heat, long-life performance and utmost safety to *thousands* of the nation's leading aircraft.

SOUTH WIND provides expert engineering assistance, complete testing facilities and specialized production techniques to help solve your most challenging aircraft heating problem.

WRITE TODAY for specific model information or experienced counsel on any phase of aircraft heating. Address inquiries to the South Wind Division Stewart-Warner Corporation, Indianapolis 7 Indiana

South Wind

Stewart-Warner

AIRCRAFT HEATING AND THERMAL ANTI-ICING EQUIPMENT

Power Study for Long-Range Transports

Analysis covers three propulsion schemes for high-speed travel.

By Alexander Kartveli*

In discussing the requisites of air transportation, it has always been my opinion that there is one basic parameter—speed. In addition to its practical importance, the factor of speed has a psychological value, and its influence on profit and cost cannot be evaluated by mathematical formulas.

Importance of speed becomes much more pronounced in the case of long range transports where, in addition to psychological advantage, the saving of time is the most attractive feature. Therefore, we should exert all our efforts to the attainment of greater speeds within practical limits of safety and economy.

As we all know, the postwar era has brought into existence several new propulsion devices offering interesting prospects for increasing speed. How can these new propulsion devices at our disposal affect the performance of long range transport planes, and what improvements in speed at a given range can be obtained?


Three possible power plant versions are now made available for this type of aircraft. Reciprocating engine compounded with turbo-supercharger, turboprop, and pure jet. Each type has its advantages and defects, and each is now being considered by the aeronautical engineers.

▶ **Approach**—The problem of appraising the fitness of a power plant for a given type of airplane is very complex when treated in its generality. It not only involves factors depending upon the engine, but also those of the airplane and outside conditions.

Factors such as engine size and weight, specific fuel consumption, cooling, propeller efficiency, airplane weight and useful load, aerodynamic characteristics of the wing, compressibility, structural considerations of aeroelasticity, etc., should all be considered in their respective relation. Because of the multiplicity of factors, a general analytical study becomes so involved that







RAINBOW VERSIONS piston engine (top), turboprop (center), turbojet (bottom)


* Vice president chief engineer, Republic Aviation Corp. Paper delivered at the Fifth Annual Flight Propulsion Meeting of the Institute of the Aeronautical Sciences Cleveland, Ohio, Mar. 24.



The Birdmen's Perch

"We're lost!" the Captain shouted

Unless you're one of those eccentric buzz-boys who enjoy an emergency landing in somebody's pea patch, those words should scare the be jeepers out of you



It gets you right under the safety belt, as they say, and it ain't good Yet, plenty of otherwise good flyers, who don't know their navigation from a hole in the ground, just plain go out and "get lost.

Take the average lightplane pilot who flies without radio help He's a demon at following a four-lane highway on a clear day, but throw in some poor visibility and it's another story And—even if he sports the latest in radio equipment, a fuse can blow his set deader than a herring

There's only one answer—practice your navigation! Keep your technique "fresh" and there's no reason for you to ever get lost or miss your destination.

And Speaking of Destinations...

One of your regular destinations should always be the source of that scintillating super lube, Gulfpride Aviation Oil—Series D!

Modestly enough, it's the world's finest detergent dispersant oil for horizontally opposed engines because—it's the only lightplane oil put through Gulf's exclusive Alchlor process to remove extra carbon and sludge formers!

If your plane has the nasty habit of crying like a baby when you wheel it out of the hangar, all the little fellow needs is a shot of Gulfpride Aviation Oil—Series D—to free those sticky valves and rings.

And you'll increase those periods between overhauls up to 100%!

Little Known Facts Dept.

And now, students if you can tear your eyes away from 'Smiling Jack' for a



minute, the Dean has an important honor to confer Will Mr Leonard King of Adrian, Mich., step forward please

Mr King, your Little Known Fact About Well Known Planes has been carefully scrutinized by the faculty and termed not only appropriate, but highly sensational. Therefore, with the powers invested in me by goodness knows who, I commission you as Petch Pilot (bottom rung)! If the student body will now rise, I shall read the Little Known Fact, submitted with PROOF!



"It was just twenty years ago that Jim Doolittle made the first instrument landing under the hood at Mitchel Field and proved that it was possible."

Ah pioneers, oh pioneers! Nice work, Leonard! Now suppose you tell the other boys and girls how proud you are of the new diploma and just how easy it was to dig up that L. K. F.

Don't remain unsung forever. Send your Little Known Fact About Well Known Planes—with PROOF—to this address

GULF AVIATION DEPT., GULF BUILDING
PITTSBURGH 30, PA

Gulf Oil Corporation . . . Gulf Refining Company . . . marketers of

GULF AVIATION PRODUCTS



the conclusions reached are of academic and general character.

Analysis of the relative merits of various powerplants, therefore, should be conducted not from the academic, but from a purely engineering point of view in the light of the present state of the art, available methods and technique and equipment which exist, or which will exist in the near future.

▶ **Basis of Comparison**—In this analysis, we first considered a long-range transport plane equipped with four turbosupercharged reciprocating engines. We assumed this airplane to be designed in accordance with modern technique using the latest available equipment, and complying with all necessary requirements. For this airplane, curves of range versus cruising speed were computed at various altitudes. Studies were then made of how these curves would change if the reciprocating powerplant were replaced, first by a turboprop, and then by a pure jet powerplant.

To make this comparison valid, the payload, as well as the fuselage and its contents, were left the same in all cases. Certain small adjustments were made, however, in the thickness and area of the wing to bring its aerodynamic qualities in accordance with the speed attainable with a given powerplant. In making this adjustment, the volumetric capacity of the wing was kept the same in each case, so that the total volume of fuel carried remained unchanged. We believe that this basis of comparison is rational. For the sake of clarity, however, we would like to explain this point in more detail.

▶ **Wing Considerations**—In choosing the wing for a high-speed airplane, the thickness, aspect ratio, span and a certain magnitude of area are first assumed to comply with necessary structural, weight, flutter and compressibility requirements. A check is then made that such a wing meets auxiliary requirements of takeoff, climb, maneuverability, landing, etc., when used with a given powerplant.

It is usually found that with modern powerplants these requirements are not critical within the acceptable values of wing loading. This is because of the high horsepower at takeoff these powerplants develop due to water injection in the case of reciprocating engines, inherent large horsepower of turboprop engines, and the use of afterburning in the case of pure jet engines. These requirements, therefore, do not affect the value of wing area.

An analytical study of range versus cruising speed shows that for the achievement of greater cruising speed without much loss in range it is advantageous to keep the wing area rather small to reduce compressibility drag. It is, however, impossible to reduce the

SPS AIRCRAFT FASTENERS

UNBRAKO



NAS INTERNAL WRENCHING LOCK NUT

...a superior safety nut. Sizes from #8 to 1".



NAS INTERNAL WRENCHING AIRCRAFT BOLTS

...are made to latest NAS Specifications. Threads are fully formed by rolling after heat treatment, an important UNBRAKO feature. Full range of standard sizes.

FLEXLOC

EXTERNAL WRENCHING NUTS

...incorporate the famous FLEXLOC self-locking principle and one-piece, all-metal construction. The exceptional reliability of this construction has been proved by the millions of FLEXLOCS used in the aircraft industry.


Other outstanding advantages include:
Maximum tensile with minimum weight
Approved under latest NAS Specifications
Large bearing surface
Positive self-locking—"won't shake loose"
Temperature range to +550° F.
No special tools needed—use standard 12-point socket or box wrenches. Designed for use in cramped quarters
Sizes from ¼" to ¾" NF Thread Series
Send for samples and information.



FLEXLOC

ONE-PIECE SELF-LOCKING NUTS

The one-piece FLEXLOC is both a stop and a lock nut, due to its resilient segments which lock *positively*, even under extreme vibration. Torque is unusually uniform—within a few inch pounds "Thin" and "regular" types; NC and NF threads. Officially approved by many U. S. depts., bureaus, etc., and CAA for aircraft use.



Write for further information on these* UNBRAKO *and* FLEXLOC *Products.


See us at Space 128, A S T E Exposition, April 10-14, Convention Hall, Philadelphia

SPS STANDARD PRESSED STEEL CO.


JENKINTOWN 3 PENNSYLVANIA

New **ADEL** Lightweight

3000 PSI SOLENOID, PILOT-OPERATED 4-WAY SELECTOR VALVES



New ADEL poppet type selector valve No 21700 Internal leakage in neutral position 1 drop per minute maximum at 3000 psi When in neutral, cylinder lines vented to return Can be used as a pair of separately controllable 3 way valves ⅜ and ½ inch line sizes.



New ADEL slide type selector valve No 23386 Internal leakage in neutral position 1 cc per minute at 3000 psi When in neutral, cylinder lines can be blocked or vented to return Variations available with centering springs or detents ¼, ⅜ and ½ inch line sizes

CHARACTERISTICS OF BOTH POPPET AND SLIDE TYPE VALVES:

- ★ No moving seals
- ★ Integral filter for protection of pilot valve against effect of dirty oil, foreign particles, etc
- ★ Continuous duty solenoids either 1 or 2.
- ★ 4500 psi proof pressure on all ports.
- ★ Pressure drop 50 psi at 6 gpm.; 100 psi. at 9 gpm.
- ★ Produced for 17 30 volts dc, 10 watts minimum; available for other dc voltages
- ★ Available with or without manual control

New designs are more compact, have low weight, longer service life, less maintenance, easy installation characteristics plus increased operating efficiency ADEL'S extensive engineering and manufacturing experience in Aviation Hydraulic Equipment insures uniform excellence of products

ADEL

FOR DEPENDABLE PERFORMANCE *Specify* ADEL For complete engineering specifications and counsel, address ADEL PRECISION PRODUCTS CORP., 10777 Van Owen Street Burbank, California.

ADEL PRECISION PRODUCTS CORP. BURBANK CALIF. • HUNTINGTON W. VA.

CANADIAN REP. RAILWAY & POWER ENGINEERING CORPORATION, LIMITED

wing area to the desirable lower limit because of the necessity of having a given minimum volumetric capacity for fuel

Thus, the volumetric capacity becomes a very important factor in determining the final value of the wing area It is logical, therefore, that in pursuing this analysis, wings with the same volumetric capacity should be considered in each case.

In this way three airplanes of approximately the same size, carrying the same payload, and having the same fuel capacity, were obtained. The gross weight of these craft varies within reasonable limits depending upon the conditions of each case. It is believed that the problem so treated will yield interesting practical results, and will correspond to the actual case which confronts the industry now

▶ **Rainbow**—As a basic airplane of this type, we have chosen the Republic Rainbow for which a large number of flight tests, wind tunnel and theoretical investigations are available.

This airplane is a long range transport carrying 40 passengers and 6 crew members, with a total payload of 10,000 lb It has a mid wing arrangement with a wing area of 1,640 sq ft, aspect ratio of 10, and an average thickness of approximately 15½ percent The buffeting limit is approximately 76 Mach number The wing has an available internal volume to carry 6200 gal of gasoline With 10 000 lb of payload and 6200 gal. of fuel, the gross weight of the plane is 120,300 lb

The reciprocating engine powerplant consists of four Pratt & Whitney R-4360 engines developing a takeoff horsepower of 3800 at sea level with water injection Each engine is equipped with an exhaust driven supercharger which permits high cruising powers to be carried to 40,000 ft The turbosupercharger is so arranged in the nacelle that the exhaust gases are ejected horizontally through the aft end of the nacelle, thus providing a certain amount of jet thrust

For this airplane, curves of range versus cruising speed at altitudes of 20,000, 30,000 and 40,000 ft were computed It was assumed in these computations that 10 min at normal rated horsepower were spent on the ground for warm up, taxiing, and take off

It was further assumed that the climb to cruising altitude was performed under optimum conditions of minimum fuel burned and maximum distance gained in the climb, and that the reserve fuel allowance is 600 gal The horizontal distance covered in the climb was added to the computed level flight range, but no increase in range was taken due to the horizontal distance covered in the descent.




Fig 1 shows range versus speed curves at three altitudes for this reciprocating engine version

At each altitude, the horsepower of the engines was varied between maximum permissible cruising horsepower at that altitude and the minimum cruising power corresponding to the best value of miles per pound. Where applicable, the lower limit of cruising power was taken equal to that power which gave a rate of climb of 200 fpm.

It is seen that the range speed performance of this airplane improves considerably when the altitude increases. At 40,000 ft, a range of approximately 4000 mi could be obtained at an average cruising speed of 400 mph, while a range of 2750 mi. could be flown at a speed of 450 mph or a Mach number of 67, thus giving a margin below buffeting limit of 1 Mach, or 66 mph.

This airplane could, therefore, be used on trans-Atlantic runs between New York and London with an average cruising speed of 400 mph., and also on transcontinental New York to Los Angeles runs with a speed of 450 mph.

▶ **Rainbow with Turboprops**—We next studied the same airplane equipped with four Allison turboprop engines The accompanying illustration shows the smaller nacelles attainable with this type of powerplant

In this study, we again assumed that the fuselage and contents remained unchanged, that is to say, payload, passenger accommodations, and all the equipment and accessories necessary to operate and control the airplane are identical.

The wing, however, while basically identical to the preceding case, has a longer average chord which brings its average thickness to 14 percent or 14 percent thinner than that of the Rainbow. This change is accomplished by extending that portion of the leading edge which overhangs the front spar Under this condition, the wing has an area of 1750 sq ft, a slightly smaller aspect ratio, and the same available volumetric capacity of 6200 gals Its critical buffeting limit for values of lift coefficient involved is increased from .76 to approximately .8

Bendix-Skinner

ORIGINATOR OF **MICRONIC** FILTRATION

the *Finest*

Defense Against Clogging and Wear



There can be no more demanding job for filters than in today's high speed, long range planes That's why manufacturers and the U. S. A. F. turn to ***Bendix-Skinner*** filters. They know from past experience, as well as current operational records, that nine times out of ten ***Bendix-Skinner*** filters will supply the "finest" answer. Why not let ***Bendix-Skinner*** filters solve your problems too?

Over 350 Models *providing filtration from ½ micron (.00001") upwards at flow rates from 1 to 5000 g p m*



SKINNER PURIFIERS DIVISION OF
1500 TROMBLY AVENUE, DETROIT 11, MICHIGAN
Export Sales: Bendix International Division, 72 Fifth Ave., N. Y. 11, N. Y.
Bendix AVIATION CORPORATION



FIRST CHOICE in Nation-Wide Survey— GLIDAIR Aircraft Finish!

GLIDAIR Aircraft Finish tops all other brands! From coast to coast, fixed-base operators—men with experience in using all types of aircraft finishes—have named GLIDAIR as their first choice. This fact was confirmed by a nation-wide survey conducted recently by an independent research organization.*

Achieving this top preference rating is additional proof of the superiority that has earned GLIDAIR Finishes industry-wide acceptance by manufacturers, airlines, and service organizations. GLIDAIR Aircraft Finishes are unexcelled for appearance, performance, and ease of application. If you are not now using GLIDAIR Finishes, it will pay you to investigate their outstanding qualities. Write for detailed information:


*details furnished upon request

THE GLIDDEN COMPANY
AVIATION SALES HEADQUARTERS
CLEVELAND 2, OHIO

QUALITY Glidden PRODUCTS

GLIDAIR

Aircraft Finishes for every purpose



Each turboprop is installed in a nacelle of 40 in. maximum diameter. Distance between wing main spars is sufficiently large to permit the engines to be housed inside of the wing between these spars. Extension shafts protrude forward of the front spar and carry dual rotation propellers. Engine air is admitted through two openings in the leading edge, symmetrically located on either side of the nacelle.

Due to the lighter weight of the turboprop engine, and absence of cooling equipment, such as intercoolers, oil coolers, various air inlets and ducts, the total weight of the powerplant is considerably less than in the preceding case. A saving of 6600 lb results from this interchange of powerplants. Since the fuel capacity of the wing is the same as before, 6200 gal. of kerosene could be used instead of gasoline, giving an increase of fuel load of 4960 lb.

Allowing certain additional weight for wing reinforcement to take care of the longer leading edge and higher speed, the gross weight of the airplane becomes 119,400 lb.


Curves of range versus velocity were computed for this airplane under the same assumptions as before. Fig. 2 gives these curves for the same altitudes of 20,000, 30,000 and 40,000 ft.

In these computations, it was assumed that the rpm. of each engine varies between the value corresponding to full normal power and the value giving 60 percent of normal power. Since the specific fuel consumption increases rapidly below 60 percent of normal power, it was assumed that further reduction of power was accomplished by stopping one of the two siamesed engines in various nacelles. First two units, then four were assumed inactive. This explains the steps in the performance curves on Fig. 2. Numerical computations were based on re-rated values of power which will be available in the near future.

As can be seen, the range increases with altitude, while the maximum possible cruising speed is obtainable at lower altitude. A maximum range of 4750 mi. at 410 mph. can be obtained at 40,000 ft. At 20,000 ft. a cruising speed of 515 mph. will give a range of 1875 mi.

A transoceanic non-stop flight of 4000 mi. at 40,000 ft. will have an average cruising speed of 465 mph., while a transcontinental run of 2750 mi. will take place at approximately 500 mph. at 30,000 ft. In both cases, the margin below buffeting limit is approximately .1 Mach.

It is to be noted that propellers used in these computations are of existing types. It appears, therefore, that this combination does not involve the development of any new equipment.



► **Rainbow with Turbojets**—In the turbojet version of this airplane, the payload, fuselage and its contents remain the same. The airplane is, however, equipped with an entirely new wing. A sweptback wing having 35 deg. of sweep and a thickness of 12 percent was chosen. The wing has an area of 2000 sq. ft., aspect ratio of 8, and can house the same 6200 gals. of fuel. Its buffeting limit, within the values of lift coefficient considered, is estimated to be approximately .9 Mach.

A structural penalty of 6500 lb. was assumed as the additional cost of this wing, and added to the gross weight of the airplane. Under these conditions, with kerosene as fuel, the gross weight of the airplane is 126,150 lb.

The airplane is equipped with four recent-type turbojet engines located in two underslung nacelles. Each nacelle houses two engines, staggered one behind the other. Landing gear is also housed in the nacelles. Recent tests show that interference drag of an underslung nacelle can be considerably reduced if the boundary layer in the wing-nacelle inboard intersection is bled away. The drag of this airplane was carefully computed, using recently available data.

Curves of range versus speed at various altitudes were established under the same conditions as before. Fig. 3 shows these curves. Again the range at a given speed increases with altitude, but the increase is of a much lesser amount than in the two preceding cases. A relatively constant range for wide variation of cruising speed is characteristic of jet propelled airplanes.

At 20,000 ft., a cruising speed of 580 mph. with a range of 1000 mi. could be obtained. At 40,000 ft. a range of 2000 mi. corresponds to a cruising speed of 550 mph. In both

Hartman 120-volt DC relays take the sting out of electrical problems in Northrop Scorpion




Photo Courtesy Northrop Aircraft, Inc.

High voltage electrical systems cut space and weight—all important considerations in a high-performance aircraft such as the Northrop F-89 Scorpion. But, heretofore, problems in breaking large currents at the higher voltage have prevented use of the more efficient 120-volt DC system.

Solution by Hartman engineers of problems concerning interrupting capacity, operation at altitude, welding of contacts and difficulties of control, has resulted in installation of the improved equipment in the Northrop F-89 *—the first production airplane to employ a 120-volt DC system.* In addition to seven 120-volt relays of four different types, the F-89 is also equipped with six 28-volt Hartman relays of three different types.


If your problem involves DC controls, turn it over to Hartman where it will be analyzed and engineered with an efficiency that comes from nearly half a century of specialization in DC control equipment. A-3084




Reverse Current Cutout—250 amp, 120 volts DC (USAF Spec. 32649, Type Q-1)



Overvoltage Relay—120 volts DC (USAF Spec. 32652, Type E-3)




Generator Field Relay—120 volts DC (USAF Spec. 32655, Type M-3)



External Power Relay—250 amp, 120 volts DC (Can break 2500 amps, 120 volts)



Reverse Current Cutout—600 amp, 28 volts (AN3025-2)



1st Starter Relay—28 volts (AN3391-1)



Overvoltage Relay—28 volts (USAF Spec. 32591, Type E-2)

the Hartman Electrical Mfg. co.
MANSFIELD, OHIO



The Sky is Filled with Aircraft using

REFRASIL

High Temperature Insulation (To 1800° F)

These (not illustrated) also Use Refrasil Insulation

DOUGLAS D-558 (Skystreak) · BOEING B-47 · MARTIN XB-48
CHANCE VOUGHT F6U · CONVAIR XB-46
DOUGLAS X-3D (Skynight) · NORTH AMERICAN B-45 (Tornado)

90% of Jet Aircraft Manufacturers Choose REFRASIL

TO MEET ALL REQUIREMENTS OF SPEED OR SIZE

An amazing figure? Not when you realize that Refrasil, with a nominal thickness of only 3/16 inch is far more flexible and lighter in weight than standard high temperature insulation materials. Yet Refrasil will withstand sustained temperatures up to 1800° F., flash temperatures up to 2400° F, with absolutely no breakdown . . or even discoloration.

Blankets, boots and covers, encased in stainless steel or other metal-foil material, can be preformed to your precise specification, to fit your every high-temperature aircraft insulation need

Whatever your 'high temp' insulation problem may be, our 'heat-wise' Engineering and Research staff can help you solve it with Refrasil. Call them in—any time or write the factory for insulation facts


REFRASIL PATENTED U.S.A. Pat. No. 2 491 761 Pat. No. 2 580 092


BE 'HEATWISE'—THOMPSONIZE!


The H. I. THOMPSON CO.
Dept. A, 1733 Cordova Street
Los Angeles 7, Calif., U.S.A.

Eastern Rep
Fred W. Muhlenfeld
5762 Maplehill Road
Baltimore 14, Md.

In Seattle
J. Lawrence Larsen
3608 Schubert Place
Seattle 22, Washington







cases the margin below buffeting limit is approximately .1 Mach.

▶ Comparisons—We are now in possession of sets of curves for each airplane and are in a position to make a comparison. Fig. 4 shows range versus speed curves for the three combinations at 20,000 ft. For lower speeds, the reciprocating engine has a slightly greater range than the turboprop. At 365 mph., the range for both engines is equal, but beyond this speed the range of the reciprocating engine decreases rapidly and stays below that of the turboprop.

The curve for the turbojet is considerably below the two others. The maximum attainable speed for the turboject, however, is some 90 mph. greater than that of the turboprop.

Fig. 5 gives similar curves for 30,000 ft. The turboprop curve is located entirely above that for the reciprocating engine, while the curve for the turbojet has shifted upwards slightly. For a range of 3000 miles, the cruising speed of the turboprop is some 50 mph. faster than that of the reciprocating engine. The maximum speed of the turbojet is approximately 90 mph. faster than that of the turboprop, but for a much lower range.

Fig. 6 shows the comparison at 40,000 ft. The curve for the turboprop has very definitely assumed the highest



NOW...AND IN THE FUTURE
Curtiss Electric Propellers and Turbo-Props

Since the days when propellers were carved from wood by hand, Curtiss Propellers have paced aircraft propulsion progress.

The first all-metal propeller was a Curtiss product. Curtiss-Wright pioneered the electric propeller . . and the first full-feathering propeller . . . perfected and proved the hollow steel blade . . . introduced automatic synchronization . . . developed the reversible propeller now in universal military and commercial use.

Today, Curtiss Electric Propellers are the standard of quality wherever aircraft fly. They equip the modern post-war transports of the world's leading airlines . . . and superbombers like the Air Force B-36. In over 40 different aircraft models now in operation, Curtiss Electric Propellers have built an international reputation for dependability, durability and flexibility of electrical control.

Against a background of demonstrated performance, Curtiss-Wright faces the dawning era of trans- and super-sonic speeds well prepared to anticipate and meet new trends in military and commercial aircraft . . . to maintain the leadership it has established.

In the same Curtiss-Wright laboratories where present production types were conceived in advance of their time, new propellers have taken shape. Propellers of the future, built by Curtiss-Wright, are being flight tested at speeds up to 600 miles per hour. Turbo-props under development today will be ready when they are needed tomorrow. Every avenue of research is continuously being explored.

Curtiss-Wright propellers will play a major role in the conversion of current experimental aircraft developments into accepted practice. Meanwhile, Curtiss-Wright will continue to produce the propeller types required to maintain America's superiority in the air . . . time-tested Curtiss Electric Propellers of advanced design whose every feature has been proved. *Propeller Division, Curtiss-Wright Corporation, Caldwell, New Jersey.*

These leading Airlines use Curtiss Electric Propellers

BOEING 377 STRATOCRUISER	American Overseas Airlines United Air Lines
CONVAIR 240	American Airlines CATC (China) Northeast Airlines Swissair
DOUGLAS DC-6	American Airlines BCPA (Australia) Philippine Airlines SAS (Scandinavia)
LOCKHEED CONSTELLATION	Air France Air India BOAC (British Overseas Airways) KLM (Royal Dutch Airways) LAV (Venezuela) QANTAS (Australia) South African Airways
AERO SUD EST SE 2010	Air France

CURTISS WRIGHT



position at all speeds within the capability of the engine. The reciprocating engine and the turboprop attain their maximum range at the same speed of 410 mph. At 450 mph, the range of the turboprop, however, is some 1500 mi greater. For equal range, the cruising speed of the turboprop airplane is approximately 45 mph greater than that of the reciprocating engine.

The curve for the turbojet has again taken a slight upward shift, and gives practically the same range of 2000 mi. for speeds from 420 to 570 mph.

It is to be remembered that only existing design propellers were considered in the cases of the turboprop and reciprocating engine. The use of supersonic propellers will undoubtedly extend the speed of the turboprop.

▶ **Conclusions Drawn**—This study was conducted on an unbiased basis with no preference to any of the three combinations. While lacking generality the results correspond to a modern, medium size transport airplane which brings it into the scope of the problem now confronting the industry. The final choice of the type of powerplant to be used could, of course, only be made after detailed study of the economics of each case, together with relative reliability and other service problems proper to each type of engine. From a purely engineering point of view, however, definite conclusions can be drawn.

As we strive for greater speeds coupled with long range, and in the presence of ever-increasing competition, it appears that the reciprocating engine no longer offers an adequate solution. Its range drops very rapidly after 400 mph. The choice is, therefore, between the turboprop and the pure jet.

The turboprop powerplant at altitudes from 30,000 to 40,000 ft. offers any range between 2500 and 4500 mi at speeds of from 450 to 500 mph.

The pure jet at altitudes from 20,000 to 40,000 ft. covers the range between 1500 to 2000 mi at 550 to 580 mph.

For non-stop transoceanic and transcontinental flights the turboprop is, therefore, the answer. For shorter runs of 2000 mi., or below, the pure jet gives considerably higher speed.

To obtain greater range with the pure jet an amount of fuel considerably in excess of that assumed would be necessary, which would automatically lead to a much larger airplane. Pure jets are, therefore, confined to high speed, relatively low range flight until such time as engines with much more efficient fuel consumption are available.

One more point appears evident from this analysis. Unless jet transports are flown at speeds of from 550 to 580 mph, their use is unjustified because for lower speeds approximately the same results could be obtained with the turboprop with considerably less fuel expenditure. The aerodynamic design of the pure jet airplane must, therefore, be the most advanced, and it would be an error to build a jet propelled transport airplane of conventional design with straight wings.

The sudden burst of air transport activities in England where turboprop and pure jet transports are about to be put into service, makes it necessary for our industry to face the challenge. If we are to keep our air supremacy over the seven seas, it is imperative that the industry start without any loss of time to develop turboprop transport planes for fast, long range service, and pure jet transports for shorter range at still higher speeds.

RAF Control Knobs

To lessen the possibility of pilot error, all new planes designed for the RAF must have cockpit control knobs of standardized shapes readily identified by feel alone. Thus, no matter what type of plane a pilot flies he will know that a control knob of a particular form performs a particular function.

Shapes were selected following a series of trials by the RAF Institute of Aviation Medicine to find those readily recognized by feel alone. Some configurations chosen:

- **Flap control** will be a uniform-size sphere with small cylindrical projections on each side.
- **Supercharger control** will be a ¾-in. cube.
- **Mixture control** will be a disk with small pyramids on the rim.

Quick sight identification, by conspicuous color striping, will be applied to emergency controls, such as those for ejection seats or fire extinguishers.

Tests Lubricants

Aimed at eliminating the need for elaborate cold-room setups, a compact, "semi-portable" tester for checking low temperature operation of ball bearing lubricants has been developed by the General Electric Co.'s Schenectady Works laboratory.

The device is, essentially, a cooling chamber consisting of a large bucket accommodating a smaller bucket within it. Space between the walls of these two units houses dry ice.


The ball bearing is placed on a spindle in the inner bucket and rotated by a small electric motor, and a strain gage measures the tendency of the bearing's outer ring to move with the inner ring. If the test lubricant thickens from the cold, the inner ring does not turn freely, the gage registering a greater strain on the outer ring.

Bendix Brings You Motors that Really Meet AN-M-10a and AN-M-40



Bendix now adds a new series to its already famous line of small D.C. motors. Designed to meet the latest government specification—ANM-40, these motors, with specially shielded brush boxes and equipped with radio noise filters tailor made for each specific type, are guaranteed to be noise free within specification limits over the range from .15 to 20 megacycles for conducted noise, and from .2 to 156 megacycles for radiated noise. These limits are maintained throughout the required ambient temperature range of −55°C to +71°C. Light, compact, and highly efficient, these tiny motors are available in a wide variety of horsepower, speed and torque ratings. Send your detailed requirements to our Engineering Department. We will be glad to forward typical performance data and other engineering information.

When only the best is good enough, choose Bendix motors for:
- Actuator drives
- Recorder drive and take-up
- Servo mechanisms
- Fan and blower drives
- Band-change switching
- Stall-warning mechanisms



Dynamotors • Inverters • Convertors • D.C. Motors • Carbon Pile Voltage Regulators

RED BANK DIVISION of Bendix AVIATION CORPORATION
Red Bank, N. J.
Export Sales: Bendix International Division, 72 Fifth Avenue, New York 11, New York

EASTERN AIR LINES and TRANS WORLD AIRLINE Choose

new model Martin 4·0·4

pressurized, high-speed
AIRLINER

. . . and here's why

these great airlines have chosen this most advanced transport to

Modernize Their Twin-Engine Fleets

OPERATING ECONOMY! Martin 4-0-4 Airliners will offer maximum economy because of high revenue capacity, high cruising speed and low cost of maintenance. Fast ground loading will mean shorter stops because of such features as built-in loading ramp, efficiently arranged cargo compartments, fast taxi speed, high-speed underwing refueling. Originally designed for low cost maintenance, the 4-0-4's basic configuration affords the further improvements developed through actual airline experience.

PASSENGER APPEAL! Pressurized, air-conditioned, comfortably quiet Martin 4-0-4s will put passengers in the lap of luxury. Spacious interior, modern styling, large windows and seats . . . *plus* shorter trip times . . . mean more appeal for travellers, more traffic for airlines.

DEPENDABILITY! Martin 4-0-4 Airliners will have excellent low-speed flying qualities with higher cruising speeds and consequent economy because of efficient wing and flap design . . . and yet the 4-0-4 can be operated into and out of smaller airports, aiding the expansion of air travel. Built-in aerodynamic stability permits wide range of loading passengers and cargo. Thermal anti-icing, tricycle landing gear, convenient pilot compartment . . . contribute to reliable operation.

DESIGN WITH A FUTURE! Present structural and performance margins of the Martin 4-0-4 will permit gross weight, payload and power plant changes to meet future airline requirements without altering the basic configuration. For air coach service, the 4-0-4's passenger capacity can be increased from 40 to 48 or 53 seats. And the Martin 4-0-4 will be designed and stressed for conversion to turbo-prop engines . . . to substantially increase its operating speed and extend its useful life by many years.

The Martin 4-0-4 is the twin-engine airliner with a future . . . the *new* standard for speedy, dependable, economical twin engine fleet operation! THE GLENN L. MARTIN COMPANY, Baltimore 3, Maryland



Martin AIRCRAFT

Builders of Dependable Aircraft Since 1909

Properties of Tested Laminates

(77 F and 50 Percent Relative Humidity[1])

Type of laminate	Density (g/cm³)	Ply arrangement	Impact strength[2] (ft.-lb./in. of notch)		Tensile modulus of elasticity (10⁶ lb / in.²)	Tensile strength (10³ lb / in.²)	Flexural strength (10³ lb / in.²)	Compressive strength (10³ lb / in.²)
			Flatwise	Edgewise				
Low-pressure cotton-fabric phenolic	1.34	Cross	6.0	3.2	1.0	12	18	22
Low-pressure Grade C phenolic	1.23	Cross	6.6	3.3	0.8	9	16	19
High-pressure Grade C phenolic[3]	1.36	Cross	5.7	2.8	1.0	10	18	20
Grade C phenolic	1.34	Parallel	5.1	2.7			21	25
Rayon-cotton-fabric phenolic	1.37	Cross	17.6	6.6	1.9	32	34	25
High-strength-paper phenolic	1.42	Cross	4.2	0.8	2.6	30	33	19
Grade AA asbestos-fabric phenolic	1.50	Parallel	4.6	3.8	1.5	8	16	20
Glass-fabric unsaturated polyester	1.82	Cross	31.5	9.9	3.0	43	53	42


1 All strength values are for the lengthwise direction of the sheet.
2 The impact strength, flexural strength, and compressive strength measurements were made on 1/2-in thick material. The tensile tests were made on 1/8-in.-thick material.
3 Commercial sample

Temperature Data on Laminated Plastics

Studies at National Bureau of Standards reveal how properties are affected in −70 to 200 F. range.

Light weight and high strength of laminated plastics have stepped up the use of these materials in aircraft applications—in floors, bulkheads, ducts, propellers, wing flaps, radomes and other components—but little or no information has been available on their mechanical properties at high and low temperatures.

To establish such data, the mechanical properties of 8 representatives laminated plastics were evaluated at the extreme temperatures of use, by J. J. Lamb, Isabelle Albrecht, and B. M. Axilrod of the National Bureau of Standards in a project sponsored by the National Advisory Committee for Aeronautics.



In low- and high temperature tensile tests of laminated plastics, specimen, grips and strain gage were enclosed in temperature-controlled cabinet shown in place in hydraulic type testing machine. Window and armholes permit convenient handling of specimens and equipment. Selsyn motor links tensile strain gage and stress-strain recorder. A servicing unit supplys air of proper temperature for test enclosure.

Izod impact strengths, flexural, tensile, and compressive strengths; and elastic moduli were measured at −70, 77, and 200 F. One of the laminates studied was made of a polyester resin with glass-fabric reinforcement, while the others were of phenolic resins reinforced with asbestos fabric, paper, cotton fabric, and rayon fabric.

This work was part of the Bureau's continuing program on properties of these materials, which has included effect of simulated service conditions and resistance to fuel immersion. Other projects now under way deal with resistance of glass-fabric laminates to high temperatures (up to 600 F.), effect of low-temperature storage on impact strength, and influence of production variables in the manufacture of glass fabric laminates on the properties of the finished sheets.

▶ **Equipment Used**—Tests of mechanical properties were carried out in thermally insulated enclosures built specially for this purpose. And special jigs and fixtures also were required for flexural and compression tests.

For impact tests, a Baldwin-Southwark pendulum type Izod impact machine was used. Flexural, tensile, and compressive tests used two Baldwin-Southwark hydraulic universal testing machines located in a room where atmosphere was controlled at 77 F and





one of the 38
aircraft manufacturers
currently specifying

TINNERMAN
Speed Nuts*

Because:

1. SPEED NUTS weigh less than any other self-locking aircraft fasteners.
2. They're easier to install.
3. They're easier to remove for servicing.
4. Provide greater resistance to vibration loosening.

Thousands of SPEED NUTS*, SPEED CLIPS*, and SPEED CLAMPS* are designed specifically for aircraft applications, and provide lower costs, increased production, and improved product quality. For more details, phone your Tinnerman representative—he's listed in major city directories. Tinnerman Products, Inc., Cleveland, Ohio. Distributor: Air Associates, Teterboro, N. J.

TINNERMAN
Speed Nuts
*Trade Mark Reg. U. S. Pat. Off.



FASTEST THING IN aircraft FASTENINGS

50 percent relative humidity.

►**Tensile, Compressive Strengths**—The tensile strengths of the high-strength-paper, rayon-fabric, and glass-fabric laminates were found to be about three times those of the cotton-fabric and asbestos-fabric phenolics. In compressive strength the glass-fabric laminate was outstanding, at 77 F, its strength in the crosswise and lengthwise directions was 36,000 and 42,000 psi, respectively. Compressive strengths of the other laminates were about 21,000 psi.

It was found that the tensile and compressive strengths and moduli of elasticity of all the laminates increased at low temperature and decreased at high temperature.

Thus, for all laminates except the asbestos-fabric product, tensile and compressive strengths at 200 F were approximately half of the corresponding values at —70 F. In the case of the asbestos-fabric product, the changes in the strength values were much smaller.

Decrease in the tensile and compressive moduli of the samples with temperature was much greater from —70 to 77 F than from 77 to 200 F. Except for the high-strength-paper material, and overall changes were greater for the cellulose than for the mineral-type laminates. In general, the high-strength-paper, the asbestos-fabric, and glass-fabric products showed about the same variation of tensile and compressive moduli with temperature.

►**Impact Data**—The Izod impact strength values for the rayon-fabric and the glass-fabric laminates were much greater than for the other materials. It was also evident that the variation in impact strength with temperature was different for plastics having different types of reinforcement.


While the glass-fabric laminates decreased steadily in impact strength with increasing temperature, the cotton-fabric laminates exhibited increasing impact strength with temperature, roughly doubling their strength values between —70 and 200 F. On the other hand, the asbestos-fabric, rayon-fabric, and high-strength-paper laminates showed little variation in impact strength between —70 and 200 F.

►**Flexure**—In flexural properties the high-strength paper and glass-fabric laminates were superior, considering both flexural strength and flexural modulus of elasticity. An increase in flexural strength was noted for all the samples at low temperature; at high temperature a decrease occurred for all except the asbestos-fabric laminate, which showed no change.

The results of the Bureau's study indicate that the flexural properties of plastic laminates at high temperature are not a function of temperature only.



A Personal Lounge
for everyone



A double seat which reverses at the touch of a finger—that's the great new development by Weber for the comfort and convenience of airline passengers.


Now, any airline may offer "Lounge Comfort"... and not one lounge, but as many lounges as there are alternate reversible seats in the cabin. Beautifully finished both the 'Reversible' seats and their stationary "look-alike' companion seats are a masterpiece of engineering and design.

Production deliveries of these revolutionary seats are currently in progress. They will be used by T W A. and Chicago & Southern Airlines in their new Lockheed "Constellations." This is another "first" by Weber's staff of experts to supplement the "know-how" of progressive airlines. Why not place the enjoyment of Weber's "personal lounge" facilities at the disposal of your customers?


The new "Reversible" Seat is the latest development by Weber—the world's leader in the design and production of aircraft interior equipment.

For complete information on passenger seats, pilot and crew seats, buffets, galleys, lavatory equipment and other Aircraft Interior Equipment, write the Weber Aircraft Division today.

WEBER AIRCRAFT DIVISION
SHOWCASE & FIXTURE CO. INC.
2001 SLAUSON AVENUE
HUNTINGTON PARK CALIFORNIA







"BUMPER"

Giant missile born of teamwork!

Miles above the earth, the slender "Wac Corporal" rocket blasts loose from a modified German V-2, and attains a speed of 5,000 mph and an altitude of 250 miles—fastest and highest flight by any rocket. This most successful firing, from White Sands Proving Ground, New Mexico, February 25, 1949, gave scientists important information on little known phenomena of outer space and other data required in missile research.

The "bumper" rocket used in this spectacular test was developed by Army Ordnance working with General Electric, California Institute of Technology Ballistics Research Laboratories, and Douglas Aircraft Company. Structural design of the "bumper" and construction of the "Wac" were among the contributions made by Douglas.

This is just one of the many missiles projects, so vital to America's defense, to which Douglas engineers have been devoting their skill and energies since 1941.

DOUGLAS AIRCRAFT COMPANY, INC., SANTA MONICA, CALIFORNIA



DEPEND ON DOUGLAS

30TH ANNIVERSARY YEAR

but may be affected by further cure of the resin and loss of moisture content.

It was also apparent that the effect of high humidity in addition to an elevated temperature may be quite different from the effect of temperature alone. Thus, a severe loss in strength was noted for the high strength-paper and one low pressure cotton fabric laminate at 150 F. when the humidity was increased to 90 percent.

Copying Machine

Accuracy in fabrication of turbine blade manufacture is getting special emphasis at A. V. Roe Canada Ltd., Malton, Ontario, through use of a machine for reproduction of three dimensional surfaces to any scale. Designed by company technicians L. E. Marchant, V. W. Hall and J. O. Creek, the setup employs a master pattern larger than the article to be duplicated, and forging dies, reproduction masters and the like can be made by a reduction process so that the errors will be proportionally reduced to negligible size.

The machine consists of master table and a work table connected by a pantograph linkage governing the scale of reproduction. An overhead reduction lever carries a tracer wheel at its outer end and a ratio-related cutting medium, such as a grinding wheel, towards its fulcrum end.


The master pattern, usually made of plaster, is caused to move in two planes so that the tracer wheel contacts the entire surface during its passage, while simultaneously the work piece is being moved in a like manner, except that distance is in accord with the ratio prescribed by the pantograph. The third dimension, or rise and fall is transmitted from the tracer wheel to the cutter or grinding wheel by the medium of the overhead lever.

The machine now in use has a reduction ratio of 10 to 1 and the finished workpiece embodies only one tenth the error in the plaster pattern which, because of its large size, can be made with considerable accuracy and finish.

Sensitivity is a feature of the machine, the profile of a piece of "Scotch" tape on the surface of the plaster pattern being readily noticeable on the surface of the workpiece.

When completed, the workpiece is available as a master of accuracy for 1:1 quantity reproduction. Forging and coining dies, forging trim dies and punches, contour templates, and various other patterns in wood or metal may be produced. The machine can be adapted to produce enlarged copies of a master pattern where a proportional increase in the dimensional errors is of minor importance.


Why each month sees more airlines depending on Fenwal's positive fire detection



Cutaway view of Fenwal Fire Detector. 2-oz. hermetically sealed units comply well within CAA Technical Standard Order C-11 in accordance with Society of Automotive Engineers, Specification AS-401.

Further information on request

Employing unique THERMOSWITCH* thermostat, Fenwal Aircraft Fire Detection Systems provide fast, positive action and extreme accuracy over a long service life. That is why airline after airline has investigated and installed this constantly dependable protection — as a logical step toward maximum safety and efficiency in air transportation.



Exclusive single conductor loop circuit operates detectors even if circuit is accidentally broken. Even a double break only eliminates detectors located between breaks; other detectors remain independently operative . . . no averaging effects.

Unusual Simplicity of Operation and Installation

Surprisingly low in cost, Fenwal hermetically sealed Aircraft Fire Detectors offer no maintenance problem, require no bulky panels, relays or supervisory instrumentation. Easily installed by any competent mechanic. The single terminal allows no errors of connection.

Fenwal Incorporated, 124 Pleasant Street, Ashland, Massachusetts

Fenwal

TEMPERATURE CONTROL ENGINEERS

THERMOSWITCH*

*Reg U S Pat Off.

Aircraft Fire and Over-Heat Detectors

SENSITIVE . . . *but only to heat*

We have designs on YOUR ACTUATOR and MOTOR PROBLEMS

The exacting specifications for actuators and special motors for today's and tomorrow's aircraft pose many tough questions... but it's likely that you can find the answer through EEMCO. Our experience in designing and developing many hundreds of special types of electrical actuators and motors places at your command the "know-how" for producing units of remarkably ingenious design, compact construction, low weight, and high performance. We have the engineering personnel and facilities to handle the most difficult design and development assignments... and the manufacturing facilities to deliver the largest of orders with gratifying efficiency and speed. This is a matter of record with our many customers of note in the aircraft industry.
Put one of your current problems up to EEMCO

Typical EEMCO solutions of difficult Actuator and Motor design problems



STABILIZER ACTUATOR, Linear Type

Magnetic clutch, radio noise suppressors. Normal load 2500 lbs. Maximum load 8 000 static, 20,000 lbs. Stroke 7-1/2 in. Rate of travel .62 inches per second. Weight, 17 lbs. Non-jamming end stops.




FLAP ACTUATOR, Linear Type

Magnetic clutch and brake, radio noise filter, internal anti-jamming stops, auxiliary drive for manual operation. Normal load, 1800 lbs. Stroke, 5 1/2 inches. Rate of travel at normal load, 35 inches per sec. 28 volt d. c. Weight, 7 1/2 lbs.



EXPLOSION-PROOF HYDRAULIC PUMP DRIVE

Equipped with inline gear reduction Gearbox designed to keep acoustic noise level at an absolute minimum. For continuous duty operation with duty cycle varying from 1-1/2 to 5 H.P. load. Designed to operate for 2000 hours without maintenance. Operates in a vertical position. Weight, 28-1/2 lbs.



ROTARY ACTUATOR PACKAGE

Magnetic clutch and brake and gear reduction, radio noise filter, adjustable travel limit switches. Explosion-proof motor. Entire unit totally enclosed in box equipped with mounting bracket. Output RPM at 3 inch-pounds load, 2500. Weight, complete, 3 1/4 lbs.



MOTOR FOR VALVE ACTUATOR

Weight 11.7 ounces. 2 5/8" long by 1 5/8" by 1 13/16" 20 watts output at 18,000 RPM, intermittent duty. 28 volts d. c.




400 CYCLE BLOWER MOTOR

Capacitor type. Weight, 1 lb. 2 11/16" long, 2 3/8" dia. 10 c/2 watts output at 7500 RPM, continuous duty, 115 volts, single phase.



DOUBLE MOTOR POWER DRIVE

Small motor operates in conjunction with automatic pilot. Large motor used for manual control. Small motor—helical and worm gear reduction. Large motor—no reduction. *Outputs:* Small motor, 1/150 h. p. continuous, large motor, 3.3 h.p., 6 sec. duty cycle. *Output RPM*—driven by small motor, 1000; driven by large motor, 10 000. Radio noise suppressors. 26 volts d. c. Weight, 16 1/2 lbs.



Performance Charts and Design Drawings for the above units, and many others, will be sent to executives and engineering and design personnel making request on company letterhead. These prints illustrate solutions of difficult design problems. They may suggest answers to similar problems of your own. Additional prints, for permanent reference file, supplied as released.



1/2 HORSEPOWER EXPLOSION-PROOF MOTOR

For use on a bomb bay dolly. 24 volts d. c., 3-450 RPM, continuous duty. Weight, 17 lbs. Built to withstand exposure to the element.



GUIDED MISSILE CONTROL MOTOR


3/4 H.P., 25 000 RPM, 10 minute duty cycle. Weight, 2.9 lbs. Silicone insulated. High temperature materials throughout. Temperature on outside of case at end of run 250°C without damage to materials.

ELECTRICAL ENGINEERING and MFG. Corp.

EEMCO

4612 West Jefferson Blvd. Los Angeles 16, Calif.

DESIGN • DEVELOPMENT • LARGE-VOLUME MANUFACTURING



FLIGHT SIMULATOR's gimbal-frame, background, set up to contain characteristics of theoretical aircraft, responds to various commands transmitted from control board being operated by Dr. Albert C. Hall, of MIT's analysis and control lab.

Computer 'Flies' Aircraft Designs

An electronic-mechanical flight simulator has been developed to enable engineers to study flight characteristics and control systems of aircraft or missile designs prior to construction. It is stated that the device can save much of the cost and time involved in full-scale flight testing and also aid in improvement of the design.

The analogue computer, as it is technically known, was built in the Massachusetts Institute of Technology's dynamic analysis and control lab under the auspices of the Navy Bureau of Ordnance. The device is credited with already solving about 5000 intricate problems, each of which would have taken from 100-1000 hr. to work out manually using a desk calculator. One problem was handled in 20 sec.

▶**Operation**—Required are characteristics obtained from working plans and wind tunnel test data of a model of the craft being studied. An "electrical model" of the design is then set up by positioning electronic computer dials to represent weight, velocity, altitude, wing span, etc.

The question is then fed into the simulator by applying appropriate electrical signals through a control board. The answer is recorded on a chart in a matter of seconds. It is stated that the problem can be computed in exactly the time it takes the control process to occur.


If the aircraft or missile's performance on the flight simulator is recorded as unsatisfactory, wing or tail designs for instance, of the electrical model may be changed by simple adjustments of the computer dials until satisfactory behavior is noted. These changes may then be transferred to the plans before the actual craft is built.

▶**Construction**—Used are rapid calculating machines and a "flight table" on which the actual problems relating to flight stability are worked out. The table consists of an arrangement of gimbals, delicately suspended to incline freely in any direction and supported on an independent foundation to obviate vibration.

The gimbal frame, operated by high-speed automatic controlling instruments which carry out motions in accordance with electrically transmitted commands from the control board, is used to orient the automatic control system of a plane or missile design exactly as it would be tested in actual flight. The gimbal frame table rolls, pitches and goes through all the motions the craft would make in the air under stated conditions. Its motions are recorded on a plotting board, but may also be studied visually.

▶**Computer Designers**—Among MIT scientists contributing to the computer's development were Dr. John F. Blackburn, automatic controls and supervision of mechanical design of gimbal frame, Emery St. George, Jr., instruments and electronics, Charles M. Edwards, electrical computer, and Thomas F. Jones, Jr., simulator operation. Dr. Albert C. Hall is director of the dynamic analysis and physics lab.

Darnell Casters



& E-Z ROLL WHEELS

For light or heavy duty service Darnell Casters and Wheels are made *for* a long life of trouble-*free* usage, to protect *floors* and increase employee efficiency.

DARNELL CORP. LTD.
Long Beach 4, Calif.

40 Walker St., New York 13, N. Y.
36 N. Clinton, Chicago 6, Ill.

Improved

DC-4

ENGINE MOUNTING



New LORD Dynafocal Core Delivers Smoother Performance . . . . . Longer Service Life

The *new* LORD MR-26-1B Dynafocal Core is now available. DC-4 operators should specify this superior core for replacements. Here is why:

- Increased Service Life
- Increased Protection Against Metal-To-Metal Bottoming.
- Increased Passenger Comfort.
- Less Frequent Replacement.
- Lower Maintenance Cost.
- Directly Interchangeable With Those Now In Use.

MOUNTINGS FOR EVERY AIRCRAFT NEED

For any type of aircraft, or any aircraft application LORD can supply the Mountings you require. Our specialized knowledge and experience in Vibration Control is at your service

LORD MANUFACTURING CO.
ERIE, PENNA.

Canadian Representative
Railway & Power Engineering Corp. Ltd.

LORD
Engineered Vibration Control


NEW AVIATION PRODUCTS

Tiny Transformer

"The smallest standard audio transformer in the world" has been developed by the **United Transformer Co**, 150 Varick St., New York 13, N. Y., according to that firm.

Designated type SSO, unit is said to be specially suitable for use in aircraft and particularly in Navy emergency miniature transmitters. Small enough to permit 30 to fit in a cigarette pack, it measures .4 x .75 x .56 in. Weight is .28 oz.

Firm says "great dependability is provided . . . through the use of a molded nylon bobbin and non-hygroscopic insulation throughout." Transformers are vacuum impregnated to permit operation under high humidity conditions. Five stock types cover input, interstage, output and reactor applications. Designs are available for all types of low level applications requiring wide frequency range.







Small Fire Truck

Low-cost Jeep fire truck carrying 340 lb of dry chemical capable of extinguishing large-area liquid, gas, and electrical fires has been developed by **Ansul Chemical Co**, Marinette, Wisc., in two models.

Model 340-J1 has one hose, coiled in steel cabinet, attached to chemical tank. Model 340-J2 has two hoses. Hoses may be operated singly or together.

There are two Ansul 20 extinguishers mounted on Jeep's hood. All fire equipment controls may be worked from the driver's seat, and the chemical tank can be pressurized en route to fire.

Up to four men can be carried. Truck's curb weight is given as 3200 lb, overall width 67 in., height 69 in., length 127 in. Wheelbase is 80 in., tread 48½ in., and minimum road clearance 8⅝ in.

For Switch Jobs

Designed for many uses in aircraft electrical systems, three-position momentary contact switch (top) No 1AT1, offered by **Micro Switch**, Freeport, Illinois, is said to have special circuit arrangement not found in usual designs of momentary-contact double throw switches.

Unit consists of metal bracket which mounts self-centering toggle and two V3-type switches. With toggle at center, one switch is normally closed and other normally open, with jumper wire connecting common terminal of two switches.

Operating toggle lever to right closes normally opened circuit of one switch, while throwing toggle to left opens normally closed circuit of the other switch. Entire unit weighs about 2 oz. Switch is rated at 10 amp., 125-250v a.c., 10 amp., 28v d.c., non-inductive load, 6 amp., 28v d.c., inductive rating.

Small, hermetically sealed snap-action switch (bottom) No 1HS1, is designed for aircraft applications involving wide variance of temperature, extremes in air pressure, and hazardous atmospheres. Unit even may be operated under oil and other fluids.

Sealed case, or upper part of switch, is metal and filled with inert gas under pressure. Case is secured to plastic base. And secured to base are six screw terminals, arranged to avoid strain on glass beads which seal conductors into metal case.

This switch is single-pole, double throw type and is interchangeable with Micro Type Z "Pm" plunger basic switches, and can be used in all actuators and housings made for these plunger switches.

Current capacity, at any altitude at 28v d.c., is 25 amp., resistive, 10 amp., inductive.

Other characteristics of unit are: operating force, 16 oz. p/m 6 oz.; release force, 4 oz. min.; movement differential, .020 in., max.; pretravel, .065 in., max.; overtravel .010 in., min.; contact break distance, .036 in., min. Switch dimensions are 1⅛ × ¾ × 1⅝ in.



Tiny Chopper

Stated to have less than ¼ volume of d.c.-a.c. choppers previously available, "Mini-chopper" is 1.3-oz. unit represented capable of carrying out all functions of modulation, de-modulation, rectification and inversion of intelligence signals normally accomplished by electronic or electro-mechanical choppers.

According to maker, **Servomechanisms, Inc.**, Mineola, N. Y. "there is no loss in efficiency" despite the "outstanding reduction in size and weight" of unit.

Incorporated in tube the size of lipstick container, chopper is designed for installation in standard 7-prong miniature electronic tube socket and for retention with standard miniature tube retainer. It is said to have life expectancy of over 1000 hr. and is claimed to be suitable for use in airborne equipment.

National Aircraft Maintenance Corporation

A WINNING COMBINATION



Section of Maintenance and Test Dept., National Aircraft Maintenance Corp., Hangar No. 8, Newark, N. J. Airport. Shown are: Test Machines for Fuel, Vacuum, and Hydraulic Pumps (1); Fuel Booster Pumps (2); Aircraft Generators (3); Aircraft Heaters (4). Other Test Machines not shown include Hi to Tension Magnetos, and Propeller Governors.

Photo Courtesy of National Aircraft Maintenance Corp.

MR. WILLIAM J. CUNNINGHAM
President
National Aircraft Maintenance Corp.

"Greer built maintenance and test machines for aircraft and engine accessories have been used in our shops for the past two years. By the use of this equipment it has been possible for us to handle the large volume of maintenance and overhaul work which our schedule calls for."

Precision Testing of Aircraft Systems and Accessories is a matter of "Know How" and the right kind of equipment.

It's no wonder, therefore, that leading airlines and airport operators specify "Greer" when selecting maintenance and test equipment for hangar and field operation. They know that they are assured of precision equipment made by the sole manufacturer of a complete line of aircraft maintenance and test machines.

A typical example of such a winning combination is illustrated above. National Aircraft Maintenance Corporation is Greer equipped to meet any maintenance and test requirements.

Write or phone today for our complete catalog.

OTHER GREER TEST MACHINES FOR

Lubrication Systems • Electrical Systems • Synchronizer Systems
Hydraulic Systems • Vacuum Systems • Fuel Systems • Propeller Governor Systems

YOUR SYMBOL OF SERVICE

GREER
HYDRAULICS INC.
454 EIGHTEENTH ST., BROOKLYN 15, N. Y.

AIR FORCE CONTRACTS

February Awards Top $70 Million

Curtiss-Wright highest contractor for month, and its B-36 propeller order is largest single contract.

Air Force contracts awarded in February totaled approximately 580, valued at about $73 million, the lowest figure in several months. Curtiss Wright Corp was top contractor receiving orders aggregating $16,248,176

CW's largest single contract, $11,-$16,559 for B 36 propellers, was also the largest single award during the month. A $3,770,541 order for Wright engines was the third largest single contract.

Boeing Airplane Co was in second place for the month with orders totaling $5,511,182 The order for the B-47C (AVIATION WEEK, Apr 17), $4,122,427, was the largest single February award made public

Most of the Air Force contracts during the month, 438, were let on a fixed price basis However, the greatest amount of money, $42,510,976, was involved in fixed price contracts with redetermination provisions USAF is still negotiating the majority of its contracts, in February 371 calling for expenditure of $65,802,570 Contracts let after advertising totaled 190, valued at $7,026,992 Ten awards totaling $109,144 were made during February by Watson Laboratories and contracts let by Cambridge Laboratories numbered 20, valued at $229,836

List of February contracts follows, with estimated completion dates indicated Contracts for $100 000 or more are in addition to those published April 10

$100,000 and Over

Beech Aircraft Corp, Wichita spare parts for T-7, T-11 and C-45 aircraft June, 1950 (two contracts) $1 160 205 $114 957

Bell Aircraft Corp., Niagara Falls N Y spare parts for H-13B aircraft, June, 1950, $371,541

Bendix Products div Bendix Aviation Corp., South Bend Ind, control assemblies May, 1951, $122 200

Boeing Airplane Co, Seattle Wash spare parts for B-29 and B-50 aircraft July 1950, $345,979, spare parts for B-26, B-17G, B-50 and C-97 aircraft, July, 1950 $715 - 129, training parts for ATC to be provisioned, Apr 1950 $300 000 modification of one B-47B airplane and installation of four J-35-A 23 engines, June, 1951, $4 122,-427

Canadian Commercial Corp, Montreal, spare parts for maintenance of C-47 and C-54-type aircraft June, 1950, $204,000

Cook Electric Co, Chicago, study of recovery systems for missiles and target aircraft, Mar, 1951 $200 000

Cox-Stevens Aircraft Corp, Mineola, N Y electric aircraft weighing kit, July 1950 $134 250

Curtiss Wright Propeller div, Curtiss-Wright Corp. Caldwell N J. installation and spare propeller assemblies, control blade assemblies and spare parts for B 36 airplanes July 1952, $11 816,559

Douglas Aircraft Co, Santa Monica spare parts for maintenance of C 47 and C-54-type aircraft, Feb, 1950, $397,340.

Eclipse Pioneer div Bendix Aviation Corp, Teterboro N J, spare parts for instruments June 1950 $125.000

Fairchild Aircraft div, Fairchild Engine & Airplane Corp, Hagerstown Md, spare parts for C 119-type aircraft Nov 1950, $1,455 000 spare parts for C 82 aircraft June 1950, $500 000 kits of parts required for compliance with Fairchild service bulletin June 1950 $136 618

Gerity Michigan Mfg Co., Adrian, Mich, payment of state and local real property taxes on plouer $24, Adrian Mich, Dec, 1950 $110 000

Goodrich, B F, Co Akron spare parts for wheels and brakes Jan 1951 $120 245 spare parts for B 45J aircraft June 1950, $232 400

Hackensack Cable Corp Hackensack N J, cable Aug 1950 $112,340

Linde Air Products Co, New York liquid oxygen and nitrogen and cascade oxygen and nitrogen June 1950 $140 174

Minneapolis-Honeywell Regulator Co, Minneapolis spare components for B 4 turbo regulator systems Feb, 1951 $118 - 118

North American Aviation Inc, Los Angeles, spare parts peculiar to T-6G, Feb, 1951 $350 000 increase in spare parts for F-45A aircraft, May 1951 $100 000 ; 102 kits for B-45 airplanes and data Feb, 1951, $141,275 spare parts for F 6, T-28 F-51 F-86, F 82 B-25 and B-45 aircraft, June 1951 $271 600 spare parts for F-6 and T-51 aircraft June, 1950 $1 572 000

Remington Rand, Inc Dayton visible filing cabinets, Apr 1950 $150 740

Republic Aviation Corp, Farmingdale N Y, spare parts for F-84 aircraft July 1950 $254 050 spare parts for F-84 aircraft, July, 1950 $515 513 spare parts for F 84 and F-47 aircraft, July, 1950, $203 - 200, spare parts for F 84 and F-47 aircraft, July, 1950 $382 300

Sperry Gyroscope div, Sperry Corp, Great Neck N Y spare parts for instruments June 1950 $100 000

Wright Aeronautical Corp., Curtiss-Wright Corp Wood-Ridge N J R-1300, R 1820 76B engines spare parts and tools Nov, 1951, $5,779 541

Less Than $100,000

AC Spark Plug div General Motors Corp., Flint, Mich, revision pages for technical data, May, 1950 $1524

Acadia Synthetic Products, Chicago, rubber sheet May 1950 $18 759

Acme Code Co, New York, publications, law books Mar 1950 $2553

Acme Infra-Red Co, Detroit infra-red oven and maintenance data Mar, 1950, $5720

Acme Lithe Plate Graining, Brooklyn N Y, lithographic plates Mar, 1950, $8905

Adams Mfg Eng Co, Huntington Park, Calif., pliers, Mar 1950, $3900

Adamson United Co, Akron, additional work in connection with installation of brake and wheel roll test machine, July, 1950 $26 927

Aero Service Corp, Philadelphia maps, Ft. Worth and Birmingham areas Apr, 1950 $7 103

Aero Supply Mfg Co, Corry Pa., aircraft bolts May 1950 $6251

Aerolr Corp, Greenwich, Conn, maintenance data May 1950 $3518

Aerquip Corp, Jackson, Mich aircraft hose Mar 1950 $7400

Air Associates, Inc Teterboro N J, Tinnerman speed nuts May 1950 $2138

Air Maze Corp, Cleveland, oil filters, Aug 1950 $2723

Air Products, Inc, Allentown Pa, modification of one A-1 oxygen generator, Apr, 1950 $9490

Air Reduction Sales Co, New York, kit—portable birl arc welding kit type AH-1, June 1951 $20 050 breathing oxygen June 1950 $9120

Aircooled Motors, Inc Syracuse N Y, emergency spare parts for O-235 3 engines used in H-13 aircraft June, 1950 $1080; emergency spare parts for O-425-0 engine installed in H-13 aircraft June, 1950 $10-000; O-425 1 engines for the YH-16 aircraft, June 1950 $94 309

Aircraft Fittings Co Cleveland elbow May 1950 $2979 hose elbows and unions, May 1950 $2940

Aircraft Products Co, Clifton Heights Pa., aircraft bolts, May 1950 $1225

AiResearch Mfg Co Los Angeles heater assembly May 1950 $1478

Airequipment Co, Burbank Calif, type P 1 aircraft maintenance stands July 1950, $54 747

All-American Airways Inc Wilmington Del modification of government-furnished airliner pick up unit Apr 1950 $4327

Allied Business Comm, Los Angeles, services of technical representatives Aug., 1950 $16 640

Allison div, General Motors Corp Indianapolis services of overseas technical representatives Oct. 1950 $84 400

American Auto Typewriter Co Chicago, mock-up and demonstrator trainer, July, 1950 $2300

American Blower Corp Dayton 85 each radar set blower Apr 1950 $1388

American Blower Corp, Detroit electric blowers June 1950 $6991

American Bosch Corp., Springfield Mass, maintenance and overhaul spare parts and/or subassemblies for magnetos on R-3350 engines July 1950 $2208

American Chain div, American Chain-Cable Co, York, Pa cotter pins May, 1950, $5570

American Chronoscope Corp, Mt Vernon, N Y study of required instrumentation for test and maintenance of aerial and ground photographic May 1950 $16 000

American Flex Couplings Co Erie Pa., aircraft accessory power transmission shaft, Dec 1950 $10 138

American Gas Accumulator Co, Elizabeth N J 60 each time delay relay, Apr, 1950 $1575

American Hair and Felt Co, Chicago, felt Sept 1950 $43 420

American Machine Foundry Co Brooklyn N Y assemblies for AN TPS-10 antenna July 1950 $27 820

American Phenolic Corp, Chicago, receptacles Feb 1950 $2067

Anderson-Bolds Inc, Cleveland electric oil tempering furnace May 1950 $1690.

Ansco div General Aniline Film Corp., Binghamton N Y, photographic film, Apr, 1950 $3470

Arbrko Webbing Co Pawtucket R I, parachute webbing July 1950 $4160

Armour Research Foundation, Chicago, research on the physical and electrical properties of fuel samples Aug, 1950 $2442

Aro Equipment Corp, Bryan, Ohio, anti-G valves Dec 1950 $4990

Asserlole Aircraft Tool Mfg Co, Hamilton Ohio oil free air pump Jan, 1951, $39,-057.

Associated Co., Wichita, aircraft clips, May 1950 $70 210

Associated Engineers, Inc, Ft. Wayne, Ind design and manufacture of one lofting machine Mar 1951 $10 321

Avia-Lite Battery Corp Toledo aircraft storage battery 24 v. 34 amp., dry, charged, Mar., 1950 $77,243

WINGS THAT SERVE AT PHILADELPHIA INTERNATIONAL AIRPORT

Esso


THE FAMOUS WINGED ESSO OVAL *means dependable Esso Aviation Products teamed with the efficient, round-the-clock aircraft service of* **WINGS, Inc.** *at Philadelphia International Airport.*



IDEAL FOR PRIVATE AND EXECUTIVE aircraft (no landing fee), the up-to-date radio, weather, lighting and beacon facilities you find at this modern airport mean easier, safer landings at Philadelphia.

AND AVAILABLE 24 HOURS A DAY at International are the maintenance crews of Wings, Inc — who combine expert service with high-quality Esso Aviation Products for your better flying

PROVED BY MORE than 40 years of actual flying, backed by continuing research in one of America's largest and most modern aviation petroleum laboratories, Esso Aviation Products are *famous* for dependable performance!



MAP LEGEND

1. Control Tower, Beacon Domestic Terminal, Restaurant, Taxi Stand, Post Office, Emergency Station
2. WINGS, INC Office, Hangars, Maintenance and Repair Facilities, Pilots' Lounge
3. Air Park and 'T' Hangars Refueling Area for Visiting Private Aircraft Famous Esso Aviation Products available



MODERN EQUIPMENT MEANS SPEEDY SERVICE at this Wings, Inc refueling pit Here Wings, Inc President Guy Millet (center) discusses aircraft maintenance with Operations Manager Joe Trapuzzano while a Beechcraft is being serviced for take-off by line boy James Duffy

Esso

AVIATION PRODUCTS

SOLD IN: Maine, N. H., Vt., Mass., R. I., Conn., N. Y., N. J., Penna., Ohio, Del., Md., D. C., Va., W. Va., Ky., N. C., S. C., Ga. Fla. Ala. Miss., Tenn., Ark., La., Texas.

The AVRO Jetliner — America's First Jet Transport



more passengers . . . fewer aircraft

In presenting the AVRO Jetliner for consideration by airline operators in the medium-range field AVRO Canada is sincerely aware of the responsibility it must assume in the introduction of this new and dynamic medium of *Jetflight*.


Facts and figures about the Jetliner's performance, carefully acquired during the past eight months, merit immediate attention by interested operators. They will be agreeably surprised about the economic advantages of the Jetliner. Their flying customers will be even more pleased with the quiet, restful, vibrationless comfort of Jetliner flight. Pilots, crews and maintenance personnel will find their duties and work simplified.

AVRO Canada is prepared to submit studies of Jetliner application which will show how its high cruising speed can improve schedules and influence the flying habits of this generation.

A. V. ROE CANADA LIMITED

MALTON, ONTARIO

AVRO CANADA



MEMBER OF THE HAWKER SIDDELEY GROUP

Aviaeo Mfg. Co., Los Angeles, design study of, and 3 each, constant speed drive transmissions, Feb., 1951 $59,959.

Barber-Colmae Co., Rockford, Ill., meter and valve assembly, Apr., 1950 $4000.

Beaumont-Crandall, Inc., Kansas City Mo., aircraft covers June 1950, $6642.

Beech Aircraft Corp., Wichita, C-45, T-7 and T-11 aircraft spares, June, 1950, $85,-918.

Belknap Hardware Mfg. Co., Louisville, battery clip 20, 29, 50, 100, 200, 300, assp., insulated negative clip Apr., 1950, $24,053.

Bell and Howell Co., Chicago, photographic magazines, Mar., 1950, $8188, miscellaneous photo equipment, June, 1950, $41 $84.

Bell Aircraft Corp., Buffalo, N. Y., conversion kits of parts for 800 hp engine conversion Apr., 1950, $17,836.

Bell Aircraft Corp. Niagara Falls, N. Y., spare parts for YH-13 and H-13 aircraft, June, 1950, $2077.

Boeing Airplane Co., Seattle, Wash., 60-day extension and an additional 180 hr accelerated flight test program on B-50D airplane Mar., 1950 $48 929.

Bendix Aviation Corp., Pacific div., N. Hollywood Calif., technical data, May, 1950 $18,539.

Bendix Products div., Bendix Aviation Corp., South Bend Ind., emergency procurement of fuel injection and carburetor spare parts June, 1950, $75,000 replacement parts for wheels and brakes and wheel and brake assemblies, July 1950, $64,903; developmental and test of a new-type shock absorber incorporated with a 30 x 7' 7" sled wheel, Dec., 1950 $39,000; technician services, June 1950 $96,769; temperature drop tests with spin up of an F-84 main landing gear strut July 1950 $27,300.

Bendix Radio div., Bendix Aviation Corp., Towson Md., factory familiarization training Mar., 1950 $2478.

Berkeley Scientific Co., Richmond, Calif., meter timer, interval and decoder, Sept., 1950, $28,143.

Blackhawk Mfg. Co., Milwaukee, Wisc., spare parts for hydraulic jacks, Oct., 1950 $3283.

Boeing Airplane Co., Seattle Wash., spare parts for YC-97 aircraft, July 1950 $29,000; kits for portable air pump assemblies fabricated in accordance with AMC sketch SK-2-4490 for AEC for special weapons testing, May, 1950, $13,229; special instrumentation of B-50D airplane 49-294 for SAC for special flight testing, Mar., 1950, $13,257; flight tests and study to determine means of reducing aileron control forces on B-50 airplanes, Feb., 1950 $22,144.

Boice-Crane Co., Toledo, saw band metal cutting, Mar., 1950, $3899.

Bone Engineering Corp., Glendale, Calif., bench, portable, electrical aircraft instrument repair, Sept., 1950, $6628; antenna assembly, June, 1950 $27,820.

Booz, Allen and Hamilton, Chicago, time-phasing study on production program for manufacture of guided missiles July, 1950 $10,000.

Bordon Corp., Danbury, Conn., ball bearing shaft, May 1950 $19,650.

Berrae Corp., Newark, N. J., actuator assembly July 1950, $17,174.

Brilhart, Arnold Ltd., Mineola, N. Y., plastic wedges, Mar., 1950, $3975.

Buhl Optical Co., Pittsburgh, lens assembly, June 1950, $7872.

Deresa of Federal Supply, Cleveland, storage cabinets Apr., 1950, $2949, desks, May 1950 $89,235, storage cabinets, Apr., 1950, $9734.

Burke and James, Inc., Chicago developing and processing tanks, Apr., 1950, $5144.

Burlington Mills, Burlington, Wisc., felt, May, 1950, $11,123.

Burlington Mills Corp., Greensboro, N. C., parachute webbing June, 1950, $13,069.

Burton Mfg. Co., Los Angeles, recognition light, June, 1950 $8703.

Bauer, R. G., Silk Corp., Paterson, N. J., nylon reinforcing tape, June 1950 $6242.

Camloc Fastener Corp., New York, fasteners, June, 1950, $5053.

Candee, Inc., Chicago, galvanized steel sheet, June 1950, $15,991; low carbon low alloy sheets July 1950, $91,939.

Carborundum Co., Niagara Falls, N. Y., abrasives May, 1950, $84,019.

Carnegie Institute of Technology, Pittsburgh metallurgical research, Dec., 1950 $40,000, research on the relativity of movement and rhythm, May 1951, $9289.

Cattie, Kenneth, Urbana, Ohio, push rod tool, housing, installing and aligning, Mar., 1950, $1180.

Celanese Corp. of America, New York, plastic sheet, May, 1950, $5899.

Century Ribbon Mills, Inc., New York, reinforcing tape May 1950 $1782.

Champion Spark Plug Co., Toledo, maintenance and overhaul spare parts for ignition equipment, June 1950 $1295.

Chandler-Evans div., Niles-Bement-Pond Co., Hartford, Conn., valves and bearings June, 1950 $1179.

Chase Chemical Co., Newark N. J., photographic chemicals Apr., 1950, $2080.

Chicago Aerial Survey Co., Chicago photographic kits, May 1950 $12,382.

Chicago Cardboard Co., Chicago, photographic mounts, Mar., 1950, $1723.

Clark Metal Products, Inc., Fairfield Conn., plug, engine cylinder dehydrator Feb., 1950 $18,312, dehydrator plugs May 1950 $43,928, dehydrator plugs, May 1950 $51,650.

Collins Radio Co., Cedar Rapids, remote tuning assembly for radio compass Aug. 1950 $40 819.

Consolidated Engrg. Corp., Pasadena Calif., repair and modernize one recording oscillograph and repair and modernize 14 galvanometers July 1950 $5980.

Consolidated Vultee Aircraft, San Diego 165 additional rombusters Mar., 1950 $7053.

Continental Aviation and Engrg. Corp., Detroit, engineering services and technical assistance for testing jet engines used in model XQ-1 target missile, June, 1950 $9999.

Continental Motors Corp., Muskegon, Mich., spare parts for O-180-1, 0-295-1 and O-470-7 engines installed in L-19A, L-16B and L-17 aircraft, June, 1950 $28 900.

Coogan Co., N. Hollywood, Calif., filter assembly June, 1950 $1140.

Cook Electric Co., Chicago pressure warning switch assembly, selling switch assembly, pressure emergency fuel July 1950, $13 535.

Cooper Precision Prod., Los Angeles, aircraft bolts, May 1950 $1272, aircraft bolt Apr., 1950, $1194.

Cornell Aeronautical Lab., Buffalo, investigation of rain erosion resistance properties of plastic materials July, 1951 $29 002, research on lateral stability and control in stalled flight Feb., 1951 $85,177, engineering services in the problem of static pressure research Feb., 1951, $75 797, instrumentation of F-80 aircraft, Dec., 1950 $77,759.

Crockett Mfg. Co., Los Angeles, aircraft pins May, 1950 $1051.

Curtiss-Wright Propeller div., Curtiss-Wright Corp., Caldwell, N. J., propeller control parts for B-50D series airplanes Aug., 1950, $10 044, propeller assembly for B-36D one spinner assembly and one complete set of propeller controls Mar., 1950 $18,705, adaption of model C746S-18 propeller to T-31 power plant, Aug., 1950, $23 977.

Dmais B. G., Co., Dayton, labor and materials to perform various maintenance services for engineering division, May, 1950 $10 000.

Darleon Chemical Corp., Baltimore, dehydrating agent, Feb., 1950, $1300.

Dayton Aircraft Products, Inc., Dayton, type B-4 hydraulic aircraft jacks, Oct., 1950 $81,239.

Dayton Supply Tool Co., Dayton, benchwork laminated hardwood and metal top, Aug., 1950 $36,273.

Delco Products, div., General Motors Corp., Dayton, motor assembly, June, 1950 $9710.

Delron Co., Los Angeles, nuts, June, 1950 $17 150.

Design Fabricators, Inc., Dayton, mockup and demonstrator trainers, May, 1950, $1880.

Delrex Corp., Detroit, spray booth floor, Mar 1950 $2145.

Detroit Diesel Engine div., General Motors Corp., Detroit, Mich., generator, Mar., 1950 $24 338.

Deolgeh Co., Los Angeles pipe fittings, May 1950 $5815.

Denil Cincinnati Co., Cincinnati furnace aluminum gas melting furnace, brass gas melting Apr., 1950 $3867.

Douglas Aircraft Co., Santa Monica, Calif., icensing tabulator, May 1950 $10,720, spare parts for maintenance of B-29 aircraft for Air National Guard Mar 1950 $20 000 spare parts for maintenance of Air Force Reserve B-29 aircraft Feb., 1950 $2300, spare parts for maintenance of Air Force Reserve C-47 aircraft Feb 1950 $49,000.

Dynamic Air Engrg., Los Angeles fan assembly Mar., 1950, $4901.

Dzus Fastener Co., Babylon N. Y., cowling fastener May, 1950 $2624; fasteners Mar 1950 $1702.

Eastman Kodak Co., Rochester N. Y., photographic paper (General Expenses Marine) Apr., 1950 $9272, photographic film (Aviation Navy) May, 1950, $8442, photographic chemicals Apr., 1950 $28,954, print straighteners Sept., 1950 $8749, photographic film paper and plates (General Expenses) Mar 1950 $1103; photographic paper and film (Aviation Navy Maint. Bur of Ships Research Navy) Mar 1950 $3972 miscellaneous photographic equipment Apr 1950, $1570 photographic film (Aviation Navy) Mar., 1950 $2671.

Eaglman Samcel Co., Inc., Concord, N. H. spare parts for maintenance of crash fire trucks Sept., 1950 $40,489.

Eclipse-Pioneer div., Bendix Aviation Corp. Teterboro, N. J., indicators, position and humidity June 1950 $7226, voltage regulators July 1950 $42 414; pressure indicators and transmitters Aug 1950 $46 267, oil pressure transmitters July 1951 $85,295 accessories Eclipse S 1A A unit 1004-3 voltage electronic regulators Sept 1950 $10 000 pressure transmitters, Oct 1950 $47,645 pressure indicators Mar 1951 $51,713 landing gear position indicator type C-1, June, 1951 $51 252 extractor driver wrench spacer compressor etc Aug 1950 $3607 indicators and transmitters Nov 1950 $2240.

Elastic Stop Nut Corp of America, Union, N. J., aircraft nuts, Apr., 1950 $1916; aircraft nuts, May 1950 $1843.

Electric Auto-Lite Co., Toledo lamps-6V and 12V sealed unit service step HD lamp Apr., 1950 $2899.

Electrical Engrg-Mfg Co., Los Angeles technical data May, 1950 $1991.

Electro Impulse Laboratory, Pistcutown, N. J., standing wave indicator Apr 1950 $17 460.

Electro Tec Corp., Little Ferry N. J., gaskets engineering reports and engineering data Feb 1951, $3300.

Electronic Associates Inc., Long Branch N. J., plotting board model June 1950 $21 375.

Elitron Inc., Jackson Mich. maintenance communication spare parts Mar., 1950 $1270.

Elwood Foifero Works, Indianapolis, printer assemblies, Apr., 1950, $44,799, miscellaneous photographic equipment, Apr 1950 $2989.

Engelhard, Charles, Inc., East Newark N. J., temperature bulb, Aug., 1950, $5122.

Fafnir Bearing Co., New Britain Conn bearings, Mar., 1950 $1092.

Fairchild Aircraft div., Fairchild Engine and Airplane Corp., Hagerstown Md., spare parts for C-82 aircraft, June 1950, $4800.

Fairchild Camera Instrument, Jamaica, N. Y., miscellaneous photographic equipment, Jan., 1951, $17,871; filter assembly and lens assembly Sept., 1950 $3999 140 each indicator subassemblies, July, 1950, $10 993.

Firestone Tire Rubber Co., Akron, aircraft casings, Feb 1951, $44,400.

Fogarty Electric Co., Cincinnati, additional work in connection with installation of electrical facilities, building No. 28, Apr, 1950, $9780; installation of electrical equipment, Sept. 1950, $37 858.

Fordham University, New York research on rigid type insulators, Aug., 1951, $54 078.


Frank and Worren, Brooklyn, N. Y., conduit assembly, rieg assembly, Apr., 1950 $3003.

Want proof* of HUFFORD efficiency?


* These five typical aircraft parts tell a story of Hufford savings. Each was formerly made on equipment commonly found in large plants. With the installation of a Hufford stretch-wrap forming press, parts were switched to the new machine in an effort to improve production and efficiency. The results speak for themselves.


Besides speed, accuracy and economy, numerous other advantages result with the Hufford system. Parts may be formed directly in the ST condition, eliminating heat treatment and refrigeration. Straightening, planishing, drop hammer operations and other corrective procedures are usually unnecessary. Material is uniformly stressed over-all. Yield strength is actually increased, and often ultimate strength is improved. Uniformity of pieces effects savings in hand labor and assembly time. *These are typical of the many ways Hufford stretch-wrap forming makes better airplane parts at lower cost.*

Whatever your forming problem, whether it involves extrusions or skins, investigate Hufford—the only machine with the exclusive stretch-wrap forming principle.


INTER DUCT NACELLE SKIN


INTER SCOOP DUCT SKIN


FUSELAGE FRAME


TAIL PIECE


PILOTS CANOPY FILLET

HUFFORD MACHINE WORKS, INC.
207 NORTH BROADWAY
REDONDO BEACH, CALIFORNIA
MANUFACTURERS OF STRETCH FORMING EQUIPMENT

Franklin Institute, Philadelphia research human frequency response Apr... 1951 $03 457

Fyr-Tyte Co., Dayton, fire extinguisher, June 1950 $2025

Gardner, Inc., Cincinnati machine key duplicating automotive, July 1950 $2103

General Electric Co., Dayton instrument control relay switch percentage differential—time overcurrent, June, 1950 $1237

General Electric Co., Schenectady N Y, nut and retainer assemblies June 1950, $4447; revisions of handbook data, May 1950 $5545; spare parts for turbos and turbo regulators July 1950 $44,000 spare parts for supercharges and turbo regulators June 1950 $25,000 spare parts for fire control systems of the B-29 B-50 and B-36 airplanes Jan... 1951 $64,552 position indicator type A-7 July 1951, $27,232 position indicator and position transmitter July 1950 $4958 technical data covering thermocouple tail pipe temperature and radiator Aug... 1950 $4540

General Electric Co., Syracuse N Y, 40 inch wave guides GE type July 1950, $90,000 15 each motors Dec, 1950 $5400

General Electric Supply Corp., Dayton spare parts for F-5 F-7A and F-2 and F-2A trailer, June 1950 $20,840 extension-cord 2 conductor 18 AWG type SJ cable Mar... 1950 $2802 plugs Mar 1950 $1965

General Lamps Mfg Corp., Elwood, Ind. lamp assembly Mar 1950 $1426

General Radio Co Cambridge Mass, generator—standard signal May 1950, $1225

Georgia Institute of Technology, Atlanta, services research on development of twist on raven orlon and nylon Sept. 1950, $10,910

Germanow, Simon Machine Co Rochester, watch crystals Mar 1950 $2076

Gilfillan Bros. Inc., Los Angeles, services of field engineer Mar 1950 $1953, electrical-indicator May 1950 $4033

Globe Wernicke Co., Washington, D C, bookcase bases and steel sections Apr, 1950 $23 485

Goodrich B F Co., Akron, spare parts for C-47 aircraft June 1950 $4730, nose wheels Dec. 1950 $24,228, nose wheels Sept. 1950 $7027 rubber matting May 1950 $7357; maintenance data May 1950 $1270 airplane tubes, Aug 1951 $4782 nose wheels and parts, Aug... 1950, $4719 wheels brakes spare parts, Apr 1950, $4538 aircraft casings, July 1950 $10,420

Goodyear Aircraft Corp., Akron, modification of Douglas C-54D stabilizer and rudder assembly for radar purposes, Apr. 1950 $16 543

Goodyear Tire and Rubber Co Inc, Akron wheels and brakes spare parts Dec. 1950 $40 651 brake assemblies Aug. 1950 $11,482 nose wheels Dec, 1950 $20,668 tail wheels Sept... 1950 $13,943, nose wheels Nov. 1950 $9947 46 x 6 wheels and strain gage study of 17 stress rest, July 1951 $26 036 aircraft casings, Jan. 1951 $13,264 aircraft casings Nov. 1950 $35,501 aircraft tubes, Nov. 1950, $4472

Gosiger C H, Machine Co., Dayton, band saws, Mar., 1950 $2823

Goyle George W Son Frankfort, Ky, adapters—aircraft May, 1950 $1817

Graf, V L, Co, N Bellimore Mich elbow and nipple May 1950 $1500 elbow May 1950 $6573 aircraft nuts Apr. 1950, $1123

Graflex, Inc., Rochester, miscellaneous photographic equipment June 1950 $16,988

Grand Machine Co, Detroit, aircraft belts May 1950 $1310

Greybar Electric Co, Inc, Dayton lamp assembly Feb 1950 $17,950

Great American Industries div Connecticut Telephone and Electric Corp Meriden plug May, 1950, $2569

Greer Hydraulics Inc, Brooklyn N Y, starter stand assembly proof brake type B-1 Mar 1950 $3960

Grimes Mfg Co, Urbana Ohio, fuselage light assembly, Apr 1950 $9948; 75 watt lamps and light assemblies aviation, green, red yellow and white Mar, 1950, $1558

Hamilton Standard Propeller div United Aircraft Corp Hartford, Conn, modification of GFF model No. 24F60-73 B6521A-8 to 24F60-345 B6521A-8, Mar., 1950, $21-497, modification of internal oil control assemblies, Mar... 1950, $21,055, stress survey of oil system, June 1950, $6500

Hartman Electrical Mfg, Mansfield, Ohio, cutout, reverse current generator overvoltage relay, Oct... 1950 $44,700

Holloway Instrument Co., Denver, photographic papers and charts, Mar., 1950, $10,000

Holl Coil Corp, L. I City, N Y, tape gages inserters and extractors, Mar, 1950, $4361

Holldorfer Costellini, Dayton install systems study equipment, Aug, 1950, $15,500

Howill Rubber of Hoffnie div, Hewitt Robins Inc. Buffalo, hose gasoline thin wall July 1950 $27,843.

Biggins, William, Sons, Buffalo, dismantling and crating for shipment leading on carrier and blocking of certain government-owned machinery and equipment located at the plant of Playboy Inc, Tonowonde N Y Mar... 1950, $12 150

Hoyt Electrical Instrument Works, Cambridge Mass voltmeter-switchboard D C 0-150 V round flush MTG bakelite case, Apr... 1950, $1980

Hoffman Mfg Co, Dayton copperized 1 gal measures, June, 1950 $7010

Hughes Aircraft Co, Hollywood Calif, maintenance data, Mar 1950, $1020

Hughes-Simonsen Engrg Co Dayton, installation $000 PSI pressure compressor, Apr, 1950, $2700

Hulbert Mfg Co, Ashtabula, Ohio, floor-creeper, pivoting casters, Feb. 1950, $3780

Hunter Mfg. Co. Cleveland, spare parts for UH-0 heaters May, 1950, (two contracts) $2744, $1987

Hydrographic Office U S. Navy Dept., Washington, D C., publication, Mar, 1950, $7F10.

Ideal Lab Tool Supply Co, Cheyenne, Wyo., demonstrator trainer, Aug., 1950, $10,755

Illinois Glove Co, Champaign Ill. 2000 pair N 4 mittens large 6000 pair N 4 mittens medium June, 1950, $54 000

Interstate Engr. Corp, El Segundo Calif, nose gear strut assembly for B-36 aircraft, Feb. 1950, $12 571.

Jork-Reiche Precision Inds, Cleveland, generators regulators and panel assembly, Dec, 1950, $35,800, tachometer generator Dec, 1950 $20,639

Jorchs Aircraft Engine Co., Pottstown Pa services and materials to overhaul R 755-11 engines June 1950 $21,000

Johns-Manville Sales Corp, Cleveland, asbestos cloth Apr... 1950 $2272

Kaiser Frazer Corp., Willow Run Mich storage services in Bohn aluminum plant, Adrian, Mich., Dec. 1950, $10 632

Kas-Kel Electrical Co, Inc, New York cord-extension 50 ft. 2 conductor AWG type SJ cable Mar, 1950 $2221

Kearfoot Co, Inc, New York, technical data for wiper assembly, May 1950 $1902, spare parts for wiper assembly, Apr, 1950 $2383

Kiddr, Weller and Co, Inc., Belleville N J. drs extinguishers, July, 1950, $2300

Kinsey, E A, Co, Cincinnati, milling machine horisontal plain, Apr, 1950, $10,549

Kollman Instrument div, Square D Co Elmhurst, N Y, torque pressure gages, Oct., 1950, $5050, manifold pressure transmitters, June, 1951 $82 821, airspeed indicators, Sept. 1950, $82,624; airspeed indicator, pitot static types Dec. 1950, $91-923; transformer and test fixture, Apr, 1950 $1025

Kolman Electric Co., Bay City, Mich., transformer and fuse box, Mar., 1950 $1027

Laird Engrg Co, Charleston, W Va, thermometer test stand assembly, May, 1950 $2792

Lapine, Arthur S, and Co., Chicago, photographic chemicals, Mar, 1950, $2278

Lear, Inc., Grand Rapids, experimental flight indicator Dec, 1950, $14,958, modification of controls, Aug., 1950, $71,775; actuator assembly automatic temperature control spare parts and technical data, July, 1950 $86 754

Leland Electric Co, Dayton, inverter, laboratory equipment May 1950 $8163

Lewis Engineering Co, Naugatuck, Conn, temperature indicator type H-1 Mar, 1951 $15,757 temperature indicator, type G-6 May, 1950, $3423 bulb Apr, 1951, $2054, temperature indicator type K-7, May, 1951, $17 026, maintenance data Apr 1950 $1328 maintenance data, Apr, 1950 $1428 maintenance parts for temperature indicator, Apr. 1950 $1388

Liberty Mirror, Brackenridge, Pa mirror May, 1950, $2537

Linde Air Products Co, New York liquid oxygen and nitrogen June 1950 $21 336

Liquidometer Corp., L. I City, N Y, tank unit June, 1950 $1186

Lilico Industries San Carlos, Calif, magnetrons Apr... 1950 $9000

Lockheed Aircraft Corp Burbank Calif services of technical representatives, June 1950 $53 310

Lockheed Aircraft Service, Inc, Burbank, Calif spare parts for F-80 aircraft June, 1950, $20,57

Lycoming Div., Avco Manufacturing Corp., Williamsport, Pa., emergency spare parts for O-435-1 and O-435-11 engines installed in L-5 aircraft June 1950 $21,500

Machine Products Co, Wichita, extension of contract period maintenance contract at Wichita, Dec. 1949, $23 620

Magnolia Aircraft Products Co, Houston, breathing oxygen, Dec., 1950 $2341

Mallinckrodt Chemicals Works, St. Louis, photographic chemicals Mar 1950 $40 000

Management and Research, Inc, Primos, Pa., mock-up and demonstrator trainers Sept. 1950 $7600

Manhattan Lighting Equipment Co, New York fuse extractor post, Mar, 1950 $0222, oven electric pot electric, Apr, 1950, $8325

Federal Mogul Corp., Wenkesha, Wisc., spare parts for bearings, Oct., 1950 $14,150

Morinelle Glove Co., Inc., Marinette, Wisc, N-3 mitten 10,000 pair, July 1950, $27,200

Marlin-Rockwell Corp, Jamestown, N Y, ball bearings May 1950 $38 350

Mormon Products Co, Inglewood, Calif clamps, Apr, 1950 (two contracts) $2374 $0100

Marvel, A., Co., Caldwell, N J propeller balancer assemblies and stand, Sept., 1950 $76 94F

McGill Mfg Co Valparaiso Ind., bearings, May 1950 $15 290

McLean Development Labs Dallas, wing dly rack and gear type bomb ejectors, Sept., 1950, $28 314

McQuay-Norris Mfg Co., St. Louis, switch assembly, Apr 1950, $2084

Mead Aviation Equipment Co, Trenton, N J, parachute assembly, emergency sustenance kit June 1950, $00 600

Meriam Instrument Co, Cleveland automatic pilot assembly stand and compass assembly stand, May 1950 $4310

Metal Hose and Tubing Co, Dover, N J, gasoline hose, June, 1950, $46 434

Metal Trims, Inc., Youngstown, print washer Apr... 1950 $4230

Meyer Hugo Co., New York miscellaneous photographic equipment Mar, 1950 $1940

Michigan Ball-Nol Co... Inc., Detroit, nuts July 1950 $1871

Michigan Wire Cloth Co, Detroit, funnels, May 1950, $0000

Midland Co., Kansas City, crystal units, May 1950 $19,130

Midwest Research Institute Kansas City reports presenting theroretical studies of the effects of aspect ratio on straight and swept wing flutter, Aug. 1950 $4028

Miller William, Corp, Pasadena, Calif, galvanometers Apr... 1950 $1800

Minea Equipment division St. Louis spare parts for B-29 aircraft, Apr, 1950, $3000

Minneapolis-Honeywell Regulator Co, Minneapolis, B-4 turbo regulator system components, June, 1950 $3718; cabinstat and cap, May, 1950 $5000 autopilot spare parts Dec. 1950, $13 715, altitude controls May 1950, $12,553; automatic trim controls, June 1950 $13 515

Minneapolis-Honeywell Regulator Co, Philadelphia, potentiometer Mar 1950, $3340

Model Engr. Mfg. Co., Huntington Ind fuel system data plate, Apr... 1950 $2370

Monadnock Mills, S. Leandro, Calif, cowling fasteners May, 1950, $5035

Monterey Products Co., El Monte Calif

front end rear propeller cones, May, 1950, $3870

Mosely D and Co., Tulsa heater assembly Mar 1950 $10 250

Morse Instrument Corp., Hudson Ohio glass vertical viewfinder May 1950, $3056; printer assemblies Aug 1950 $78-775

Monsino Mfg and Service, Inc., New York relays May 1950 $4407

National Bureau of Standards, Washington D C development of production techniques in the manufacture of optical glass, Feb 1952, $20,000; crazy and crack resistance of laminated acrylic plastic research Feb, 1951, $12,000; construction of infrared pnashcard system, Feb, 1951 $10 000

National Lock Co., Rockford Ill. aircraft bolts May 1950, $2537

North American Aviation, Inc., Los Angeles services of technical representatives, June, 1950, $96 309; modification kits for F-86A airplane Sept. 1950, $75 918; spare parts for F-93 airplane Apr, 1950 $36,157; pneumatic gun charging system on YF-93A airplane and nose gun dring section, Apr, 1950, $8852; spare parts for T-6 and T-6J aircraft June 1950 $85 900

Northrop Aircraft, Inc., Hawthorne Calif., spare parts for YC-125A and B aircraft Nov 1950 $20 030; revised model specifications for the YC-125A and YC-125B aircraft, Dec., 1950, $1611

Nueker Engrg. Products, Yellow Springs Ohio repair and modernize control unit, six channal oscillograph May 1950 $1350

Nuli-Shel Co., Los Angeles aircraft nuts Apr 1950 (two contracts) $3180 $3180

OPW Corp., Cincinnati fuel servicing system nozzle nipple, Apr., 1950, $1124

Oak Mfg Co., Chicago switches, June 1950, $57 220

Octogon Process Inc., Brooklyn N Y photographic chemicals, Feb 1950, $17,726

Ohio State University Research Foundation, Columbus research guidance and planning program Mar 1952 $20,000; crew composition study, June, 1950 $0400; study drum failures and develop information to insure the use of suitable materials for handling fuming nitric acid Mar 1951, $75 010; coaduct research analysis and investigation in connection with the problem of the development of suitable techniques for use in development of infrared band pass detector, Mar., 1951 $10 040

Oman D W., and Sons Inc., Minneapolis, armature relay, Apr., 1950 $1057

Pacific Piston Ring Co., Los Angeles elbows, May 1950 $1423; aircraft elbows and lees May 1950, $1009

Pako Corp., Minneapolis print dryer and spares Jan 1951 $44 700; miscellaneous photographic equipment, Apr 1950 $4374; spare parts for photographic equipment Apr 1950, $2143

Parker Appliance Co., Cleveland hose adapters and unions May, 1950, $1800

Patterson Moos-Co., L. I City N Y., relay for experimental purposes May 1950, $5000

Pease, C L., Co., Chicago, blueprint filing section and bases, May 1950 $14,782

Pesco Products div. Borg Warner Corp Bedford Ohio fuel booster pumps June 1950 $4780

Peteor Research, Newark N J fire detectors Mar., 1951 $36 000

Phileo Corp., Philadelphia, domestic service field engineers, June 1950 $09 972; services of overseas and domestic field engineers Nov., 1949 $45 511

Phipps Products Co., Boston, dry powder fire extinguishing agent, Feb, 1950, $6500

Phoenix Trimming Co., Chicago parachute webbing June 1950 $42 823

Photoswitch, Inc., Cambridge Mass., switches for fire detector equipment Mar, 1950 $1087

Pierce Governor Co., Anderson Ind., gear drive shaft and governor assembly June 1950 $10 430

Pierson Elec Engrg Corp., Los Angeles, technical data—generator assembly Apr 1950 $1570

Pioneer Parachute Co., Manchester Conn., parachute suspension line, Feb 1951 $18 981

Pollak Engineering Co., Newark N J container assembly May 1950 $34 950

Price Electric Corp., Frederick, Md relays Apr 1950, $2360

Proleolessal Co., Chicago, gasoline-oil-can May 1950 $7700 gasoline cans and tanks Apr 1950, $12 132

Pryme William, Inc., Dayville, Conn., tee head pins July, 1950, $2713

Purdue Research Foundation, Lafayette Ind., adhesion of strain gages Dec. 1950 $5224

Pyrolator Products Inc., Newark N J, hydraulic filter elements, July 1950 $13 000

Pyle National Co., Chicago, receptacles, Mar 1950 $1082

RCA Victor div. Camden N J film recording equipment, Mar., 1950, $2050

Radiopinne Co. Van Nuys Calif., modification of OQ-19A wings to rotary launcher Sept 1950 $8013; oolss filter and kits Mar 1950 $1050 fabrication and installation of telemetering on OQ-19A, May 1950 $44 506; rotary launcher for O 19 aerial targets and spare parts June, 1950 $42,837

Ranger Aircraft Engines div. Fairchild Engine and Airplane Corp Farmingdale, N Y spare parts screw gasket kit case etc July 1950, $5487

Rano Machine-Tool Corp. Buffalo N Y aircraft bolts May 1950 $2221

Rannenhoff, N., Inc., Cincinnati, milling machine bench type horisontal, Apr., 1950, $4078

Rerordak Corp., Washington D C photographic film Mar 1950 $10 975

Reed Products Inc. Milwaukee high altitude fixing mask June 1950 $29 887

Reeves-Hoffman Corp. Carlisle Pa., crystal units Apr 1950 $1200

Reeves Instrument Corp. New York, polynomial plotter Nov 1950 $00 000

Republic Aviation Corp. Farmingdale N Y spare parts for F-84 and F-47 aircraft, July 1950 $90 342; spare parts for F 47 aircraft July 1950 $13 038 kits for rework of wings on F-84 aircraft Feb 1950 $12 456 services of overseas technical representatives June, 1950 $12 138; test stand Mar 1950 $2455 fire pilots ejection seat Feb 1950 $0040

Rhodes Lewis Co., Culver City Calif., modification of K 24 cameras and drawings Dec 1950 $10 700 jettisonable rocket launcher housing Sept 1950 $13 280 drawings and specifications for solenoid bomb and rocket arming Mar 1950 $3750

Richardson Bellows Reery Co. New York research on a ground accident report form, June 1950 $10 524

Rochester Mfg Co., Rochester N Y thermometer type C-17, July 1950 $2810

Rockford Clutch div Borg-Warner Corp Rockford Ill. spare parts for clutches and transmissions Sept. 1950 $2890

Rosen, Raymond, Engr Prod., Inc., Philadelphia, dynamotor commutators Mar 1950 $1560

Rutgers University, N Brucewirk, N J., research to obtain fundamental information on ternary systems of metal-ceramic bodies containing MGO-tia-NIO Apr, 1951, $17-000

Ryan Aeronautical Co. San Diego spare parts for C 74 aircraft June 1950 $23 102

S-K Screw Products Co., Los Angeles shaw tac nelon May 1950 $1403

Sanford Aircraft, Inc., Inglewood Calif., aircraft nuts Apr 1950 $1875

Schenell, F G., Rohber Co. Baltimore, aircraft casings Nov 1950 $2563

Schwien L N., Engraving Co., Los Angeles, spare parts for bank and turn indicators Apr., 1950 $7204 vertical gyro indicator June 1950 $37 733 turn and bank indicator type C-3 June 1950 $06 338

Scintilla Magneto div Bendix Aviation Corp Sidney N Y technical data for switch assembly May 1950 $1392 maintenance and overhaul spare parts for magnetos used on R-1300-1 and R-1820 78 engines May 1950 $2378; maintenance and overhaul spare parts for ignition equipment, Aug., 1950 $1027

Seaboard Electric Co., New York flashers, June 1950 $14 000

Seamless Rubber Co., New Haven, Conn., bladder assembly July 1950 $9960

Sierra Engineering Co, Sierra Madre Calif. anthropometric dummy Oct 1950 $19 746

Sikorsky Aircraft div United Aircraft Corp., Bridgeport Conn., spare parts for H-5 aircraft, July 1950, (two contracts) $18,410, $4062

Singer Sewing Machine Co., New York sewing machines with stands, Aug., 1950 $16 455

Skinner Purifiers div, Bendix Aviation Corp Detroit hydraulic filter element, July 1950 $00 000

Solar Aircraft Co. San Diego spare parts for F-80 aircraft, July 1950 (three contracts) $6270, $4500, $7201

Sonia Wind div. Stewart Warner Corp., Indianapolis bellows switch assembly, Aug., 1950 $12 186

Specialty Assembly and Packaging Co., Brooklyn, N Y., fabrication of B-7A switches, July 1950 $16 050

Spencer Thermanial Attleboro Mass., circuit breakers Mar 1950, $1243.

Sperry Gyroscope Co., div Sperry Corp Great Neck N Y., compass indicators V-2, Feb., 1951, $6500 compass indicators, V-4, Feb, 1951, $65 940 compensator, May, 1950 $0413; altitude controls turn generator assemblies Oct. 1950, $9005 handbook data for compass systems June 1950 $8374

Watson Lab

Network Mfg. Corp., Bayonne, N J three modified antenna pattern analyzer group AN-URM-18 June 1950, $4400

Photographic Products, Inc., Hollywood Calif., photographic cell for GCA evaluation Mar 1950, $10,007

Processing Equipment Corp., Hillside N J., one each high voltage regulator DC power supply, Aug., 1950, $10 000

Cambridge

Brojue Electronic Corp. New York oscilescopa railhods ray, oscilloscope features Apr 1950 $12 946

Commander Boston Naval Yard Boston services and materials necessary to fabricate one each antenna table, Apr, 1950 $1300

Consolidated Engrg Corp., Pasadena Calif., oscillograph June 1950 $7810

Dumont Allen B., Labs., Inc., Clifton N J., cathode ray oscillograph for 115v 60 cycle using 5CP1A cathode ray tube Feb., 1950 $8482.

Electra Mechanical Research, Ridgefield Conn one each infra-red measuring equipment Jan 1950 $2321.

Flader, Frederic Inc., N Tonawanda N Y., set recorder electrostatic AN-ASH-1 May 1950 $4500

Johnson, Weiler J., Inc. New York, research texts Feb, 1950, $3000; research texts Mar, 1950 $1405.

Kuno-Elliott Electronics Inc., Baltimore chassis metal plate tube type 2J67, Mar., 1950 $0020

Kennedy, D S and Co., N. Scituate Mass services and materials necessary for the voltr antenna Feb 1950 $1200.

Leeds and Northrup Co. Philadelphia bridge wheatstone anthony pattern, June 1950 $1352

New York University, New York research on atmospheric heat balance Nov., 1951 $20 000

Philco Corp. Philadelphia tube quadrature—quantizer May 1950 $4500

Polytechnic Research and Development Co. Brooklyn N Y termination fixed waveguide attenuator detector tuners adapter band tee etc. June, 1950 $6692

RCA Victor div. Camden N J tube storage, modified radechon May 1950 $1475

Raytheon Mfg Co., Waltham Mass., tube reflex klystron oscillator Apr, 1950 $1063

Steiner William F, Silver Springs Md equipment wall conductivity, model WI, June 1950 $5890

University of Denver Denver experimental investigation June 1951, $17 000


University of Saskatchewan, Saskatoon Canada basic research on the aurora and excitation processes in the upper atmosphere Jan 1952, $50 000.



save time

drive rivets with a hammer

As simple as hammering nails, you can save valuable time on sheet metal assembly jobs with Drive-Pin Rivets. There are no special procedures, no special tools with the Cherry Rivet Company's series of Drive-Pin *blind* Rivets



When installed, the serrated pin is driven into the tapered hole in the rivet. The surrounding section of the rivet shank is first expanded into the hole in the material, then the four sections of the protruding end of the shank expand to form a blind head at the back of the work.

Available in six diameters in steel (3/16", 1/4", 5/16", 3/8", 7/16", and 1/2") and three diameters in aluminum (3/16", 1/4", and 5/16") Grip lengths for material thicknesses from 1/16" to 1 1/16". Brazier-head and Countersunk (100°) head styles.


Drive-Pin Rivets are ideal for fastening light sheet to heavier sheeting or to framework where rigidity is great enough to withstand hammering. Driving the pin forces the head of the rivet against the top sheet. In turn, the top sheet is forced against the material beneath. The rivet forms a tight head on the blind side.

drive-pin rivet advantages

1. Installed by one man working from one side of the job.
2. An ordinary hammer is the only installation tool needed.
3. Requires very little preparatory instruction on the job.
4. Unusually good material thickness tolerance.
5. Hole-filling qualities are exceptional.

FIT YOUR FASTENING JOB EXACTLY

FIRST . . . look to Cherry Rivet Company's complete line of blind rivets and high strength structural bolts



CHERRY RIVETS, the standard of industry are available in more rivet types and a greater range of diameters—grip lengths—and material thickness tolerances than any other blind rivet manufactured and many other fasteners.

BLIND BOLT. A large diameter blind fastener designed for heavy sheet metal jobs where access to the job is blind or limited. Blind Bolts install fast they have strength characteristics equal to or greater than AN bolts.

LOCK BOLT A high-strength structural non-blind bolt to be used where shear and tension loads are high. Will not loosen in service. Size of installation saves time. You save considerable weight over nuts and bolts.

UTILITY RIVET A low-cost straight stem, mechanical blind rivet offering many advantages of the Cherry Rivet but manufactured to more liberal standards. They are installed with Cherry Tools equipped with adapters.

WRITE FOR DETAILS TODAY!

Cherry Rivet

CHERRY RIVET CO., 231 Winston St., Los Angeles 13, Cal.

Cherry Rivets are approved by Underwriters Laboratories, Inc., U S Navy, U S. Air Force and Civil Aeronautics Authority. (Cherry Rivets are patented)

Cherry Rivet Company, Dept D-116,
231 Winston Street, Los Angeles 13 Calif.

Please send me detailed information on Cherry Rivet Company products as checked here:

- ☐ DRIVE-PIN RIVETS
- ☐ CHERRY BLIND RIVETS
- ☐ LOCK BOLTS
- ☐ CHERRY VISEUR
- ☐ BLIND BOLTS
- ☐ UTILITY RIVETS

Name_____ Firm_____

Address_____

City_____ Zone____ State_____

Damon, Patterson Top Salary List

Airline payments to employes in 1949 generally higher than in 1948, with average rising from $3600 to $3800.

Airline paychecks during 1949 were fatter than ever before.

Both top executives and lower-bracket personnel shared in the salary gains. Average domestic airline employe received more than $3800 in 1949, compared with about $3600 in 1948.

Some carriers, such as Delta, Northwest and Western, made few increases last year in executive salaries. But even here the average pay for other employes of the companies rose substantially.

►**Damon, Patterson Lead**—Top salary of $62,500 went to two airline presidents last year—Ralph Damon, TWA, and W. A. Patterson, United Air Lines. Which of these was actually the top-paid executive in the industry is open to question.

Damon, who during 1948 received $40,000 as president of American Airlines, didn't take over as TWA president until Feb. 10 of last year. His contract provides for a $75,000 salary on a full-year basis.

In addition to his $62,500 salary, Patterson last year received $26,915 in indirect compensation, representing United's contribution toward the executive's retirement plan. Patterson also made $62,500 in 1948, but received only $5229 in company paid retirement plan contributions.

►**Other Presidents**—C. R. Smith was paid $50,000 as president of American Airlines last year, compared to the $60,000 he received as AA board chairman in 1948. T. E. Braniff, president of Braniff Airways, received $28,500 in salary plus $3256 in indirect compensation during 1949, compared with $24,000 plus $2925 in indirect compensation in 1948.

Salary of Capital Airlines President J. H. Carmichael rose from $27,500 in 1948 to $35,000 last year; Chicago & Southern President Sidney Stewart went from $25,416 to $30,000, Colonial President Sigmund Janas from $18,000 to $24,500, National President G. T. Baker from $26,250 to $33,750, Northeast President George Gardner from $16,850 to $17,900 and TWA Board Chairman Warren Lee Pierson from $50,000 to $58,749.

Slick Airways President Earl F. Slick received no salary as head of his all-cargo company during 1949, and the same was true of Harry R. Playford, president and board chairman of U. S. Airlines.

Other airline salaries last year, with 1948 payments, where available, in parentheses:

►**American**—O. M. Mosier, vp, $27,083 ($25,000); R. E. S. Deichler, vp, $27,000 ($23,333); L. G. Fritz, vp, $27,500 ($24,166); W. J. Hogan, vp-treas, $27,000 ($23,222); William Littlewood, vp, $27,500 ($25,000); C. W. Jacob, vp-secty, $22,500 ($19,038); Rex Smith, vp, $21,200 ($16,166); Amos Culbert, vp, $20,000 ($20,000); Glen Markl, asst. vp, $9429; W. H. Miller, asst. vp, $18,000 ($17,500); Carlene Roberts, asst. vp, $14,200 ($12,000); C. R. Speers, asst. vp, $16,000 ($16,334); P. G. Lantz, comptroller and asst. treas., $16,000 ($15,466); V. J. Long, asst. secty. and asst. treas., $13,000 ($10,000); W. L. McMillen, asst. secty. and asst. treas., $13,100 ($11,330); T. O. English, asst. treas., $10,200 ($9700); L. E. Glasgow, asst. comptroller and asst. treas., $10,075; C. H. Kilbee, asst. treas., $14,500 ($12,208); A. A. Paradis, asst. secty., $7500 ($6656); A. R. Bone, regional vp, $11,469 ($10,495); W. N. Bump, regional vp, $11,000 ($10,748); Walter Johnson, regional vp, $11,000 ($7852); Stanley Klug, regional vp, $12,000 ($2177), M. D. Miller, regional vp, $12,750 ($11,469).

Stockholders with more than 5 percent of American's outstanding capital stock as of Dec. 31, 1949: none.

►**Braniff**—R. C. Shrader, vp, $16,979 plus $1822 indirect ($18,000 plus $1007); Charles Beard, vp, $23,000 plus $1330 ($22,000 plus $1671); C. G. Adams, secty.-treas., $16,875 plus $1500 ($15,000 plus $1458); Hal Thurman, gen. counsel, $15,000 plus $998 ($13,000 plus $1005); John Walker, vp, $11,666; Oscar Crane, asst. treas., $6400 plus $622 ($7500 plus $625); R. L. Barrier, asst. secty., $7200 plus $428 ($6000 plus $550).

Stockholders with more than 5 percent: T. E. Braniff, 27.05 percent; the Braniff Foundation, 9.03 percent.

Average Airline Salaries

Carrier	1949	1948
American	$3907	$3603
Braniff	3522	3258
Capital	3921	3650
Chi. & So.	3713	3605
Colonial	3923	3552
Continental	3894	3573
Delta	3504	3161
Eastern	3727	3733
Inland	4348	3952
Mid-Continent	3551	3113
National	3708	3267
Northeast	3715	3539
Northwest	4235	3841
TWA	3936	3638
United	4128	3967
Western	4192	3764

* Domestic payroll as of fourth quarter of each year.

►**Capital**—R. G. Lochiel, vp-treas., $23,000 ($20,369); J. W. Austin, vp, $18,000 ($18,678); J. B. Franklin, vp, $18,000 ($15,700); R. J. Wilson, vp, $17,750 ($15,000); Hayes Dever, secty., $14,000 ($12,874); R. P. Wright, asst. treas., $10,578 ($9780); C. H. Murchison, chairman of executive committee, $10,050 (none).

Stockholders with more than 5 percent: none.

►**Chicago & Southern**—Carleton Putnam, board chairman, $20,000 ($20,000); Junius Cooper, vp, $18,000 ($18,200); William Arthur, vp, $11,278; Richard Maurer, secty. and gen. counsel, $12,806 ($12,000); Thomas Hambleton, treas., $7900 ($8400); Robert Scrivener, asst. treas., $8180 ($8160); Erma Murray, asst. secty., $4589 ($4680).

Stockholders with more than 5 percent: Carleton Putnam, 10.75 percent; L. M. Simon & Co., St. Louis, 12.62 percent.

►**Colonial**—Edward Ridley, vp, $10,899 ($9990); Alfred Hudson, vp, $10,066 ($9999); Francis Dykes, vp, $10,000 ($10,000); Sigmund Janas, Jr., vp, $10,999 ($9,196); James Germley, treas., $11,418 ($9166); Warren Cooper, secty., $7658 ($8375).

Stockholders with more than 5 percent: Sigmund Janas, 7.16 percent; Merrill Lynch, Pierce, Fenner & Beane, 5.23 percent.

►**Continental**—Louis Mueller, board chairman, none (none); Robert Six, president, $30,000 ($20,791 plus $15,000 indirect); C. C. West, vp, $10,000 ($14,166); R. G. Hansler, vp, $15,000 ($14,953); Joseph Uhl, vp, secty.-treas., $12,916 ($11,416); Ronald Kinsey, vp, $10,382 ($8858); Dorothy Rylander, asst. secty., $3966 ($3800).

Stockholders with more than 5 percent: Estate of W. R. Erhart, 20 percent; Louis H. Mueller, 7 percent.

►**Delta**—C. E. Woolman, president-general man., $24,000 ($24,000); C. E. Duik, board chairman, $12,000 ($12,000); Charles Dulson, vp, $10,000 ($14,000); Leigh Parker, vp, $18,000 ($18,000); L. F. Judd, comptroller and asst. secty., $10,000 ($10,000); M. S. Biedenharn, vp, none (none); Travis Oliver, treas., $12,000 ($12,000); C. H. McHenry, secty., $12,000 ($12,000); Catherine Fitzgerald, asst. treas., $4150 ($3400).

Stockholders with more than 5 percent: R. J. Reynolds, Winston-Salem, N. C., 22.78 percent; C. E. Woolman, 6.40 percent.

►**Eastern**—E. V. Rickenbacker, president, $35,000 plus $5561 indirect through directors' fees and retirement plan contribution ($35,000 plus $6301); Paul Braitain, first vp, $22,000 plus $4066 ($26,250 plus $5540); Sidney Shannon, second vp, $25,000 plus $2766 ($23,750 plus $2731); T. F. Armstrong, secty.-treas., $17,500 plus $2247 ($19,675 plus $21931); J. W. Moore, asst. secty. and asst. treas., $16,000 plus $1531 ($21,488 plus $1830); L. F. Arnold, vp, $17,500 plus $2025 ($16,470 plus $1750); M. M. Frost, vp, $32,500 plus $2162 ($21,875 plus $668); S. deJ. Osborne, vp, $22,500 plus $1763 ($21,975 plus $1606).

Stockholders with more than 5 percent: Merrill Lynch, Pierce, Fenner & Beane, 5.09 percent.

►**Inland**—See Western, which holds 97.2 percent of Inland stock.

►**Mid-Continent**—T. F. Ryan, III, board chairman, none (none); J. W. Miller, president-general man., $24,999 plus $731 indirect ($24,343); J. C. Collins, vp, secty., $9666 plus $282 ($10,567); J. A. Cunningham, vp, $13,000 plus $353 ($12,617); H. W. Coburn, vp, $10,999 plus $644 ($12,567); C. H. Calhoun, vp, $16,666 plus $324 ($19,458); W. L. Walker, treas., $9900 plus $117 ($8228); W. D. Kline, asst. treas., $5900 plus $89 ($5393); F. H. Carr, asst. secty., $4300 plus $140 ($4096).

Stockholders with more than 5 percent: T. F. Ryan, III, 20.08 percent.

►**National**—J. L. Morris, vp, $12,750; J. D. Crane, vp, $11,674 ($10,220); C. Kershaw, vp, $17,000 ($14,999); Waller Sternberg, vp since Sept. 6, 1949, $5642; R. E. Wieland, vp, $6300; J. M. Rosenthal, vp, $10,499; R. F. Foreman, secty., $10,125 ($6328); J. C. Brawner, treas., $11,124 ($9375); T. A. Prevost, asst. vp, $10,624 ($8378); F. E. Howe, asst. secty. and asst. treas., $7500 ($8003); W. F. Johnston, asst. treas., $6750 ($6180); H. C. Dobbs, vp, who resigned Aug. 2, 1949, $12,000 ($13,749).

Stockholders with more than 5 percent: G. T. Baker, 10.90 percent; W. R. Grace & Co., 17.4 percent.

►**Northeast**—Paul F. Collins, board chairman, none ($12,000); A. A. Lane, vp, $14,400 ($2400); Hamilton Heard, treas., $12,000; R. H. Herrnstein, asst. treas., $7800 ($7500).

Stockholders with more than 5 percent: Atlas Corp., 63 percent common and 98 percent preferred.

►**Northwest**—Croll Hunter, president and general manager, $45,000 ($40,000); L. C. Gletzbach, vp and asst. to pres., $17,000 ($17,000); E. I. Whyalt, exec. vp, $20,000 ($20,000); A. E. Floan, vp-secty., $17,000 ($17,000); K. R. Ferguson, vp, $24,000 ($18,000); R. O. Bullwinkel, vp, $18,000 ($18,000); L. S. Redstad, treas., $15,024 ($18,000); Frank Judd, res. vp, $15,000 ($15,000); D. J. King, res. vp, $17,000 ($15,860); Charles Stearns, asst. secty., $4498 ($9000); W. J. Elden, asst. treas., $10,600 ($10,600).

Stockholders with more than 5 percent: Merrill Lynch, Pierce, Fenner & Beane, 5.63 percent preferred and 4.02 percent common.

►**TWA**—E. O. Cocke, vp, $32,500 ($30,575); J. A. Collings, vp, $35,000 ($31,613); A. V. Casile, vp-treas., $26,400 ($25,400); C. E. Fleming, vp, $17,270 ($18,000); G. H. Clay, secty., $12,915 ($10,937).

Stockholders with more than 5 percent: Hughes Tool Co., 73.57 percent.

►**United**—Harold Crary, vp, $21,000 plus $2978 indirect representing retirement plan contribution ($16,500 plus $2902); J. A. Herlihy, vp, $32,500 plus $2526 ($30,000 plus $2417); R. W. Ireland, vp, $28,000 plus $2901 ($30,000 plus $2369); Hal Monrse, vp, $18,859 plus $1432 ($17,000 plus $1337); R. F. Ahrens, vp, $18,000 plus $1314 ($17,416 plus $1216); Curtis Barkes, vp, $18,000 plus $922; D. F. Magarrell, vp, $20,000 plus $1218 ($17,416 plus $1086); S. P. Martin, secty., $12,000 plus $774 ($11,954 plus $743); C. H. Blanchar, comptroller, $11,700 plus $525 ($10,548 plus $475); N. B. Haley, treas., $13,000 plus $7071 ($13,000 plus $1000).

Stockholders with more than 5 percent: Inos & Co., New York, 5.34 percent preferred; Josephthal & Co., New York, 6.20 percent preferred; Merrill Lynch, Pierce, Fenner & Beane, 5.75 percent common; W. A. Patterson, 13.64 percent management; Harold Crary, 5.46 percent management; R. W. Ireland, 8.46 percent management; J. A. Herlihy, 5.46 percent management.

►**Western**—T. C. Drinkwater, president, $34,999 plus $300 indirect ($34,999 plus $100); S. R. Shallo, vp, $15,000 plus $800 ($18,000 plus $100); M. W. Landes, vp, $10,000 ($10,000); R. A. Dick, vp resigned Oct. 31, 1949, $8863 ($10,000); A. F. Kelly, vp, $10,000; P. E. Sullivan, vp-secty., $10,200 ($10,200); D. P. Reads, asst. secty., $6100 ($6325); J. J. Taylor, treas., $9900 ($9600); R. H. Purnell, controller and asst. treas., $7650 ($7200).

Stockholders with more than 5 percent: Earnham Co., New York; Merrill Lynch, Pierce, Fenner & Beane, New York; Walston, Hoffman & Goodwin, New York.

►**Slick Airways**—Lewis Moorman, exec. vp, none; Thomas L. Grace, vp, $9100; Joseph E. Grant, secty., $6200; David Stewart, treas., $6407; William E. Miller, asst. secty., none.

Stockholders with more than 5 percent: Guaranty Trust Co. of New York, 19.3 percent; Harris Trust Savings Bank, Chicago, 16.9 percent; Earl F. Slick, 5.6 percent; Tom F. Slick, 57.9 percent; Charles F. Urschel, Jr., 6.5 percent; Mrs. Bernice Slick Urschel, 5.5 percent.

►**U. S. Airlines**—R. W. Starkey, vp and general manager, $10,000; H. P. Grevely, secty.-treas., $7200.

Stockholders with more than 5 percent: H. R. Playford, 33 percent.

►**Caribbean-Atlantic Airlines**—Dionisio Trigo, president, $10,000 ($10,000); Benigno Trigo, vp, $3800 ($10,015); Manuel Rivera, vp, $5400 ($5900); Frank Sheldon, vp, $2100; Jose Sierra, vp, $10,000 ($3300); Adelfe Valdes, secty., $1960 ($420); L. A. Lockhart, treas., $7200 ($6500).

Stockholders with more than 5 percent: Dionisio Trigo, 24 percent; Benigno Trigo, 24 percent; Juan Trigo, 16.8 percent; Henry Molina, 6.0 percent.

►**Hawaiian Airlines**—Stanley Kennedy, president, $27,500 ($14,400); Alexander Smith, vp-secty., $14,000 ($14,000); Ford Smedsaker, vp, $14,000 ($14,000); David Watson, treas., $11,000 ($11,000).

Stockholders with more than 5 percent: Inter-Island Steam Navigation Co., 87.31 percent.

►**Trans-Pacific Airlines**—Ruddy F. Tonze, president, $6000; H. K. Hee, treas., $8300; Archie Wong, secty., $3200; William Mandall, vp, $7273.

Stockholders with more than 5 percent: Jacob Ing, Honolulu, 6.45 percent.

NAL Traffic Soars

National Airlines celebrated completion of the biggest traffic month in its history by announcing the purchase of two more DC-6s.

President G. T. Baker said March revenue passenger mileage totaled 29,304,000, up 11 percent over February (the previous record month), and 53 percent ahead of March, 1949. Passenger load factor last month was 61.1 percent—nine percent higher than the year before.

The two newly ordered DC-6s are to be delivered before next winter's busy Florida vacation season. Two other DC-6s ordered last fall are to go in service this summer. NAL now has four DC-6s in operation.

►**Excursion Fares**—Meanwhile, National is aiming for its biggest summer season despite a recent rebuff by the Civil Aeronautics Board. The federal agency refused to permit National and Eastern Air Lines to offer special roundtrip excursion fares from northern cities to Florida points at only one and one-third times the regular one-way fare during the off-season between May 15 and Oct. 31.

CAB said the roundtrip rate of 133 percent of the standard fare would be discriminatory, and declared comparable excursion tariffs effective last summer had diverted considerable regular fare traffic. The Board indicated it might approve summer excursion fares equal to 150 percent of the standard one-way fares if the special rates apply only from July 5 to Aug. 30 and carry a 21-day limit.

National will continue to offer its New York-Miami coach service during the summer and plans to refile its application for excursion fares.

IATA Seeks Standard Visas

Means of further streamlining immigration and customs formalities for bona fide tourists and businessmen traveling by air through the Mediterranean and Far East areas was sought by members of the International Air Transport Assn. during a conference in Cairo.


Revision of visa forms has been suggested in IATA to make sure that the information they carry will be more

Van Dusen
AIRCRAFT SUPPLIES
TOPICS

While many aviation firms are "consolidating" their operations, we have much progress to report at Van Dusen—such as the new Customer Service Department at Minneapolis where our store and display room has been restyled and enlarged to handle the constantly increasing number of customers.



Not long ago another progressive step was made by Van Dusen to serve our airline and airport operator customers in New England. We moved to new and larger quarters at Boston's Bedford Airport where a complete stock of aviation supplies and equipment is maintained.



One of the things about which we pride ourselves most at Van Dusen is our intimate knowledge of aviation and flying needs which goes back quite a way. For instance, only old-timers will recognize Van Dusen's first airplane, an Aeromarine Klemm of early 1930 vintage shown in photo above.

This long time knowledge of flying needs and flying supplies, whether for airlines or private flying, means a lot in giving you the best possible aviation supply service. You can't go wrong with Van Dusen.

Van Dusen
AIRCRAFT SUPPLIES INC.
Serving all 4 BEST
Warehouses at
MINNEAPOLIS
TETERBORO, N. J. (New York)
BEDFORD, MASS. (Boston)
AIRLINES
OPERATORS
EXPORT
MANUFACTURERS
CABLE ADDRESS VANDUSAIR 7E7EB0B0, N. J.

easily understood despite language differences International carriers are responsible for validity of a passenger's visa granted by the country of destination If there are any mistakes the carrier must bear the expense of returning the traveler to his point of origin

An international agreement on documents and procedures required of airlines by governments for transit of planes, passengers, crews, goods and supplies through their territories was put into effect by member states of the International Civil Aviation Organization last fall But deviation from ICAO standards was permitted

Fuel Consumption—DC-6 vs. Jet

	Distance	Speed	Altitude	Fuel
DC-6	2000 mi	300 mph	20,000 ft	2300 gal
	2000 mi	200 mph	5000 ft	2000 gal
TURBOJET	2000 mi	400 mph	35,000 ft	4500 gal
	2000 mi	200 mph	5000 ft	11,000 gal

Jets No Traffic Control Problem

ATA's navigation expert says turbine transports will speed solution of present questions, not add new ones.

Arrival of jet transports on the commercial air transportation scene probably won't require radical changes in air traffic control planning, but it will add a new note of urgency to solution of existing problems

That's the opinion of Sam Saint, director of the Air Transport Assn 's Air Navigation and Traffic Control division. While he believes the jet will put our future air traffic control system to the acid test, he sees no reason why the new aircraft can't be handled in conjunction with slower, propeller-driven planes

▶**Fosters Sound Approach**—Certain special considerations demanded by the nature of the fuel-hungry jet transport will help screen out unsound approaches to the traffic control problem, Saint told the Society of Automotive Engineers' National Aeronautic Meeting last week in New York "The jet engine is our best insurance against taking a wrong road in air traffic control development," he declared

The ATA expert said it is clear that jet-powered transports cannot be operated economically under the present traffic control system, with its uncertainties and frequent delays The jet demands a complete solution to the traffic control problem, and thus same solution should also be best for propeller-driven planes

▶**Compared to DC-6**—Saint compared the DC 6 to a turbojet in the same general category to point up the latter's special problems

A DC-6 can fly at 2000 ft or 20,000 ft and cruise at below 200 mph or above 300 mph without great change in economy of operation On a 2000-mile flight at 300 mph cruising at 20,000 ft , the DC 6 would need about 2300 gal of fuel For the same length flight at 200 mph and 5000 ft altitude, the DC 6 would save around 300 gal — or a difference in allowable payload of 1800 lb favorable to low altitude

It's a different story with a jet in the DC 6 category To fly such a plane 2000 miles at 35,000 ft at 400 mph, requires about 4500 gal of fuel

But to fly the jet 2000 miles at 5000 ft at 200 mph requires about 11,000 gal (66,000 lb) of fuel—considerably more than the plane is capable of carrying Thus, Saint observed, the jet requires nearly 19 tons more fuel to make the same flight at the lower altitude and lower speed Its lack of flexibility means that air traffic control tolerances must be tighter

▶**Holding Problems**—Besides the higher rate of fuel consumption en route, the jets are handicapped by having only a small margin of holding fuel Saint estimated that a comparable jet burns four times as much fuel while holding as a DC-6

The jet is, however, able to slow down on entering the terminal area, and can fly through the final approach patterns at the same respectable slow speed used by other planes If required to hold, it can do so at a speed well below 200 mph with a reasonably small turning radius

"It is not necessary," Saint emphasized "to visualize a momentarily blocked runway diverting a stream of 500-mph airplanes in great swinging arcs across the sky But the jet must have reasonable assurance of prompt landing on arrival at its destination If the originally intended flight path or airport is blocked for unexpected reasons, the jet must be diverted quickly to a suitable alternate field "

▶**Minimum Delays**—By 1960, if proper air traffic control plans are carried out, a jet should be able to make a three-hour flight from Dallas to New York with the promise of no more than ten minutes delay for landing, Saint declared He envisions each jet receiving a priority number on the basis of the flight plan submitted

If the jet is early, it will be forced to wait its turn in a holding pattern If it is late, there will be no penalty, and slower conventional planes will be taken into the approach system ahead of it to keep the runways in full use

Saint said that within five to ten years the airlines believe improved air ways and landing aids will permit 40 landings and 40 takeoffs per hour on a dual runway airport, even when there is only a 100-ft ceiling This average of one landing or one takeoff every 45 seconds is more than double the best that can be done today

Stated another way, the airlines by 1960 hope to move 3600 passengers hourly into and out of an airport in weather thick enough to slow highway traffic

Frontier Airlines Formed by Merger

The nation's largest feeder, formed by merger of Monarch Air Lines, Challenger Airlines and Arizona Airways, will operate under the new name of Frontier Airlines

Last link in the sprawling Rocky Mountain area short-haul system was forced recently when the Civil Aeronautics Board approved the consolidation of Monarch and Arizona Airways Monarch's acquisition of Challenger was approved last December

CAB's sanction of the Monarch-Arizona merger was on condition that MAL show within 30 days its financial ability to inaugurate and maintain service over the consolidated feeder routes

▶**Terms Listed**—The merger agreement provides that Monarch acquire all outstanding stock in Arizona in exchange for 6000 shares of MAL stock and assumption by Monarch of $150,000 of Arizona Airways' liabilities Arizona was awarded a three-year feeder certificate in June, 1948, but never inaugurated service because of financial difficulties

CAB authorized Monarch to extend its present route from Gallup, N Mex , to Winslow, Ariz , to form a connecting link with Arizona's system No service will be instituted over Arizona's Phoenix-Yuma link pending outcome of the reopened CAB case on additional California-Nevada service

Opposition to the Monarch Arizona merger was expressed by CAB member Harold Jones in a dissenting opinion He said that whereas Arizona was certificated in 1948, there was insufficient public interest by people of the Southwest in the proposed system to obtain adequate financing for its operation

▶**High Cost**—Jones asserted that the cost to the government of the merged Monarch Challenger-Arizona system will be at least $3 million annually, possibly higher He indicated that the consolidated Rocky Mountain feeder can hardly be called a supplemental local system since it will comprise 4941 certificated route miles from Mexico almost to the Canadian border It will be larger than the trunk line operations of Continental, Colonial, Inland, Mid-Continent, National, Northeast and Western, and the domestic system of Braniff

Jones said CAB has spent over $40 million to date in mail pay alone on its feeder experiment He added that the Board no longer has a common understanding of just what the feederline experiment is, what it can be expected to prove, or its cost to the government

Tito Turns From East to West

Yugoslavia trying hard to qualify for U. S. aid to build transport network, but it's a tough problem.

By John J. Christie
(McGraw-Hill World News)

Belgrade—The Yugoslavs are going bravely ahead extending their commercial air ties with the west, even if they don't know where the next plane or engine is coming from

Negotiations are well along with the Italians, French and Swiss, and others are in the offing, following implementation of the politically significant air pact which was signed with the U S on Dec 23

▶**PAA Aid**—In fulfillment of the U S agreement, the Yugoslavs have managed to provide radio beacons and a minimum of other communications equipment to accommodate Pan American Airways PanAm save some 350 miles by flying from Munich across Yugoslavia to Istanbul The agreement provided full fifth freedom rights for U S carriers but commercial field facilities are inadequate for four engine planes

JAT (Yugoslav National Airlines) has inaugurated a twice-weekly Frankfurt-Belgrade service in pursuance of rights granted for landings in U S -occupied Germany and Austria Cabotage for a Munich stop on one of the weekly flights also was granted by the Civil Aviation Board of the Allied High Commission

Actually, the first western air connection was established in November by an interim agreement with the Swiss This pact, now in process of re-negotiation, is implemented by a weekly round trip by JAT and another by Swiss Air between Belgrade and Zurich

▶**Expansion Urge**—Only a country with guts enough to defy the Kremlin would be making such a bid to extend its international air service as the Tito regime now is doing Here's why

● **Best estimates** indicate the Yugoslavs have only about 14 DC-3s at this writing And, at least one of these can be counted upon as marked for cannibalization

● **JAT already is saddled** with a flourishing domestic service There are daily flights between Belgrade and Zagreb and daily but one between the capital and Titograd And, there are other points served irregularly

So Tito is really on a desperate shopping tour He'll take all the second-hand DC 3s he can get For extension of international service westward is an important political prestige point at this time.

▶**No Dollars**—The U S in January cleared the way for civil aviation equipment to be exported to Yugoslavia But this has been of little practical help so far due to the condition of Tito's pocketbook Only small orders for engines and parts have been eked out of dollar exchange earnings No way has been found yet to meet repeated requests for dollar credit for civil aviation requirements

Still the Yugoslavs and those U S officials intimately concerned with sustaining Titoism are hopeful that the U S will be able somehow to make at least a few discarded DC-3s available in the near future Meantime, the Yugoslavs probably can obtain some equipment from western European countries and possibly Britain under terms of forthcoming air agreements or through the medium of bi lateral trade and payments arrangements

▶**Facilities**—The commercial airfield serving Belgrade is at Zenum, about three and a half miles from the center of the city It has a grass runway about 4500 ft long and 250 ft wide Two-engined aircraft can be handled satisfactorily but the landing of a DC-4 would be possible only under limited conditions

New radio beacons at Belgrade and Zagreb installed for the Pan Am flights, are high powered Lorenz equipment of unknown origin And there is air-ground radio telephone

Beacons are switched on only when a flight plan has been sent to flight control at Belgrade There is a 24-hour manual radio telegraph service for receiving this information

A new international airport is to be built beyond Zenum at a site about seven miles from the center of Belgrade On paper, it is a grandiose scheme charcteristic of the regime's Five Year Plan Even a subway connection with the center of the city is planned eventually.

Of immediate concern is the first phase of the long range development program This calls for completion by mid-1951 of a 10,000-ft instrument runway, with both GCA and ILS equipment

The Yugoslavs at present aren't equipped to perform more than third echelon repairs They have no capacity for depot repair work Engines were sent to Czechoslovakia for overhaul prior to the Cominform break, but now go to Holland

Though poor in civil aviation equipment, the Yugoslavs have other aviation assets worth mentioning One is cadre of competent war trained pilots, who served with a number of national air forces The other is a good safety record, only one fatal crash having occurred since the war

▶**Commie Freeze-Out**—Pan Am and civil aviation officials concerned with the implementation of the recent agreement with the U S report speedy and competent cooperation by the Yugoslavs in meeting requirements

There is very little remaining of Yugoslavia's air connections with the satellite area A Czech twice weekly Prague Belgrade-Sofia run is the only remaining regular service

Prior to the Cominform break Yugoslavia had air agreements with all members of the Soviet bloc, although the ones with Poland and Romania never were implemented Air agreements were broken or mutually terminated with Albania and Bulgaria Hungary ceased to exercise its rights some time ago under a pact which expired Feb 18 and was not renewed


There was no air agreement with Russia but the Soviets had controlling interest in a joint airline enterprise known as JUSTA Tito ordered this dissolved after his bolt from the Kremlin Unfortunately, the Russians were supplying the planes, a fleet of nine IL 2s, and of course withdrew them

Tito has given the Russians a brush off since then At first, the Soviets had blanket permission covering flights from Moscow to Tirana via Belgrade This was reduced to a monthly basis, then weekly and now for each flight Only


Edo

NEWS NOTES

Among the shortest wings used on any air-borne Air Force equipment are those being made, surprisingly enough, at our College Point plant. Mounted on the thirty foot life boats which Edo is building for Air Rescue Service, these wings have a span of only nine feet.



These clipped wings are used to stabilize this ton-and-a half air rescue boat when being cast loose from B-29 search aircraft for which the boats were designed. Once clear of the B-29 a huge Pioneer parachute, 100 feet in diameter, takes over and the boat is dropped gently into the ocean. The wings are then jettisoned by survivors once they're safely aboard.



The A-3 boat is but one of a wide variety of engineering, development, and manufacturing projects handled by Edo's experienced staff of engineers and skilled craftsmen.

Edo's prominent role in this field of research and development stems from 25 years of steady growth with aviation. For an interesting, profusely illustrated history of Edo's contribution to aircraft production methods, seaplane flying and electronics write for your copy of our Twenty-Fifth Anniversary booklet.

EDO CORPORATION
College Point, N. Y.
CONTRACTORS TO
U. S. ARMY, NAVY AND AIR FORCE

occasionally does a Soviet plane fly over the country to Albania or stop at Belgrade to deposit a diplomat.

Amber for Red

United Air Lines has received Civil Aeronautics Board permission to conduct a six-months experiment with amber rear position lights instead of red on some of its DC-3s.

Like other airlines, UAL has been operating its transports with rear position lights emitting alternate red and white flashes. The experiment, to be conducted with six planes, provides for replacing the red lens on the rear position light with an amber one.

United believes the amber flash in lieu of red will permit night-flying aircraft to be identified more readily at greater distances and will eliminate the confusion now existing between the red wing-tip light and the red rear position light. Following the six months test period, during which flight personnel of other aircraft will have the opportunity to observe the experiment, United will submit its findings to CAB and CAA.

CAB Whittles Away At PAA Mail Pay

Pan American Airways is experiencing severe financial headaches as a result of the Civil Aeronautics Board's increasingly hard-boiled attitude toward mail payments.

Latest jolt to PAA is a CAB order telling the carrier, in effect, to show cause why nearly two-thirds of a reported $10,077,000 break-even mail pay need on Latin American routes should not be disallowed. Unless Pan American and CAB get a lot closer together on mail pay requirements, some of the tentative profit figures the carrier has on its books for past periods may become deficits.

▶**Figures Trimmed**—Here's the way CAB analysts slashed away at the $10,077,000 mail pay figure which PAA says is required if it is to break even for the year ended last Sept. 30.

• $1,230,000 deducted for "unreasonable losses" resulting from operation of all-cargo services which CAB thinks were not justified by public need. These all-cargo flights, the Board declared, diverted cargo which normally would have helped build up loads on combination passenger-cargo flights.

• $4,972,000 deducted for losses stemming from operation of excess capacity. CAB suggested that PAA's Latin American division had made flights above the number justified either by the overall demands of the passenger-cargo mail traffic available or by the minimum requirements of adequate service.

INSTRUMENT SERVICE
FOR
DOMESTIC AND
INTERNATIONAL AIRLINES

- All instruments CCA overhauled
- MANUFACTURER'S GUARANTEE—All repaired instruments carry the same guarantee as that of the original manufacturer.
- CONSULTANT SERVICE — Call on our expert personalized consulting service.
- Prices hourly or flat rate.
- Our shops are CAA, CAB, Air Force and Navy Approved.
- WRITE FOR FREE CATALOG & PRICE LIST.

S. M. S.
AIRCRAFT INSTRUMENT
SALES & SERVICE, INC.
N. Y. INTERNATIONAL AIRPORT
JAMAICA 20, N. Y.
Olympia 6-5678
CAA Repair Station No. 3500

RADIO RELIABILITY
—PLUS!

THE ONE-SIXTEEN
$272.50
(Suggested list price. Prices apply only within continental U.S.A.)



The RCA One-Sixteen
—the personal plane radio that has everything in one package

- √ Entertainment—Complete coverage of standard broadcast band
- √ Four Course Ranges—For dependable navigation. Built-in range filter
- √ Marker Beacons—75 mc marker signals received clearly whether flying the beam or direct on finding.
- √ 2-Way Communications—Receives ranges and towers 200-400 kc. Transmits on new high performance VHF channels
- √ Loudspeaker Output—For cabin loudspeaker—plus headphone operation. Speaker switch on front panel.
- √ Interphone—For large cabins, or two cockpits
- √ Loop Direction-Finding—Operates on either broadcast or beacon bands with any RCA loop

See the One-Sixteen at your RCA Aviation Dealer. For free brochure, write Dept. 93

RCA AVIATION SECTION
RADIO CORPORATION of AMERICA
ENGINEERING PRODUCTS DEPARTMENT, CAMDEN, N.J.
In Canada: RCA VICTOR Company, Limited, Montreal

• $400,000 deducted by adjusting the depreciation on PAA's Convair-Liners from a five to a seven year basis.

In disallowing losses from the allegedly uneconomic all-cargo flights, CAB reiterated a policy laid down last year in orders affecting Panagra and Pan American Atlantic division mail rates. Despite the disallowances, CAB's proposed new mail rate would give PAA $2,775,000 more revenue during 1949 than the old one.

▶**Profit Allowance**—Basing its findings on figures for the year ended last Sept. 30, CAB directed PAA to show cause why $7,225,000 shouldn't be the fair and reasonable temporary mail pay for the Latin American division during calendar 1949. This $7,225,000 includes the CAB-recognized $3,475,000 break-even mail pay need (instead of PAA's $10,077,000 figure) plus an allowance of $3,750,000 which, according to the Board, represents the amount required to yield the carrier a 7 percent profit on its investment after taxes.

Since PAA indicated it needed about $10,077,000 merely to break even, the $7,225,000 total specified by CAB presumably would result in a $2,852,000 loss for the year rather than a $3,750,000 profit. CAB has proposed a 33-cents-a-plane-mile mail rate for 1950 which would yield PAA's Latin American division about the same mail revenue as specified for 1949.

PAA has the right to protest the temporary mail rates proposed by CAB. And the Board, in fixing a final mail rate, may make further adjustments in its temporary figures.

Texas Feeder Bids for Copter Mail Service

Central Airlines, Fort Worth feeder-line, has put in its bid to operate helicopter-mail service in the Dallas-Fort Worth area.

The proposed route would run between Meacham Field, Fort Worth, the main post office in downtown Fort Worth, Fort Worth International Airport (now under construction midway between Dallas and Fort Worth), the main post office in downtown Dallas, and Love Field, Dallas. An alternate routing was asked to permit operations from Love Field direct to Fort Worth International Airport on the return trip.

Fort Worth International Airport is slated for activation some time in 1951. Central hopes the Civil Aeronautics Board will approve its helicopter application before the field's opening date.

Keith Kahle, Central's president, says that if his company is certificated for the helicopter mail service it would




Who watches engine temperature when he's *in Action?*

BRISTOL! This company's remarkable automatic engine temperature control (standard equipment on Navy piston engine attack and fighter airplanes) takes over this vital function with supreme accuracy.

Bristol meets the challenge of developing and making all types of sensitive aircraft controls, with a broad base of over 60 years' experience as a leading producer of industrial control and recording devices.

No matter what your special requirement may be, Bristol's Aircraft Equipment Division stands ready to help you.



Bristol Engine Temperature Control. *Proven in stiffest tests! Sensitive, yet won't over-shoot control point.*

What's your control problem? Let us solve it! Whether your needs call for engine temperature controls, fuel cycle timers, remote positioners, electronic devices, or something completely unique, Bristol's engineering skill and extensive production facilities are at your service. 26 Branch Offices conveniently dot the country. Address initial inquiries to The Bristol Company, at Waterbury 20, Connecticut or 2181 East 25th Street, Los Angeles 58, California.

FREE! Latest Bulletin of Aero Controls


The Bristol Co., 130 Bristol Rd., Waterbury 20, Conn.
Please send me your Bulletin of Aero Controls.
Name
Firm
Address
City Zone State



61 YEARS . . . 1889-1950

BRISTOL
TESTED, TRUSTED MAKER OF FINE PRECISION INSTRUMENTS

Accuracy At Heat Source!



One of Our Many Thermocouples

Type 28018 (AN 5541-1) Bayonet Immersion Contact Thermocouple designed for Cylinder Heads

ACCURACY of temperature readings depends primarily on the accuracy of thermocouples at the source of heat. Our Aircraft thermocouples can be depended upon to transmit temperature changes with maximum accuracy and responsiveness.

For every temperature measuring job—Airborne or Test Stand—there's a Thermo Electric Couple to do the job.

Write for our Catalog C describing our Aircraft Thermocouples, Pyrometers, Lead Wires and Accessories.

Thermo ELECTRIC CO.
FAIR LAWN, N.J.

"What you want when you want it"

Aircraft Quality

U·S·S CARILLOY ALLOY STEELS

4130 —Rounds, flats, squares and hexagons to AN-QQ-S-684a and AN-S-684

4130 —Sheets and plates to AN-QQ-S-685

4140 —Rounds, flats and hexagons to AN-QQ-S-752a

4340 —Rounds and flats to AN-QQ-S-758a and MIL-S-5000

● Now you can order the Aircraft Quality U·S·S Carilloy Alloy Steels you need from any of our conveniently located warehouses from coast to coast. These top quality steels have proved their ability to take the shock of loads in landing gears . . . to withstand fatigue in engine mounts . . . to carry the stresses concentrated in many vital points in primary aircraft structures.

Phone, write or wire our nearest warehouse or sales office. You'll get the *Aircraft Quality* U·S·S Carilloy Alloy Steels you want without delay.

WHEN YOU DEAL WITH US, YOU GET Service Plus!

UNITED STATES STEEL SUPPLY COMPANY

Warehouses and Sales Offices

BALTIMORE · BOSTON · CHICAGO · CLEVELAND · LOS ANGELES · MILWAUKEE · MOLINE, ILL. · NEWARK · PITTSBURGH · PORTLAND, ORE. · SAN FRANCISCO · SEATTLE · ST. LOUIS · TWIN CITY (ST. PAUL)

Sales Offices: KANSAS CITY, MO. · PHILADELPHIA · ROCKFORD, ILL. · TOLEDO · TULSA · YOUNGSTOWN

Headquarters Offices: 208 S. La Salle St.—Chicago 4, Ill.

UNITED STATES STEEL

ask for the right to carry passengers when suitable helicopter transport equipment becomes available. Central now operates Beech Bonanzas over its certificated feeder routes in Texas, Oklahoma and Kansas.

SHORTLINES

▶ **Air Line Dispatchers Assn.**—Has negotiated contract with Monarch-Challenger Air Lines providing wage scale ranging from $355 monthly to start to $515 during the sixth year of service. Beginning Apr. 1, 1951, the scale will range from a starting $375 monthly to $525 during the sixth year and $550 during the seventh year.

▶ **Air Transport Assn.**—Is preparing ammunition to fire back at railroad interests which have been attacking airline subsidies before a Senate Commerce subcommittee. Sidney S. Alderman, general counsel for the Southern Railway System, ripped into airline subsidies in a 78 page statement which said the airlines could no longer point to an "infant industry" justification for getting 1. mail pay far in excess of fair compensation, 2. free use of beacons, weather services and airport control towers, 3. use of public airports at charges below cost; 4. benefit of government financing of aeronautical research. Alderman urged abandonment of uneconomical air routes.

▶ **All American**—Is joining the growing number of carriers painting the top of their planes white to reduce interior heat during the summer, an idea pioneered by UAL about three years ago.

▶ **Arctic-Pacific, Inc.**—CAB has rejected the Seattle nonsked's application for classification as a noncertificated cargo carrier under Part 295 of the Board's Economic Regulations.

▶ **Braniff**—Target date for inaugurating the carrier's service to Buenos Aires is now May 15.

▶ **Capital**—Hit an all-time high for Easter week-end business.

▶ **Civil Aeronautics Administration**—Four British aviation specialists have been brought to the U. S. on a three-months Marshall Plan study of CAA's airways traffic control system. British group will be based at Chicago Municipal Airport for the bulk of its training but will also visit LaGuardia Field and probably Kansas City. On their return home, the British specialists will serve as a trained nucleus to help install in the United Kingdom the single system of airways control CAA is advocating for international use.

▶ **Colonial**—Reports net loss of $318,715 on total operating revenue of $5,610,336 in 1949, compared with $261,030 loss on $4,993,834 revenue in 1948.

▶ **Eastern**—President E. V. Rickenbacker, in his recent annual report to stockholders, criticized the "unfair competition of charter and nonscheduled operators, the certification of new air freight carriers, and the pending certificate applications of air coach lines." He said present airline load factors are low enough to permit a sizeable increase in traffic volume without increasing the number of planes, flights or carriers.

▶ **Robinson**—CAB has increased the feeder's temporary mail pay to $756,000 (about 80 cents a plane mile) for the period from Sept. 10, 1948 (when certificated service started), to Dec. 31, 1949. Base rate of 60 cents a plane mile was set for Jan. 1, 1950, to June 30, 1950, and 50 cents thereafter.

▶ **Trans-Canada**—Canadian Trade Minister C. D. Howe has told a parliamentary committee investigating TCA's deficits that it would be five years before the carrier makes a profit on its Atlantic operations.

▶ **Transocean**—The uncertificated carrier's subsidiary, Transocean Engineering Co., has been awarded a $73,500 California State Highway Commission contract for bridge construction. TEC was formed by the airline to engage in general construction work, with emphasis on airports and installation of air navigation and lighting systems.

▶ **TWA**—Has announced reduced specific commodity rates for trans-Atlantic shipments.

▶ **Western**—Reports a net loss of $56,970 during the first two months of 1950—well below the $122,632 deficit shown for the same period last year. Company was in the black during March and hoped to be near the break-even point for the quarter.

CAB SCHEDULE

Apr. 24—Prehearing conference on CAB's investigation of unauthorized operations by Metropolitan Air Freight Depot, Inc. Postponed from Apr. 18. (Docket 4029)

Apr. 24—Oral argument in Florida-Ironbike case. (Docket 2218 et al.)

Apr. 28—Hearing on BOAC's request for New York-Bahamas route. (Docket 4360)

May 1—Prehearing conference in Wiggins Airways route case. (Docket 52-481E-1)

May 4—Oral argument on service to Springfield, Mass. Postponed from Apr. 17. (Docket 3746 et al.)

May 8—Hearing on case involving American Airlines' Los Angeles-San Francisco cargo rights. (Docket 4211)

May 16—Hearing on CAB's investigation of New York-Miami daylight coach service. (Docket 4282)


June 12—Hearing on applications of TWA and American Overseas Airlines to suspend service at Philadelphia on trans-Atlantic flights. (Docket 4228)

June 12—Hearing in reopened case on additional California-Nevada service. (Docket 2010 et al.)

June 19—Hearing on CAB investigation of Northwest Airlines' tariff practices and uncertificated operations of Fly Freight, Inc., and Sterling Freightways. (Docket 4290)



IT'S A FACT!



Cessna Installation

MORE NARCO UNITS ARE SOLD THAN ANY OTHER MAKE!

The Narco Antenna has become a familiar sight on personal and executive airplanes all over the country. There's because more and more, plane owners and pilots are learning from enthusiastic users that Narco is the completely dependable VHF transmitter-receiver and Omni equipment. That's why more Narco units are sold than any other make.

Narco is the only VHF and navigation set that complies with or exceeds all requirements of CAA Specification ES 63P. For static free communications, navigation, and ILS localizer approach equip your airplane with NARCO OMNI—you'll get the best dollar for dollar value the most miles per dollar and the least pounds—*you'll get the best for the least!*

See your authorized dealer for a demonstration and immediate delivery.

West Coast Representatives
THE LEE SMITH CO.
6383 Wilshire Blvd. Los Angeles, Calif.

narco
NATIONAL AERONAUTICAL CORPORATION
WINGS FIELD, AMBLER, PA.

LEWIS

SELECTOR
SWITCHES
for
Thermocouple & Constantan
THERMOMETERS



From two to Forty Points

Sturdy, Dust-Tight
Low Contact-Resistance
Positive Detent.

Our switches have been used for years in test work as well as in permanent installations.

Write for catalog today.

THE LEWIS ENGINEERING CO.
CHURCH ST. • • • • NAUGATUCK, CONN.

SEARCHLIGHT SECTION

(Classified Advertising)

EMPLOYMENT: "OPPORTUNITIES" :EQUIPMENT
BUSINESS: :USED OR RESALE

UNDISPLAYED —RATES— DISPLAYED

(Not available for equipment advertising)

Undisplayed Rates 60¢ a line, minimum 4 lines. To figure advance payment count 6 average words as a line

Individual Employment Wanted advertising rate is ½ the above rates payable in advance

Box Numbers—Care of publication New York, Chicago or San Francisco offices count as one line.

Discount of 10% if full payment is made in advance for 4 consecutive insertions

Individual Rates with border rates for prominent display of advertisements

The advertising rate is $10.00 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

An advertising inch is measured ½" vertically on one column. 8 columns—80 inches—to a page.


AERONAUTICAL ENGINEER

to perform stress analysis, design of aircraft components, and flight test data analysis for flight research organization. Minimum 5 years experience required. Submit resume to

Box AW 1688
221 W. 41 St
New York 18, N. Y.

BUFFALO RADIO SUPPLY
219-221 Genesee St.
BUFFALO 3 N. Y.

ELECTRONIC ALTIMETER
Only $45.00



Brand new APN-1 14 tube electronic altimeter in original factory packing. This famous "Eureka" unit, which weighs only 25 lbs without plugs or cables, has the set $5000 cost includes a transmitter & receiver, all tubes an altitude meter, an altitude limit switch, and two easily installed 11" antennas. Working on the radar principle the receiver measures the absolute altitude from 3 to 4000 feet, with precision enough for blind landings. In addition the altitude limit switch gives an alarm if the plane's height varies by more than 10 feet from a predialized value. Fills recent C.A.A. requirements effective Feb. 17, 1950 that all scheduled airlines must have terrain clearance indicators capable of giving warnings at 500, 1000 and 2000 ft. Another outstanding feature is that connections are provided to control an electronic automatic pilot. Send for our aircraft radio equipment catalog. Export inquiries invited.

Model for 12 to 14 volts D.C. $70.00
Model for 24 to 28 volts D.C. $85.00

WORLD WIDE MAIL ORDER SERVICE !!!


DOUGLAS AIRFRAME
Parts for DC-4,
C-54, C-47, DC-3
Send Inquiries
GENERAL OVERSEAS AIRLINES
Area 7 Newark Airport Newark, N. J.
Market 2-0964

B-29 HANGAR BUILDING

New, Size 194' x 200', Cheap.
ANDERSON MANUFACTURING CO.
1700 Sawtelle Blvd. Los Angeles
Bradshaw 2-1202

Aircraft Maintenance Equipment
for Douglas
DC-4, C-54, DC-3, C-47
Immediate Delivery
GENERAL OVERSEAS AIRLINES
Area 7 Newark Airport Newark, N. J.
Market 2-0964

Portable Radial Engine
TEST STAND



Double Cell—test stand, 250 gal. gas tank, Instrument desk for left and right engines, all instruments and controls

F.O.B. $5000.00 net

The BABB COMPANY, Inc.
444 Madison Ave. New York 22, N. Y.
Tel. Plaza 8-2361

PRATT & WHITNEY PARTS
for R-2000-7-9-11-13
Prompt Service
Send Inquiries
GENERAL OVERSEAS AIRLINES
Area 7 Newark Airport Newark, N. J.
Market 2-0964

SCHOOLS

Rising Sun SCHOOL OF AERONAUTICS
ESTABLISHED 1930
"Built Upon the Success of its Graduates"
GOVT. C. A. A. and VETERANS APPROVED
ENROLL NOW FOR NEXT CLASS
Write for Illustrated Catalog
2206-16 E. HUNTINGDON ST., PHILA., PA.

WANTED

"AN HARDWARE WANTED"

Jch lots of fittings, bolts, nuts, elastic stop nuts, rivets, washers, terminals, clamps, etc.

W-6050 Aviation Week
330 W. 42nd St. New York 18, N. Y.

CORPORATION WANTS
CONVERTED OR UNCONVERTED
B-25, B-23 or Equivalent

For Executive Transport 2000 mile cruising range very desirable. Include complete information and performance data with reply.

W-6055, Aviation Week
520 N. Michigan Ave. Chicago 11, Ill.

GRADUATE ENGINEER (PREFERABLY M.S.)

Thoroughly familiar with servomechanism analysis and synthesis techniques. Courses in aircraft stability and control desirable. Experience desirable, but not absolutely essential.

GRADUATE ELECTRONIC DESIGN ENGINEER

Experienced in the design of amplifiers or instruments for low power servomechanisms.

Apply Engineering Personnel Manager
NORTHROP AIRCRAFT, INC.
Hawthorne, California

WANTED
STRESS ANALYST

Want man with 3 to 5 years experience, CAA requirements preferably on light airplanes. State training, experience and salary required. Please reply to

NELIO AIRCRAFT CORPORATION
Box 126 Norwood, Massachusetts

REPLIES (Box No.) Address in office nearest you
NEW YORK 330 W. 42nd St. (18)
CHICAGO 520 N. Michigan Ave. (11)
SAN FRANCISCO 68 Post St. (4)

POSITIONS VACANT

HELICOPTER PILOTS and Mechanics for work in United States. Also for long months' work in Alaska. Allied Helicopter Service, Inc., Moisant International Airport, New Orleans, Louisiana.

SALES ENGINEER. New York representative for old line aircraft accessory manufacturer. Must have hydraulic engineering and sales experience. Give complete information and salary expected in first letter. P-6358 Aviation Week.

FIRST CLASS radio man for permanent work in Pacific Northwest. Must have minimum 2 year experience on overhaul and service associated airline type equipment. No others need apply. Better than average pay, working conditions, and future. Reply P-6360 Aviation Week.

POSITION WANTED

4 ENGINE ATR Pilot. 13 years airline and military flying. Senior pilot Air Transport Command. Tennessean and foreign experience. Commercial multi-pilot 1400 accident-free hours. Single and multi-engine land and sea. Instrument and instructor ratings. Administrative experience. College engineering. Complete resume upon request. PW-6352 Aviation Week.

WANTED

Wanted to Purchase:
42-D and 47 D-1 Bell Helicopters. State conditions. Time on aircraft, engine time since last major type transmission. Allied Helicopter Service, Inc., Moisant International Airport, New Orleans, Louisiana.

FOR SALE

Three DeHavilland "Doves" plus two extra engines will be sold with zero time engines. Details forwarded on request. PW-6375 Aviation Week.

NO EXCUSE NOW! STOCK UP!

DOUGLAS PARTS
Demountable Power Plants
Ring Cowls — Collector Rings

DOUGLAS PARTS
Main Gear — Nose Gear
Wheels — Struts — Braces

DOUGLAS PARTS
Wings — Rudders — Elevators
Tips — Flaps — Ailerons

DOUGLAS PARTS
Starters — Generators
Pumps — Valves — Relays

DOUGLAS PARTS
High-Density Seats — Sleeper Seats — Bags — Windows — Berths

DOUGLAS PARTS
Nose Sections — Passenger Sections — Deck Frames


DOUGLAS PARTS
Cargo Doors — Passenger Doors — Cargo Tie-Down Kits

DOUGLAS PARTS
Heaters — Ducts — Vents
Hatracks — Bulkheads

DOUGLAS PARTS
E Fuel Systems — Detectors
Dump Chutes — Cables

DOUGLAS PARTS
Priced to induce your IMMEDIATE PURCHASE!

GENERAL OVERSEAS AIRLINES
AREA 7 NEWARK AIRPORT
NEWARK, N.J. MARKET 2-0964



NEW R-2800-75's
price $3,000.00

These engines are 00:00 time since factory new and have had ACES C.A.A. approved outside in lubrication system blower to thrust plates incorporated. They have also been block tested in our modern test cells and have been prepared for long term storage.

C.A.A. APPROVED OVERHAULS
- R-1830-92 without exchange $2,500.00
- Above with exchange $2,298.00
- R-1830-65-92 Conv. less carb. $1,850.00

All Engines Complete with Form 60-B
ALL WORK AND ENGINE SALES CARRY OUR 100 hr. WARRANTY

AIR CARRIER ENGINE SERVICE, Inc.
C.A.A. Approved Repair Station No. 3604
P. O. Box 1388
Miami, Florida
Cable "ACENGSER"
ACES AIR CARRIER ENGINE SERVICE, INC.

DEAD WEIGHT TESTER
Model 1312



Dead Weight Testers for testing pressure gauges up to 500 lbs., complete with:
- 3 each 5 pound weights
- 2 each 10 pound weights
- 3 each 20 pound weights
- 8 each 50 pound weights

F.O.B. Price $250.00 net

THE BABB COMPANY, Inc.
444 Madison Ave., N. Y. 22, N. Y.
Tel. PLaza 8-2361

AIRCRAFT & ELECTRONIC EQUIPMENT

As a leading supplier we offer a complete line of

BRAND NEW INSTRUMENTS
- FLIGHT & NAVIGATION INSTRUMENTS
- ENGINE INSTRUMENTS
- AUTOMATIC PILOTS
- INVERTERS
- AUTOSYNS
- PRECISION AUTOSYNS
- RATE GENERATORS
- SYNCHROS
- ALNICO FIELD MOTORS
- GYROS
- A.C. MOTORS
- D.C. MOTORS
- SERVO MOTORS
- TORQUE UNITS
- TORQUE AMPLIFIERS
- FREQUENCY METERS
- BLOWER ASSEMBLIES

Write for complete listings
All Instruments May Be Purchased C.A.A. Certified
U. S. Export License-2140

WUX Great Neck, N. Y.

INSTRUMENT ASSOCIATES
37 E. Bayview Ave., Great Neck, N.Y.
Tele: IM perial 7-1147

25 NEW R2800-75 CERTIFIED ENGINES

THESE ENGINES TESTED AND CERTIFIED BY GRAND CENTRAL AIRPORT CO., GLENDALE, CALIF.

C.A.A. Airworthiness 49-46-2 Complied With

For Full Particulars Write
CHARLES GROSSO
432 Vine St. Modesto, Calif.

Douglas DC-4
Demountable power plants for R-2000-7-11-9-13 with fire prevention completed

Immediate Delivery

GENERAL OVERSEAS AIRLINES
Area 7 Newark Airport Newark, N. J.
Market 2-0964

LETTERS

ILS Double Check

We read with interest the article entitled, 'GCA Check on ILS Aids UAL Landing" in AVIATION WEEK Mar 13 We have taken particular interest in the paragraph entitled, 'Double Check Wanted."

For your information, we were authorized for use of ILS by CAA on Jan 27, 1950, the basis of this authorization being on the operation of a dual installation

The dual installation consists of two independently operated glide slope and localizer receivers, the pilot's cross pointer being used on one set of equipment and the second set of equipment connected to the co pilot's indicator

Our adoption of this system we understand, was the first domestic application of a double check method We are not fortunate enough to have GCA available at the six airports where ILS landings are authorized on our system

Our reasons for using this method were First, the increased safety factor in providing the pilot with a double check with the co pilot's equipment, at all times, a secondary reason was economic, for through the adoption of this system we were able to eliminate the purchase of expensive test equipment at our terminating stations, and the cost of trained personnel to operate same.

We have found that our pilots have whole-heartedly accepted this installation and have placed a great deal of confidence in the method we are using

We have also found that our first month of operations using ILS equipment has saved Southern Airways, Inc. enough in operation cost to pay for the initial investment which was required for installation of this system

E. A BOSTELMANN
Supt of Communication
Southern Airways, Inc
Atlanta, Ga

Praise

We appreciated the excellent job Irv Stone did in preparing the AVIATION WEEK article on our new ram jet laboratory

KENNETH C MEHSHOP
Public Relations Manager
Wright Aeronautical Corp
Wood Ridge, N J

Two Fighters

News that the Lockheed F 80 jet fighter is finally going out of production offers an interesting comparison between the USAF and the Navy, in my opinion. The grand old Navy still has the Vought F4U propeller-driven Corsair in production, while the Air Force is retiring an old and worn-out jet fighter from the production line!

It seems to me there's something wrong here when an Air Force jet fighter has already come and gone (as far as production is concerned) while the Navy still is plodding along building more piston engine fighters of a type that flew long before Pearl Harbor —at this late date nearly five years after V J Day!

I suppose the Navy has some very good technical reasons for still wanting the old Corsair, but I like better the Air Force's technical reason for no longer wanting the Shooting Star: later airplanes are replacing it on the production line!

K S B
Anaheim, Calif

Construction Critic

As a frequent patron of commercial air lines, I am quite dismayed over the fact that twice in one day doors of planes in flight flew open Do you recommend all passengers keeping their seat belts fastened at all times to avoid possibility of a parachuteless parachute jump? Or should we wear parachutes on every flight?

If the airplane designers can't come up with a fool proof door and fastenings, we'll be glad to turn the problem over to a construction engineer or a construction equipment designer

Yours for planes that don't come apart in flight

H W. RICHARDSON, Editor
Construction Methods and Equipment
330 West 42nd St,
New York, N Y

'Weeping for Rails'


I have just read with a great deal of interest your editorial Feb 20, "Weeping for the Rails" It is a honey And you have certainly given the bus a nice pat on the back.

EARL F THEISINGER, Executive Editor
Bus Transportation
New York, N Y

The NEW NUTT-SHEL
FLOATING TYPE SELF-LOCKING NUT

Here it is!

30% WEIGHT SAVING
AN366F WIDTH
AN APPROVED



PATENTED AND PATENTS PENDING IN UNITED STATES GREAT BRITAIN AND CANADA

THE new "Nutt-Shel" Floating Plate Nut has the same dimensions as AN366F and AN362F Stationary Plate Nut.

Float approximately 1/32" from center in all directions.

This all metal plate nut is manufactured to comply with requirements of specifications AN-N-5 and AN-N-10 and may be used at temperatures up to 550° F. with high axial load.

Write for Descriptive Engineering Data.

NUTT-SHEL COMPANY
317 EAST SECOND ST. LOS ANGELES 12, CALIF.

ADVERTISERS IN THIS ISSUE

AVIATION WEEK—APRIL 24, 1950

Adel Precision Products Corp 26
Agency—The McCarty Company

Airborne Accessories Corp 9
Agency—Weber Thomson Associates

Auburn Spark Plug Co, Inc 4
Agency—Spitz & Webb Adv

Bristol Company, The 59
Agency—James Thomas Chirurg Co

Chase Aircraft Co, Inc 8

Cherry Rivet Company 53
Agency—Dana Jones Company

Curtiss Wright Corp., Propeller Div 31
Agency—Charles Dallas Reach Co., Inc

Darnell Corporation, Ltd 43
Agency—Rhea Advertising Service

Douglas Aircraft Co., Inc 40
Agency—J Walter Thompson Co

Edison, Inc. Thomas A 65
Agency—Schuyler Hopper Co., The

Edo Corporation 58
Agency—Davis Parsons, Inc

Electrical Engineering & Mfg. Corp 42
Agency—West Marquis, Inc

Esso Standard Oil Co 47
Agency—McCann Erickson, Inc.

Ex-Cell-O Corporation Second Cover
Agency—Holden Clifford & Flint, Inc

Fafnir Bearing Co., The 5
Agency—Horton Noyes Co

Fairchild Engine & Airplane Corp Third Cover
Agency—J M Hickerson, Inc.

Fenwal, Incorporated 41
Agency—James Thomas Chirurg Co

General Electric Company Fourth Cover
Agency—G M Basford Co

Gladden Company, The 28
Agency—Meldrum & Fewsmith, Inc

Goodrich Co., The B F 3
Agency—Batten, Barton, Durstine & Osborn, Inc

Greer Hydraulics Inc 45
Agency—Joseph S Vogel & Co

Grumman Aircraft Engineering Corp Front Cover
Agency—Charles W. Hoyt Co Inc

Gulf Oil Corporation 24
Agency—Young & Rubicam, Inc.

Hamilton Tailoring Co, The 65
Agency—L. F McCarthy Co

Hartman Electrical Mfg Co, The 29
Agency—Palm & Patterson, Inc.

Hufford Machine Works, Inc. 50
Agency—Dozier-Graham-Eastman, Adv.

International Nickel Co., Inc, The 20
Agency—Marschalk & Pratt Co

Lewis Engineering Co., The 61

Lord Manufacturing Company 44
Agency—W S Hill Company

Marman Products Co, Inc 32
Agency—West-Marquis, Inc

Marquette Metals Products Co., The 37
Agency—Baldeo & Hickox Adv

Martin Co., The Glenn L 34, 35
Agency—Vansant, Dugdale & Co., Inc.

National Aeronautical Corp 61
Agency—J Brauch Briggs Adv

Nutt-Shel Company 64
Agency—Paul Silver Adv

Radio Corp of America 58
Agency—J Walter Thompson Co

Reid Bank Div of Bendix Aviation Corp 33
Agency—MacManus, John & Adams, Inc

Roe Canada Ltd., A. V 48
Agency—Cockfield, Brown & Co, Ltd

Searchlight Section 62, 63

Skinner Purifier Div of Bendix Aviation Corp 27
Agency—MacManus, John & Adams, Inc.

SMS Instrument Sales & Service, Inc 58

Socony-Vacuum Oil Co, Inc. 19
Agency—Compton Advertising Inc

Standard Pressed Steel Co 25
Agency—R E Lovekin Corp

Stewart Warner Corporation 22
Agency—MacFarland, Aveyard & Co

Thermo Electric Company 60
Agency Fred Lange Associates Inc

Thompson Company, The H I 30
Agency—McKee-Burns & McKee Adv

Tinnerman Products, Inc 38
Agency—Meldrum & Fewsmith, Inc

Torrington Company, The 10
Agency—Hazard Advertising Co.

Transcontinental & Western Airlines 61
Agency—Batten, Barton, Durstine & Osborn, Inc.

United States Steel Supply Co 60
Agency—Batten, Barton, Durstine & Osborn, Inc.

Van Dusen Aircraft Supplies 55
Agency—Davis-Parsons, Inc.

Weber Showcase & Fixture Co., Inc 39
Agency—Harrington Richards Adv

Wyman Gordon Company 6
Agency—John W Odlin Co, Inc

■

PROFESSIONAL SERVICES—
First issue of each month

■

SEARCHLIGHT SECTION
(Classified Advertising)


EMPLOYMENT
Positions Vacant 62
Positions Wanted 62
EDUCATIONAL
Schools 62
PLANES—EQUIPMENT
(Used or Surplus New)
For Sale 62-63
WANTED
Planes-Equipment 62

why are EDISON AN-5525 thermometer bulbs better?



provide faster response

permit higher operating temperatures than required by AN specs



Patented silver spring design permits faster heat transmission to sensitive windings and quicker response than required by AN specs. Springs also cushion against shock

All-mica insulation plus mechanical metal-to-ceramic seal in bulb header permits higher operating temperatures than required by AN specs—up to 600° F.

Available in standard AN 5525-1, -2, and new USAF reinforced type G-1 Write today for new descriptive bulletin and prices on AN and other Edison Resistance Bulbs.

220 Lakeside Avenue West Orange, N. J.



INSTRUMENT DIVISION
THOMAS A. EDISON, INCORPORATED



Hamilton
World's Largest Airline Tailors
OFFICIAL AIRLINE UNIFORMS
For Men and Women

Hamilton Airline Uniforms are custom tailored to individual measure to Airline specifications.

Hamilton Tailors are the accredited suppliers for

AMERICAN AIRLINES
CAPITAL AIRLINES
CHICAGO & SOUTHERN AIRLINES
DELTA AIRLINES
EMPIRE AIRLINES
EASTERN AIRLINES
MID-CONTINENT AIRLINES
NORTHWEST AIRLINES
PHILIPPINE AIRLINES
PIEDMONT AIRLINES
TRANS WORLD AIRLINES
UNITED AIRLINES
and others

"If it's Hamilton-tailored you know it's right"

THE Hamilton TAILORING CO
Columbia Parkway at Pike • Cincinnati 2, Ohio

EDITORIAL

20 YEARS—NO CRASHES!

This is probably the only time you have ever seen a full page, 60-point heavy black banner headline screaming a story about all the airline passengers who have NOT been hurt or killed

Ever since aviation's earliest days, we have seen the stories about its heart-breaking accidents headlined across the front pages of the country's newspapers

So we thought you old timers and the air transport industry would like to see how a big, black streamer headline about NO ACCIDENTS really looks. If ever we had adequate inspiration, it is completion by Colonial Air Lines last week of 20 years' operation without a fatality or serious injury to passenger or crew member

That is a remarkable achievement. It deserves a banner headline and special editorial recognition.

We agree with Colonial Vice President Alfred M. Hudson, that "Accidents will always make bigger news than safety records, but Colonial's record is really newsworthy."

In this 20-year period, Colonial estimates it has flown 310,276,067 passenger miles. That is equivalent to moving nearly the entire population of Montreal—about a million persons—to New York City. Colonial says in these twenty perfect years it has completed 455,000 landings and take-offs and carried more than 1,204,800 passengers safely over its route system, which now comprises 3182 miles

Congratulations came from the National Safety Council, the Air Line Pilots Assn. president, Dave Behncke, New York's Governor Dewey, and from airline executives

"This achievement has been made possible because of the progressive thinking of everyone in the company," President Sigmund Janas said. "It is a record unequaled in air transportation anywhere else in the world. We will continue to take an intensive interest in the progress of the art of flying but we cannot lose sight of the fundamental consideration in all transportation and that is the safety of the passenger himself. No airplane should be permitted in commercial aviation which has not been thoroughly tested in advance and it is my sincere hope that the maintenance procedures laid down here in the United States for our transport companies will be adopted throughout the world."

Mr. Janas urged "prudence and judgment" before putting revolutionary types of transports into service. He recommended that no plane be permitted to engage in commercial airline passenger service before it has flown at least 3000 hours carrying freight or in other non-passenger operations.

Meanwhile, a phrase Mr. Janas coined in the 30s, "Safety is no accident," was adopted again for the second twenty years, and Mr. Janas commended all Colonial employes—especially flight crews, dispatchers, meteorologists,, mechanics and communications staffs. He said he hoped Colonial's safety record would serve to focus the eyes of the traveling public on the excellent records of all U. S. certificated airlines, both domestic and trans-ocean, which collectively made 1949 the safest year in the history of air travel

Colonial's impressive record is important news in aviation

Blueprint for

Air Transportability



THE NEW Fairchild Packet exemplifies the continuous teamwork between the U. S. Air Forces, Air Materiel Command and the aircraft industry. As always, Air Materiel Command aeronautical experts worked closely with Fairchild designers and engineers to develop the Packet—now setting new military standards for efficient movement of cargo and personnel.

Air Force requirements called for a practical cargo and personnel carrier, versatile enough in design and operation to make it efficient for a variety of missions. The C-119, expertly tailored to fit these requirements . . . carries cargo and personnel, tanks, guns and vehicles, ammunition, rations, fuel and countless other bulk items. The Packet is also ideally suited to drop paratroopers and evacuate wounded.

An advanced version of the famed Fairchild C-82, the new, larger and faster C-119 is the result of imagination and engineering skill and production ability.

The Air Force and Navy will use these aircraft for numerous transport assignments. C-119's will play a vital role in the ever-expanding field of military air operations. Here is another Fairchild "first" in air transportability!

Teamed for Defense
Armed Forces Day
20 May 1950

ENGINE AND AIRPLANE CORPORATION
FAIRCHILD *Aircraft Division*
HAGERSTOWN, MARYLAND

Ideas For Sale

Joe Thompson, Charlie Byrum, and Charlie Young produce one of G-E's greatest "stocks-in-trade"—ideas. One of many problem-solving squads whose successes read like an aviation roll call of progress—electrically-driven autopilots; a high-frequency ignition system; airborne radar; all-electric remote fire control systems—they have new ideas and approaches that may be what you're looking for in your business.

Working closely together, and with other specialists from G-E's pool of knowledge, they have sparked many advances over the last decade. Experts at analysis, they form a hard-driving team which utilizes their widely-varied backgrounds. The vigor of their youth is backed up by G-E's generations of experience.



- TURBO-JET ENGINES
- TURBOSUPERCHARGERS
- MOTORS AND CONTROL
- INSTRUMENTS
- IGNITION AND POWER SYSTEMS
- ACTUATORS
- GENERATORS AND TRANSFORMERS

These men, and others like them at General Electric, offer the aviation industry an integrated service of research, development, engineering, and production. If you have a problem concerning aircraft propulsion or electrical systems, call on General Electric. Telephone your nearest G-E sales office or write Apparatus Department, General Electric Co., Schenectady, N. Y.

You can put your confidence in—

GENERAL ELECTRIC

210-7